

ENGINEERING COMMITTEE MEETING Minutes November 7, 2019

Covering Design, Construction, Capital Improvement, Master Plan and other Engineering, Operational and Planning Related Matters

<u>NOTICE IS HEREBY GIVEN</u> that the San Lorenzo Valley Water District has called a meeting of the Engineering Committee to be held <u>Thursday, November 7, 2019 at 2:00 pm</u> at 13057 Highway 9, Boulder Creek, CA.

AGENDA

- 1. Convene Meeting/Roll Call
- 2. Oral Communications

This portion of the agenda is reserved for Oral Communications by the public for items which are not on the Agenda. Please understand that California law (The Brown Act) limits what the Board can do regarding issues raised during Oral Communication. No action or discussion may occur on issues outside of those already listed on today's agenda. Any person may address the Committee at this time, on any subject that lies within the jurisdiction of this committee. Normally, presentations must not exceed five (5) minutes in length, and individuals may only speak once during Oral Communications. Any Director may request that the matter be placed on a future agenda or staff may be directed to provide a brief response.

3. Old Business: None

Members of the public will be given the opportunity to address each scheduled item prior to Committee action. The Chairperson of the Committee may establish a time limit for members of the public to address the Committee on agendized items.

4. New Business:

Members of the public will be given the opportunity to address each scheduled item prior to Committee action. The Chairperson of the Committee may establish a time limit for members of the public to address the Committee on agendized items.

- A. LOMPICO TANKS PROJECT- CONSTRUCTION ENGINEERING SERVICES REQUEST FOR PROPOSALS.
 Discussion and possible action by the Committee regarding a RFP for Construction Engineering Services on the Lompico Tanks Project.
- B. LYON SLIDE PROJECT
 Discussion and possible action by the Committee regarding the Lyon Slide Project.
- 5. Adjournment

In compliance with the requirements of Title II of the American Disabilities Act of 1990, the San Lorenzo Valley Water District requires that any person in need of any type of special equipment, assistance or accommodation(s) in order to communicate at the District's Public Meeting can contact the District Office at (831) 338-2153 a minimum of 72 hours prior to the scheduled meeting. Agenda documents, including materials related to an item on this agenda submitted to the Committee after distribution of the agenda packet, are available for public inspection and may be reviewed at the office of the District Secretary, 13060 Highway 9, Boulder Creek, CA 95006 during normal business hours. Such documents may also be available on the District website at <u>www.slvwd.com</u> subject to staff's ability to post the documents before the meeting.

Certification of Posting

I hereby certify that on October 31, 2019, I posted a copy of the foregoing agenda in the outside display case at the District Office, 13060 Highway 9, Boulder Creek, California, said time being at least 72 hours in advance of the meeting of the Engineering Committee of the San Lorenzo Valley Water District in compliance with California Government Code Section 54956.

Executed at Boulder Creek, California, on October 31, 2019.

Holly B. Hossack, District Secretary San Lorenzo Valley Water District

MEMO

То:	Engineering Committee
From:	Engineering Manger
Subject:	Discussion and possible action related to a RFP for Construction Engineering Services for the Lompico Tanks Project
Date:	November 7, 2019

Background

Earlier this year, the District awarded the design contract for the Lompico Tanks to Schaff & Wheeler Consulting Civil Engineers. The Project involves replacing existing redwood tanks at the Madrone, Kaski and Lewis sites with six new steel tanks. The construction documents, including the environmental documents, are scheduled to be complete by early December. Staff plans to bid the project for construction starting in January of 2020.

For large construction projects, Engineering staff recommend hiring an outside engineering firm to provide daily construction management. Attached is a draft RFP for engineering services during construction for the Committee's review and comment. Staff propose to circulate the RFP in early January at the same time the Lompico Tanks are being bid. Staff will bring both the Lompico Tank bids and the proposals for engineering services during construction to the Committee for consideration prior to approval by the Board of Directors.

Recommendation:

That the Engineering Committee approve the draft RFP for engineering services during construction for circulation.



REQUEST FOR PROPOSAL

TO PROVIDE:

PROFESSIONAL CONSTRUCTION MANAGEMENT SERVICES TO THE SAN LORNZO VALLEY WATER DISTRICT

PROJECT TITLE:

Lompico Tanks Project

RESPONSE DUE BEFORE 3:00 P.M.

ON

DECEMBER ____, 2019

San Lorenzo Valley Water District 13060 Highway 9 Boulder Creek, CA 95006 (831) 338-2153

I. INTRODUCTION

The San Lorenzo Valley Water District proposes to replace several redwood water storage tanks in the Lompico Area of the District with modern steel water storage tanks. Existing tanks at the Kaski, Madrone and Lewis sites will be affected. Improvements at the Kaski Tank site will include two (2) 60,000-gallon steel tanks, improvements at the Madrone Tank site will include two (2) 60,000-gallon steel tanks, and improvements at the Lewis Tank site will include two (2) 110,000-gallon steel tanks. The Lompico Tanks Project generally involves:

- 1. Installation of temporary tanks;
- 2. Demolition of old tanks, buildings and piping;
- 3. Site grading, the installation of storm drains and site electrical;
- 4. Installation of new steel tanks, mixers, etc.

Plans and specifications for the Project have been prepared by the engineering firm Schaaf & Wheeler. These documents are available for review on the District web site. CEQA has been completed for the project. An Initial Study - Mitigated Negative Declaration and a Mitigation Monitoring and Reporting Program have been prepared and incorporated into the plans and specifications. The estimated construction cost is ______ and there are ______ working days in the construction contract. The District intends to award a single construction management contract to a consultant firm qualified to do complete construction management for this project.

II. GENERAL INFORMATION

San Lorenzo Valley Water District is a water supplier established in 1941 and serves several communities within the 136 square-mile San Lorenzo River watershed. The District owns, operates, and maintains two permitted water systems. Each service area provides supplies from separate water sources. The North/South Service Area includes the unincorporated communities of Boulder Creek, Brookdale, Ben Lomond, Manana Woods, Scotts Valley and Lompico. The Felton Service Area was acquired by the District from California American Water in September 2008 and includes the town of Felton and adjacent unincorporated areas.

The District's legal boundaries encompass approximately 62 square miles. Land uses include timber, State and regional parks, water supply watersheds, rural residential, low-density urban residential, commercial, quarries, agriculture, and other open space. Within these boundaries, the District's two service areas have a combined area of approximately 29 square miles, made up of the North Service Area (26.7 square miles) and the Felton Service Area (2.2 square miles).

The District relies on both surface water and groundwater resources, including nine currently active stream diversions, one groundwater spring, and eight active groundwater wells. These sources are derived solely from rainfall within the San Lorenzo River watershed.

The scale and complexity of SLVWD's water distribution system reflect the San Lorenzo Valley's rugged topography, dispersed pattern of development, and widely distributed raw water sources. The District's three systems have limited above-ground storage capacity equal to a few days' average use and rely on groundwater for seasonal and year-to-year storage. The District produces and treats water based on relatively immediate water demand.

III. PROJECT SCOPE OF SERVICES

The Consultant shall provide overall project management. The Consultant shall assume at least one meeting each month with District management staff during the construction portion of the project and additional meetings to review project status at key milestones. Meetings will be held at the District's main office.

The Consultant shall provide internal quality control and quality assurance procedures.

A. Construction Management Services

- Issue necessary clarifications and interpretations of the contract documents as appropriate to the orderly completion of contractor's work. Such clarifications and interpretations will be consistent with the intent of and reasonably inferable from the contract documents.
- 2. Coordinate the submittal and shop drawing process by transmitting to the appropriate design professional for compliance with construction documents. Develop and maintain files of approved submittals and shop drawings.
- 3. Establish and hold weekly progress and coordination meetings with SLVWD and the Contractor at the site during active on-site construction phase. Prepare the agenda and summary notes for weekly meetings and review the Contractor's schedule. Monitor Contractor's compliance with submitted schedule. Request new schedules as they become outdated due to changes. Summarize project progress and include the status of change orders, of contract days remaining, work completed, adherence to schedule, and work in progress.
- 4. Visit the site each working day during the active on-site construction phase as necessary to observe the work and document compliance with the plans and specifications. Confirm that materials and installation methods used are those specified in approved submittals or the contract documents. Photographically document the progress of the work daily. Review traffic control. Prepare daily site observation logs that document progress of work performed, labor and equipment on site, and communications with the Contractor.
- 5. Review Contractor's progress payment requests and provide recommendations regarding payment in accordance with the work complete and the contract documents.

- 6. Assist with Contractor coordination with the utility companies, PG&E, Comcast, AT&T, Verizon, Sprint, etc.
- 7. If a change order request is presented by the Contractor, Consultant shall review the request, communicate with SLVWD, the Contractor, and any involved inspection/testing sub-consultants, and provide a recommendation to the District. Consultant shall maintain current records and documentation for all change orders, along with changes in contract days and contract dollar amount.
- 8. Review test reports and notify the District and the Contractor regarding reports indicating non-conforming items. Coordinate with the Contractor and the special testing and inspection sub-consultants, to resolve variations in the work from that specified in the construction documents.
- 9. Prepare a final punch list of items not yet satisfactorily completed and visit the project site to verify completion of those items.
- 10. Obtain letters of final acceptance from the associated design professionals summarizing their observations and conformance with the project plans and specifications.
- 11. Obtain record drawings from the associated design professionals based on Contractor 's as-built drawings, site observation logs, and RFI logs for District records.
- 12. Review construction for adherence with the project plans and specifications.

B. Construction Management - Subconsultants

- 1. Assemble, coordinate and manage a team of sub-consultants responsible for the completion of specialized tasks including, but not limited to, the following:
 - a) Construction surveying,
 - b) Environmental compliance inspections and documentation,
 - c) Geotechnical inspections, documentation and density testing,
 - d) Tank coating, lining, bolting and/or welding inspections,
 - e) Concrete, reinforcement and/or asphalt testing/inspection,
 - f) Electrical/SCADA inspections,
 - g) Labor compliance monitoring,

IV. PROPOSAL REQUIREMENTS

The Proposal shall not exceed 20, 8.5" x 11" single-sided pages excluding resumes, cover letter, contractual scope of services, fee schedules, dividers, front and back covers. 11" x 17" pages are allowed and will count as two pages. The Proposal must use a font size of 11 or larger and be bound into a single document with the exception of the separately bound fee table. The Responses to this RFP shall be in the following order and shall include:

1. <u>Cover Letter (2 page maximum):</u>

Include a dated cover letter indicating the firms understanding of and interest in the project and summarizing the key components addressed within the Proposal. This document shall be legally binding by a person authorized to represent the firm. Please include name, address, telephone number, email and title for each of these persons.

2. <u>Project Description and Approach (8 page maximum)</u>

- i. Explain the objective of the project, as you understand them, and how you propose to accomplish the recognized goals.
- ii. Describe, in the important aspects of the approach that your firm will take for the services and deliverables to be provided.
- 3. Identification of Prime Consultant (1 page maximum)
 - i. Legal name and address of the company.
 - ii. Legal form of company (partnership, corporation).
 - iii. If company is wholly owned subsidiary of a "parent company," identify the "parent company."
 - iv. Name, title, address and telephone number of person to contact concerning the Response Submittal.
 - v. Project team and the discipline/job title of each team member.
 - vi. Provide a general description of your firm's background and project qualifications, including years of business, any past bankruptcy filings, and identify any contract or subcontract by the firm which has been terminated, in default, or had claims made against it that resulted in litigation or arbitration in the last five years.

4. Identification of Sub Consultants, if any (1 page per sub-consultant maximum)

- i. Legal name and address of the company.
- ii. Name, title, address and telephone number of prime contact.
- iii. Number of staff and the discipline/job title of each.
- iv. Provide a general description of subcontractor's background and project. qualifications, including years of business, any past bankruptcy filings, and identify any contract or subcontract by the firm which has been terminated, in default, or

had claims made against it that resulted in litigation or arbitration in the last five years.

- 5. <u>Project Organization and Experience of the Project Team (3 page maximum, not including</u> <u>resumes)</u>
 - i. Describe proposed project organization, including identification and responsibilities of key personnel, including sub-consultants. Include only one-page resumes.
 - ii. Describe the experience of the Project Manager and the experience that the proposed personnel have working on past projects as a team.
 - iii. Describe project management approach to the work effort, locations where work will be done, responsibilities for coordination with the District, lines of communication necessary to maintain design on schedule.
 - iv. Describe the firm's capacity to perform the work within the time limitations, considering the firm's current and planned workload and the firm's current and planned work force.
 - v. Include a statement on what makes your firm uniquely qualified.

6. <u>Experience and Past Performance, Including Cost and Schedule Control (4 page max / 3 projects max)</u>

- i. Include a summary of the past experience and performance of the Engineer of Record on similar projects. Include the following information:
 - 1. Owner, contact name and phone number
 - 2. Project size and description
 - 3. Project budget and total dollar value of completed project
 - 4. Budgeted project schedule and total time to completion
 - 5. Estimated construction costs and actual construction costs
- ii. Describe the firm's past experience and performance on similar projects. Include the information listed above.

7. Exceptions to this RFP

The Consultant shall certify that it has fully read the RFP and if the Consultant does take exception(s) to any portion of the RFP, the specific portion of the RFP to which exception is taken shall be identified and explained.

8. <u>Contractual Scope of Services</u>

- i. The Consultant shall provide a detailed scope of services to be provided. This should be responsive to the requested scope of services with additional detail as necessary.
- ii. Prepare a detailed schedule based on the allowable construction contract working days

showing all facets of work that will meet the District's objectives and goals in a timely manner.

iii. Both the Scope and Schedule are anticipated to become attachments to the Contract between the Consultant and the District.

9. Insurance

- i. Without limiting Contractor's indemnification of District, and prior to commencing any Services required under this Agreement, Consultant shall purchase and maintain in full force and effect, at its sole cost and expense, the following insurance policies with at least the indicated coverages, provisions and endorsements:
- ii. Commercial General Liability Policy (bodily injury and property damage): Policy limits are subject to review, but shall in no event be less than, the following:
 - 1. \$1,000,000 Each Occurrence
 - 2. \$1,000,000 General Aggregate
 - 3. \$1,000,000 Products/Completed Operations Aggregate
 - 4. \$1,000,000 Personal Injury
 - 5. Workers' Compensation Insurance Policy as required by statute and employer's liability with limits of at least one million dollars (\$1,000,000) policy limit Bodily Injury by disease, one million dollars (\$1,000,000) each accident/Bodily Injury and one million dollars (\$1,000,000) each employee Bodily Injury by disease.
 - 6. Comprehensive Business Automobile Liability Insurance Policy with policy limits at minimum limit of not less than one million dollars (\$1,000,000) each accident using. Liability coverage shall apply to all owned, non-owned and hired autos.
 - 7. Professional Liability or Errors and Omissions Insurance as appropriate shall be written on a policy form coverage specifically designed to protect against acts, errors or omissions of Consultant. Coverage shall be in an amount of not less than one million dollars (\$1,000,000) per claim/aggregate.
- iii. Prior to commencement of any services under this Agreement, Consultant, shall, at its sole cost and expense, purchase and maintain not less than the minimum insurance coverage with endorsements and deductibles indicated in this Agreement.
- iv. The Consultant and its subconsultants are required to name the State, its officers, agents and employees as additional insured on their liability insurance for activities undertaken pursuant to this Agreement.
- v. Consultant shall file with District all certificates for required insurance policies for

District's approval as to adequacy of insurance protection. The District will require a professional liability insurance verification for coverage of not less than \$1,000,000.00.

10. Total Professional Fee and Fee Schedules

- i. Proposed fee shall be organized with appropriate breakdown into subtasks.
- ii. Proposed fee shall include the hourly rates of all staff (including subconsultants) that will charge directly to the project for project duration.

V. CONSULTANT SELECTION

The District will review and evaluate each submittal to determine if it meets the requirements for the service described herein. Failure to meet the requirements of this RFP will be cause for eliminating the applicant from further consideration. Based on the District's evaluation, the firms that meet the requirements of this RFP will be ranked. The following weighted criteria will be used to evaluate the Proposals provided in response to this request:

- a. 30% Understanding and approach to the work to be done
- b. 20% Experience of firm with similar types of work
- c. 30% Experience of staff with similar kinds of work
- d. 10% Overall clarity and presentation of Proposal
- e. 10% Firm's Local Experience

VI. SELECTION PROCESS

It is anticipated that a contract/contracts will be awarded with the highest-ranking firm being selected. However, the District reserves the right to consider other factors such as overall cost and may award contracts to any qualified applicant, regardless of the assigned rank. The District will enter into negotiations with the selected firm. If the District can't negotiate an agreement that is fair and reasonable in the District's sole discretion, it reserves the right to select an alternate firm. At this time, the District contemplates the use of a <u>Time and Materials with a</u> <u>Not-to-Exceed Total type contract for the services requested</u>. Negotiations will cover: scope of work, contract terms and conditions, office arrangements, attendance requirements and the proposed fee schedule.

VII. SELECTION SCHEDULE

The District anticipates that the process for selection of firms and awarding of contracts will be according to the following tentative schedule:

Proposal Due Date	December,	2019
Presentations (TBD-If Necessary)	December,	2019
Board of Directors Approval	January, 20	19

VIII. SPECIAL CONDITIONS / ATTACHMENTS

The following documents are intended to provide additional background and are available on the District website:

- 1. Lompico Tanks Project Plans and Specifications
- 2. Environmental documents

IX. DISTRICT CONTACT

Questions regarding this RFP should be submitted to the District's Engineer, Darren Langfield, via email at <u>dlangfield@slvwd.com</u> by **5pm on December** ____, **2019.**

X. SUBMITTAL REQUIREMENTS

- One (1) executed original marked "ORIGINAL" in red ink and three (3) copies of the proposal shall be submitted. Emailed proposals will not be accepted. <u>Submit one</u> <u>electronic copy of the proposal in PDF format (on CD, DVD or Thumb Drive)</u>. The proposal shall be signed by an individual, partner, officer or officers authorized to execute legal documents on behalf of the Firm.
- 2. Proposals must be received no later than **3:00 p.m. local time, on or before December** _____, **2019** at the office of:

San Lorenzo Valley Water District 13060 Highway 9 Boulder Creek, CA 95006

Attn: District Engineer (Construction Management – Lompico Tanks)

Failure to comply with the requirements of this RFP may result in disqualification.

MEMO

То:	Engineering Committee
From:	Engineering Manger
Subject:	Discussion and possible action related to the Lyon Slide Project
Date:	November 7, 2019

Background


The Lyon Slide occurred in January, 2017, and affects 160' of the access road to the Lyon Tank and the Lyon Treatment Plant as well as non-District properties below the slide. The District applied for FEMA assistance and has commissioned two studies with the soil engineering firm Haro Kasunich Assoc. (HKA) to evaluate the slide and determine repair options. The repair options and costs recently obtained from the second HKA report are summarized below:

- Install three rows of secant piles across the face of the slide and remove approximately five feet of the upper slide mass to reduce the weight of the slide. The secant pile range from 40 -55 feet deep. The estimated cost of this option is \$15 million.
- Install two rows of secant piles across the face of the slide; install an eightfoot diameter 250-foot-long culvert in Hessey Creek; remove approximately five feet of the upper slide mass to reduce the weight of the slide; place and compact excavated spoil over pipe. The estimated cost of this option is \$12 million.

Due to the large cost of repairs, staff thought it wise to consult with the Engineering Committee about the nest step in the process.

Timing

Upon receipt of the second study, staff applied for a one-year extension of time from FEMA. FEMA recently granted the time extension.



Project No. SC4090.1 6 August 2018

SAN LORENZO VALLEY WATER DISTRICT 13060 Highway 9 Boulder Creek, California 95006

Attention: Mr. Rick Rogers

Subject: Geotechnical Investigation

Reference: Lyon Tank Access Road Landslide Repair 365 Madrone Drive Boulder Creek, California

Dear Mr. Rogers:

In accordance with the request of the San Lorenzo Valley Water District (SLVWD), Haro, Kasunich and Associates, Inc. (HKA) have performed a Geotechnical Investigation for the repair of the access road that services the Lyon Tank in Boulder Creek, California.

The accompanying report presents our conclusions and recommendations, as well as the results of the geotechnical investigation on which they are based. A broad soil mass disconnected from the hillside during the winter rain season of 2016/2017 and mobilized downslope leaving a large head scarp that undermined a portion of the access road including Madrone Road. The access road that services the subject water tank crosses over the soil mass in several locations. Portions of the road mobilized along with the soil mass in some locations and in other locations the road was completely buried.

The San Lorenzo Valley Water District (SLVWD) has requested that HKA develop an understanding of the unstable broad soil mass and present geotechnical recommendations for stabilization and reconstruction of the damaged portions of the access road. To better understand the geologic and geotechnical parameters of the project site, HKA completed a field exploration program that included, site reconnaissance, 16 test borings drilled to depths of 7.0 and 51.5 feet below the ground surface (bgs), and laboratory testing for mechanical properties of soil samples collected from within the test borings. The study area was topographically mapped several times by Professional Land Surveyor Paul Jensen. The soil mass continued to mobilize between surveys with most recent map dated February 2018.

Geologic sections were developed using the topographical map along with data collected during the field exploration. A worst case slope stability model of the hillside was created in cross section view by assigning mechanical properties (strength,

density, moisture) to the soils layers in the geologic section. The slope stability analysis was completed with the aid of the computer software program SLOPE/W by GEOSLOPE. A double check of the inputs for the model was completed by back calculating the landslide that already occurred under wet winter conditions without the influence of seismic shaking.

The preliminary results of the analysis were presented to the representatives of the SLVWD. In brief a broad soil mass has disconnected from the hillside from the head scarp down to Hessey Creek. The disconnected soil mass is unstable under wet winter conditions without seismic shaking and will continue to reactivate overtime and creep downslope. Although the entire disconnected soil mass could be stabilized, it would be more practical to stabilize just the soil mass starting from the outboard side of Madrone Road upslope to the head scarp.

HKA recommends unloading the soil mass by removing the upper 5 (+/-) feet of soil starting just below Madrone Road up to the head scarp. The soil mass from Madrone Road up to the head scarp should be stabilized using two rows of buried secant piles. The lower row of secant piles would be constructed along the outboard side of Madrone Road and is estimated to be 200 feet long by as much as 55 feet deep. The upper row of secant piles is recommended to be constructed on the hillside approximately half way up to the head scarp from Madrone Road. The upper row is estimated to be 150 feet long by as much as 40 feet deep. To rebuild and secure the severely damaged portion of the upper access road where the soil mass dislodged from the head scarp an engineered fill slope is recommended to be constructed from the upper row of secant piles up to the inboard side of the damaged upper road.

HKA re-iterates that the disconnected soil mass downslope from Madrone Road is unstable and the recommended rows of secant piles presented in this report will not stabilize this portion of the hillside. Furthermore, any surcharge placed upon the soil mass downslope from Madrone Road may exacerbate instability. If SLVWD would like to eliminate re-activation of the disconnected soil mass below Madrone Road please communicate this objective with HKA. We anticipate a temporary road will need to be constructed to install the upper row of secant piles on the hillside. Additional working meetings with structural and civil designers, specialty contractors, and SLVWD are anticipated, in order to develop viable working drawings.

If you have any questions concerning the data or conclusions presented in this report, please call our office.

Respectfully Submitted,

HARO, KASUNICH AND ASSOCIATES, INC.

Kourosh Younesi Senior Engineer Moses Cuprill C.E. 78904

KY/MC/sr Copies:

1 pdf to Rick Rogers rrogers@slvwd.com

4 to Addressee

TABLE OF CONTENTS

GEOTECHNICAL INVESTIGATION	1
1. Introduction	1
2. Purpose and Scope	7
3. Field Exploration and Laboratory Testing	7
3.1. Field Exploration	
3.2. Laboratory Testing	10
4. Site Characterization	
4.1. Soil Layers Description	11
4.2. Groundwater	13
4.3. Soil Properties	14
5. Geotechnical Related Seismicity	
6. Quantitative Slope Stability Analysis	
6.1. General Methodology	
6.2. Quantitative Analysis with GEO-SLOPE 2018	
6.3. Seismic Coefficient	
6.4. Geometric Assumptions	
6.5. Slope Stability Models for Studied Site	
6.6. Slope Stability Conclusions	
6.7. Limitations of Analysis	
7. Building Codes and Site Class	
8. Recommendations for Design and Construction	
1. Site Grading (Fill/Cut Slopes)	39
18. Secant Pile Walls	
27. Drilled Piles for the Secant Pile Wall	
35. Active and Passive Pressures	
38. Driven Piles	
43. Surface & Subsurface Drainage	
46. Monitoring	
47. Plan Review, Construction Observation and Testing	
LIMITATIONS AND UNIFORMITY OF CONDITIONS	53
APPENDIX A	
Site Vicinity Map	Figure 1
Geological Site Map	
Boring Site Plan	
Key to Logs	
Logs of Test Borings	Figures 5 - 26
Particle Size Distribution Test Results	
Plasticity Index	
Direct Shear Results	
Variation of SPT Blows, Saturation Degree and Void Ratio Versus Depth	
variation of SFT blows, Saturation begree and volu Natio versus bepti	ii igules 40 – 55
APPENDIX B	
Lyon Tank Slide 3D Orthographical Model	Figures 54 - 58
APPENDIX C	
-	Figures 50 74
Summary Results of Stability Analysis	. Figures 59 -/1
APPENDIX D	
Some Photos From The Project Site	

GEOTECHNICAL INVESTIGATION

1. Introduction

This report presents the findings, conclusions and recommendations of our Geotechnical Investigation for the Lyon Tank Access Road Landslide Repair Project. The Tank site is located at the end of Madrone Drive in Boulder Creek, California (see Site Vicinity Map, Figure 1 in Appendix A). A broad soil mass disconnected from the hillside and mobilized downslope. We will refer to the disconnected soil mass as the "landslide" from here forward. The slow moving landslide, which initially activated in the winter of 2017, has resulted in significant damage to the only access road to the SLVWD Lyon Water Tank and Water Treatment Facility. The water tank is the main water supply for residents within the San Lorenzo Valley Water district. The landslide is located between the upper most road that provides access to the base of the Lyon Tank which we will refer to as the "upper road" (that traverses the head scarp) and Hessey Creek, located about 200 feet downslope and to the east. A 160 foot long portion of Madrone Road which we will refer to as the "lower road" crosses the active landslide deposit and has been damaged. This report presents the results of our field investigations, laboratory testing, static and seismic slope stability analysis, and development of geotechnical design criteria and recommendations for stabilization of a select but imperative portion of the landslide.

Survey Maps with cross sections of the landslide area were prepared by Paul Jensen, and provided for our use. The landslide maps, with cross sections, are

dated February 2017, June 2017, October 2017, and February 2018. The landslide area was surveyed four times to assist in evaluating the movement of the active landslide and to define potential toe of slip surfaces. The locations of exploratory borings indicated on the maps were surveyed by Mr. Jensen. The ground surface elevations at each boring location on the landslide deposit vary depending on the map date due to the ongoing movement of the landslide.

The Lyon Tank lower road crosses the landslide site immediately before a hairpin turn up to the tank. Just beyond the hairpin turn, the road forks. The lower fork of the road or the "upper road" leading to the tank has been damaged and is unusable due to landsliding. Before the hairpin, a 160 foot length of the lower road has been damaged by landsliding and temporarily repaired. The initial movement of the landslide was first observed by Haro Kasunich and Associates, Inc. (HKA) on 13 February 2017 during an on-site meeting with SLVWD Operations Management staff. We were informed ground and asphalt cracks were first observed in January 2017 after heavy rainfall at the site. At the time of our 13 February visit, the west lateral edge of the landslide and access road had dropped 2" to 4" and a 2' to 3' wide asphalt patch had been placed and compacted from the north to south side of the road to bridge the damaged area. The patch covered over a zone of 1" to 2" wide cracks in the asphalt. Soil cracks with a few inches of vertical displacement extended up the slope toward the upper access road. A 15 inch diameter culvert on the surface of the slope below the access road on the west side of the slide was observed to be discharging water and angular gravel. The gravel was part of a gravel blanket drain installed during grading for construction of the access road to the Water Treatment Plant. The landslide movement dislodged and broke the pipe, allowing the gravel to flow into the culvert and then to be discharged out the end of the culvert.

In addition to the access road landslide, surficial sliding on the upper slope between the Lyon Tank and Water Treatment Plant was first observed by HKA on 13 February 2017. The slumps occurred about mid slope in several areas. On 15 February, the portion of the upper slope where slump slides occurred was covered with plastic sheeting and sandbags tied by rope to anchor the plastic and divert incident rainfall from the slope to the asphalt road below.

The access road landslide continued to move after heavy rainfall and by 22 February the east side of the upper access road down dropped several inches and numerous 1" to 2" wide cracks along a 50 foot long portion of the road had developed as the slide moved downslope. By Sunday 26 February, the landslide moved significantly and a 70' long portion of the road collapsed at the top of the landslide. The landslide left a 1' to 5' high head scarp at the inboard side of the lower of the upper roads. The west end of the access road dropped about 4 feet and subsurface water was emanating from the landslide scarp at the access road. Buckling of the pavement was observed on the downslope portion of the access road crossing the landslide. In early March, the entire landslide surface from the access road to the slide head scarp and side scarps was covered with plastic sheeting and rope tied sandbags to prevent incident rainfall from infiltrating into the covered part of the landslide deposit.

Several large trees on the landslide deposit were observed to be leaning significantly and posed a danger to the field investigation. The district hired a tree service to remove the worst of the leaning trees, which were removed in March and/or April 2017. On the west side of the access road, which had dropped about 6 feet, the district built a temporary gravel fill slope to provide vehicle access to the Water Treatment Plant and Lyon Tank for workers who perform daily maintenance and monitoring duties required to continue supplying potable water to District customers.

The movement of the landslide continued until early May 2017 when our initial borings were drilled. The plastic sheeting had been removed prior to our drilling and the landslide was re-surveyed in May. At that time the west side and the upper portion of the landslide had dropped from 6' to 8' and a bulge had developed on the slope between the creek and the access road. The west side of the section of the access road crossing the landslide had dropped 6' to 7'. The east side of the access road on the landslide had buckled due to uplift pressure from the slide and the curb drain inlet on the inboard side of the road was damaged by the landslide. The east side of the slide is buttressed by a previous road repair in 1986 which

replaced a failed wood crib wall. The repair consisted of removal of soil on the slope and in the stream channel, installation of a large culvert in the stream, and placement and compaction of rock and soil backfill on the slope and road.

After our initial borings, a path was cleared on the slope below the access road to provide access for a drill rig to advance an additional 4 borings on the landslide deposit below the access road and 1 boring on the landslide deposit above the access road. Adjacent to Boring B-10 on the slope between the access road and Hessey Creek, a constant flow of water seeping from the toe of a steep slope was observed.

A fourth survey of the site in October 2017 indicates the upper landslide headscarp had increased to 6' to 10' high and the landslide had moved up to 4 feet horizontally toward the creek since the first survey (which had been done after significant movement had already occurred).

New longitudinal cracks in the upper road to the Water Treatment Plant were reported by the district in late October 2017. The cracks on the upper Water Treatment Plant parking area were generally 1/32" to 1/16" wide. One asphalt crack was 1/2" wide. We returned to the site and drilled 4 supplemental borings in the Water Treatment Plant parking area to assess the subsurface conditions underlying the parking area and the slope descending to the Lyon Tank.

Based on geological review of published regional geologic maps of the area, we found a fault zone traverses through the project area. The historical presence of the fault zone in the area likely sheared and weakened the earth materials during geologic time and likely also disrupted groundwater flow. The landslide slip surface has extraordinarily weak earth materials along it with very low residual strengths; in part because of historical shearing during previous instability including the 2017 re-activation. The above factors complicate landslide repair because of difficulty in maintaining safety during any mass excavation of the landslide materials. The landslide mass is expected to continue to be unstable and may expand should nothing be done to mitigate the existing condition.

HKA performed field explorations (test borings); 1) to profile the subsurface earth materials; 2) obtain samples; and 3) perform a laboratory testing program. On September 15th, 2017, a memorandum was prepared by HKA including discussion about slope improvement feasibilities. In this report, we present results of the geotechnical analysis which is limited to the 2017 landslide. The proposed mitigation solution is to install two rows of secant piles, one along the outboard side of the lower road and another on the hillside midway upslope to the upper road. The two rows of piles should be advanced into bedrock a minimum of 15 feet. A temporary road will need to be graded to install the upper row of secant piles. The upper road is recommended to be re-contructed by grading an engineered fill slope with a slope gradient of 2H:1V with its toe at the upper row of secant piles and crest along the outboard board side of the upper road. To re-

construct the travel way of the upper road, the fill slope would continue at 2%-5% from its crest to the inboard cut slope along the upper road.

2. Purpose and Scope

Our scope of services included review of existing geotechnical and geologic information related to the site, drilling and sampling in sixteen (16) exploratory borings, laboratory testing, and engineering analysis. The key focus was evaluation of the unstable landslide mass using the projected failure mode geometry; and evaluation of a practical method to improve the slope. The purpose of these services is to provide information and geotechnical recommendations relative to:

- Subsurface soil conditions;
- Groundwater conditions;
- Seismic considerations;
- Relative stability of landslide deposits and in-situ earth materials within the slip-out area (under static loading conditions);
- Earthwork recommendations.

3. Field Exploration and Laboratory Testing

3.1. Field Exploration

The field investigation has been completed at site by drilling 16 boreholes over a period of approximately 6.5 months. Twelve boreholes were drilled at the 2017

landslide between the Lyon Tank and the existing creek at the base of the slope.

Boreholes 13 to 16 were drilled at the top of the slope south of the Lyon tank. B-1

to B-12 were drilled within the landslide area. The specifics of the drilled boreholes

are presented in Table 1.

BH No.	BH Drilling Date	BH	Approximate BH	Approximate BH
		Depth (ft)	Top Elevation (ft)	Bottom Elevation
		• • • •		(ft)
B-1	May 4, 2017	51.5	819.0	767.5
B-2	May 4, 2017	31.5	819.5	788.0
B-3	May 23, 2017	36.5	815.5	779.0
B-4	May 23, 2017	46.5	822.5	776.0
B-5	May 24, 2017	41.5	847.5	806.0
B-6	May 24, 2017	33.0	851.5	818.5
B-7	May 24, 2017	30.0	810.8	780.8
B-8	July 24, 2017	46.5	797.9	751.4
B-9	July 24, 2017	41.5	792.5	751.0
B-10	July 25, 2017	35.0	778.3	743.3
B-11	July 25, 2017	35.0	779.7	744.7
B-12	July 25, 2017	32.5	838.3	805.8
B-13	November 22, 2017	32.5	888.5	856.0
B-14	October 22, 2017	7.0	888.5	881.5
B-15	November 22, 2017	31.5	888.0	856.5
B-16	November 22, 2017	21.5	888.5	867.0

Table 1Drilled Boreholes Specification

Representative soil samples were obtained from the exploratory borings at selected depths, or at major strata changes. These samples were recovered using a 3.0 inch O.D. Modified California Sampler (L), or by a 2.0 inch O.D. Standard Terzaghi Sampler (T). The SPT blow counts with large sampler (NL) should be reduced by a specific reduction factor to convert to Standard SPT blow counts (NS). The correlation between these two values are presented below:

$$N_{\rm S} = N_{\rm L} \left[(WH)/(623N \cdot 0.762m) \right] \left[(50.8^2 - 34.9^2)/(D_{\rm o}^2 - D_{\rm i}^2) \right]$$
(Equation 1)

The penetration blow counts noted on the boring logs were obtained by driving a sampler into the soil with a 140-pound hammer dropping through a 30-inch fall. The sampler was driven up to 18 inches into the soil and the number of blows counted for each 6-inch penetration interval. The numbers indicated on the logs are the total number of blows that were recorded for the second and third 6-inch intervals, or the number of blows that were required to drive the penetration depth shown; when high resistance was encountered.

Given the hammer weight and the hammer drop height used for both samplers are the same, the difference of blow counts is because of outer and inner dimensions. For the Modified California Sampler with 3 inch (76.1mm) O.D. and 2.4 inch (61mm) I.D. the reduction factor of 0.65 will be used in our project to convert NL to Ns. In Figures 48 & 49, Appendix A, variation of field SPT blows versus depth in different boreholes are shown. In these graphs, the large sampler blow counts (NL) were converted to standard SPT blow counts (NS).

The soils encountered in the borings were continuously logged in the field and visually described in accordance with the Unified Soil Classification System (ASTM D2488). The Logs of Test Borings are included in Appendix A of this report. The logs depict subsurface conditions at the approximate locations shown on the Boring Site Plans; subsurface conditions at other locations may differ from those

encountered at the explored locations. Stratification lines shown on the logs represent the approximate boundaries between soil types; actual transitions may be gradual.

3.2. Laboratory Testing

The laboratory investigation was directed toward a quantitative and qualitative evaluation of the physical and mechanical properties of the subsurface materials at the project site.

Selected samples retrieved from the exploratory borings were returned to the laboratory for examination and testing to evaluate their physical characteristics and engineering properties. Below is a description of the series of tests performed in our laboratory on selected samples retrieved from the field investigation. These tests were performed in accordance with the standards of the American Society for Testing and Materials (ASTM) and contemporary geotechnical engineering practices. Samples were tested to measure moisture content and unit weight, plasticity, grain size distribution, and shear strength. The results of the laboratory tests are presented in Appendix A and as appropriate adjacent to the corresponding sample designations on the boring logs.

TEST	Standard Code		
Atterberg Limits	ASTM-D 4318		
Grain size	ASTM-D 421 , D 422		
Specific Gravity	ASTM-D 857		
Water Content	ASTM-D 226		
Classification	ASTM-D 2488		
Direct Shear	ASTM-D 3080		

Table 2List of Laboratory Tests

4. Site Characterization

4.1. Soil Layers Description

Based on site visits and observation of retrieved samples during drilling operations, the subsurface soils consist of loose to medium dense, moist to wet, brown to grey Silty SAND overlaid on the weathered bedrock. The bedrock consists of very dense light brown weathered Sandstone with orange stains. In boreholes B-1 to B-12, bedrock was encountered at different depths with a minimum at 27 ft within B-7 and at a maximum of 46 ft in B-4. This variation is likely a result of tectonic pressures that has changed the bedrock elevation, differential weathering, and the possibility of modification by landslide mass movement.

On portions of the existing slope, man-made grading (cut and fill) has changed the soil thicknesses. In some boreholes, the soils encountered suggest Silty Sand was historically used as fill during historical grading operations that created the old reservoir at the site and/or during grading for the Lyon Tank that was constructed

to replace the reservoir about 25 years ago. According to SPT blow counts, this loose to medium dense fill material is suspected to have been placed as uncompacted fill.

Based on our observations, some of the undocumented fill material is comprised of the native soils from the site making it difficult to distinguish between the two. Some boreholes were not located within the 2017 landslide area, including boreholes B-5 to B-7. The soil layers in B-1 to B-4 and B-8 to B-12 are within the landslide. The landslide mass found in these boreholes varied in thickness. The maximum 2017 landslide mass thickness observed in B-1 was 38 ft (±).

Based on the retrieved soil samples, there are areas where native soils exist above the bedrock that did not move as part of the 2017 landslide mass. These soils lie between the landslide mass and the bedrock. In Table 3, the Soil Layer Conditions after the 2017 Landslide are presented. We note, boreholes B-13 to B-16 were drilled outside of the landslide area. Therefore, the soil layer condition for these four boreholes are not described in Table 3. The landslide and native soil layers observed during drilling of the different boreholes is also presented graphically as a 3D landslide surface within the hillside. This is shown (named as Case 1) in figures 55 & 56 in Appendix B of this report.

	Soil Layers Encountered In The Boreholes After 2017 Landslide							
BH NO.	BH depth (ft)	BH top elevation (ft)	2017 Landslide mass thickness (ft)	Thickness of undisturbed native soil below landslide layer to bedrock (ft)	Bedrock depth (ft)	Bedrock elevation (ft)	Water Surface depth (ft)	Water Surface Elevation (ft)
B-1	51.5	819.0	38	7	45	774	-	-
B-2	31.5	819.5	22	8	30	789.5	-	-
B-3	36.5	815.5	25	6	31	784.5	5	810.5
B-4	46.5	822.5	30	16	46	776.5	4	818.5
B-5	41.5	847.5	0	45	45	802.5	15	832.5
B-6	33.0	851.5	0	32	32	819.5	-	-
B-7	30.0	810.8	0	27	27	783.8	-	-
B-8	46.5	797.9	32	6	38	759.9	12	785.9
B-9	41.5	792.5	20	19	39	753.5	4	788.5
B-10	35.0	778.3	24	14	38	740.3	6	772.3
B-11	35.0	779.7	19	15	34	745.7	25	754.7
B-12	32.5	838.3	30	1	31	807.3	-	-

 Table 3

 Soil Layers Condition After 2017 Landslide Event

4.2. Groundwater

At the time of drilling, water was encountered in some boreholes at different depths. The significant difference of water level indicates that the observed water is perched water and mainly results from rainwater infiltrating at the site and at neighboring highlands and mountain slopes that then flows through permeable soils that overly the bedrock. The 2017 landslide event caused some parts of surficial soils to become scrambled and fractured, thus a change in permeability of these soil layers resulted. The wetness of the recovered interface soil samples at the slip plane contact zone indicate much higher moisture content percentage there than in the underlying weather bedrock, as a result of groundwater following the slip surface fractures. Figures 50 to 53 in Appendix A, show variation of soil

saturation degree and void ratio versus depth in the different boreholes. These values were calculated using laboratory soil samples measuring dry density and moisture content.

Groundwater conditions vary with environmental variations and seasonal conditions such as frequency and magnitude of rainfall patterns. Seasonal groundwater fluctuations should be taken into account in design and construction. We recommend the contractor alert the engineers of actual groundwater levels, if encountered during construction, to determine groundwater impact on the construction procedures and on design. Inflow of groundwater during excavation could lead to significant construction problems and unsafe working conditions for personnel. If not properly controlled, groundwater inflow could also contribute to backslope failure of temporary excavations resulting in great bodily injury or death.

4.3. Soil Properties

Topographical map of the site was provided by Paul Jensen four times in February, June and October 2017, and in February 2018 to document continuing movement of the landslide mass.

The cross section locations as shown in Appendix C, were developed by HKA using the topographic map prepared by Paul Jensen. These cross sections were used as the basis for our stability analysis. The most critical cross section with deepest landslide plane was selected to carry out the slope stability evaluation.

We utilized the exploratory borings from our field investigation to develop a subsurface profile model. Four (4) different soil types were developed in these analyses.

The soil boundaries indicated on the cross sections are based on; 1) the engineer's observations and soil evaluations in the field; 2) the results of field Standard Penetration Tests (SPT) conducted during soil sampling; and 3) the engineer's laboratory test results. The soil boundary lines were projected between and beyond the location of the test borings in both directions, presuming a straight line; based on experience and engineering judgement in the site vicinity. The model is simplified and based on extrapolation of information obtained during field and laboratory testing. Changes in the soil stratum are likely more gradual than indicated in our models.

Strength parameters for the different soil types were determined using standard penetration test (SPT) results, laboratory direct shear results, and engineering judgment. The 2017 landslide was modeled using soil and bedrock parameters determined by laboratory and field test results in the way the landslide occurred and then the physical parameter accuracy was calibrated. In Table 3, in-situ landslide silty sandy layer (Soil 1), in-situ native silty sandy layer (Soil 2), and bed rock (Soil 3). The current condition of the impacted hillside was modeled using Soil 1 to Soil 3. For the improved slope condition, for those parts that were filled by compacted in-situ soil, Compact Fill (Soil 4) was introduced and used in the model.

Soil Type (Description, #, Model	Cohesion	Friction Angle	Unit Weight	
Color)	(psf)	(deg)	(pcf)	
In-situ landslide silty sandy layer # Soil 1(Yellow)	300	22	85	
In-situ native silty sandy layer # Soil 2 (Light Green)	400	28	110	
Bed Rock #3 (Orange)	3,000	40	125	
Redensified silty sandy fill layer # Soil 4 (Light Blue)	1,500	37	115	

 Table 4

 Soil Strengths Used For Slope Stability Analysis

5. <u>Geotechnical Related Seismicity</u>

The improvements should be designed in conformance with the most current California Building Code (2016 CBC). For seismic design, the soil properties at the site are classified as **Site Class "D"** based on definitions presented in Section 1613.3.2 in the 2016 CBC that refers to Chapter 20 of ASCE 7. The longitude and latitude were determined using a satellite image generated by Google Earth. These coordinates were taken from the approximate middle of the area of the proposed improvements:

Longitude = -121.665, Latitude = 37.127

The coordinates listed above were used as inputs in the Java Ground Motion Parameter Calculator created by the USGS to determine the ground motion associated with the maximum considered earthquake (MCE) SM and the reduced ground motion for design SD. The results are as follows:

<u>Site Class D</u> SM_s = 1.500 g SM_1 = 0.902 g SD_s = 1.000 g SD_1 = 0.601 g

A maximum considered earthquake geometric mean (MCE_G) peak ground acceleration (PGA) was estimated using the Figure 22-7 of the ASCE Standard 7-10. The mapped PGA was 0.527 g and the site coefficient F_{PGA} for Site Class D is 1.0. The MCE_G peak ground acceleration adjusted for Site Class effects is PGA_M = $F_{PGA} * PGA$

$PGA_M = 1.0 * 0.527g = 0.527g$

6. Quantitative Slope Stability Analysis

Stability analysis was performed on a cross section cut through the project site. The selected cross section location was selected by HKA's Project Geologist. The slope stability analysis was performed to quantify the instability associated with the occurrence of the 2017 landslide using the 2017 slope geometry; and also to analyze the potential for failure of the proposed improved slope under static winter conditions and seismic loading conditions.

6.1. <u>General Methodology</u>

Slope failures or landslides can cause problems including encroachment, property damage, personal injury, or even death. Failures of slopes occur when stress acting on the soil mass is greater than its internal strength (shear strength). A slope is considered stable when the strength of its soil mass is greater than the stress field acting within it. Some common variables influencing stress are gravity (steeper slopes), hydrostatic pressure (perched groundwater), soil surcharge pressures (overburden), concentrated surcharge at up slope (buildings, vehicles on the road and etc...) and seismic surcharge (earthquake shaking).

Various methods of analyzing stability of slopes yield a factor of safety. A factor of safety (FS) is determined by dividing the resisting forces within the slope soils (earth materials) by the driving forces within the slope (stress field). A FS greater than or equal to 1.0 is considered to be in equilibrium. A FS less than 1.0 is a potentially un-stable slope condition. HKA considers the potential for instability of a slope or hillside to be low with a FS against sliding greater than or equal to 1.10 under seismic loading conditions and 1.50 under static loading conditions. Some governing agencies including Santa Cruz County Environmental Planning and the Mining Safety and Health Administration (MSHA) require slopes to have a FS equal to or greater than 1.20 to be considered seismically stable.

6.2. Quantitative Analysis with GEO-SLOPE 2018

The analysis was completed with the aid of GEO-SLOPE computer software version 9.0.3.15488. A model for the section was defined with the input parameters consisting of slope geometry, soil properties, loading conditions, and pore water pressure ratio. Each model was evaluated under static and seismic loading. Mohr-Coulomb material model was used to define the soil properties. The analysis calculates the factor of safety against sliding for the failure surface(s).

Trial failure surfaces for the analyses consisted of circular (general) and wedge type failures. Morgenstern-Price analysis method is used to determine normal and resistive forces in each slice. The forces in each slice are then summed up for total force acting on the mass. In circular (general) failure mode stability assessment, the computer program assumes many failure surfaces using initiation and termination points on the ground surface selected by the user. These chosen points represent the toe and scarp of each potential landslide in relation to the assumed failure surfaces. The critical trial failure surface from the pseudo static analysis condition was selected as the projected failure surface in the development of design parameters.

6.3. Seismic Coefficient

The ground motion parameter used in pseudo static analysis is referred to as the seismic coefficient "kh". The selection of a seismic coefficient has relied heavily on engineering judgment and professional publications. The 2016 California Building

Code (CBC) provides site class definitions for seismic design of structures. Based on these definitions, a review of the site soil properties presented on our soil boring logs, the site is classified Site Class D, in accordance with ASCE 7 (with March 2013 errata). The current version of the California Building Code contains reference to maps of peak ground acceleration (PGA) based on site latitude and longitude. For this project the mapped PGA is 0.527g. The PGA is multiplied by a factor related to the seismicity of the site to obtain the seismic coefficient.

Two empirical charts developed by Blake and others are currently available for estimating the seismicity factor in Figure 1 and Figure 2 of Chapter 5 Analysis of Earthquake-Induced Landslide Hazards in CGS *Special Publication 117 Guidelines For Analyzing and Mitigating Seismic Hazards in California 2008.* Each chart represents a minimum allowable displacement of the embankment or slope. Figure 1 is a minimum allowable displacement of 2 inches and Figure 2 is a minimum allowable displacement of 6 inches. In general, the more displacement the slope can tolerate, the lower the seismicity factor or percentage of PGA can be calculated. A simple way to think of it is if a maximum of 0 inches of displacement is tolerable then $k_h = 100\%$ of PGA would be calculated. If the slope can tolerate a maximum of 6 inches of movement then k_h would be much closer to 50% of PGA. If the k_h value used results in a factor of safety less than 1.2 for seismic loading conditions and 1.5 for static, a Newmark analysis should be completed.

For this analysis, a maximum displacement of 2 inches within the failure mass was presumed to be tolerable. This presumption is typical for stability analysis involving structures or permanent improvements. The seismicity factor was estimated to be 54.0% of PGA or $k_h = 0.54 * 0.527g = 0.285g$.

6.4. <u>Geometric Assumptions</u>

Six (6) geometric sections (A3, B3, C3, D3, E3 & F3) were prepared by HKA's Geologist using the topographic map and ground surface profiles prepared by the Surveyor. For our analysis, the failure surface was focused along the worst case cross section (C3) which has the deepest impacted layers in 2017 landslide event. Four (4) soil types are presented in our model. At the ground surface of the slope either in-situ land slide silty sandy layer or in-situ compacted silty sand fill (for improved slope condition) exist. Beneath the landslide layer, the native soil consists of silty sand. Below the native soil, very dense bedrock is encountered. A phreatic water surface was observed in some boreholes at different depths; and in some boreholes, no water surface was encountered. The landslide happened after an above average rainy season, and landslide movement resulted in ground fractures that act as groundwater conduits. Therefore, the top soil has the potential to become partially saturated. In order to consider the effect of rainfall in creating pore water pressure, an "Ru" coefficient is considered for the in-situ landslide material and in-situ compacted fill. Ru simply models the pore pressure as a fraction of the vertical earth pressure for each slice. Each soil can have a different Ru value. In our project model, the Ru for the top soil (either in-situ compact fill or in-situ land slide sand) was designated as 0.4.

6.5. <u>Slope Stability Models for Studied Site</u>

The project slope has been modeled in four (4) conditions and each model has been evaluated in both static and seismic conditions. The models are introduced as follows:

- a. 2017 Landslide event re-creation; Based on engineer's judgment of the landslide geometry.
- b. Current condition of the existing slope after landslide;
- c. Improved slope installing two rows of secant piles, one along the outboard side of the lower road and another on the hillside mid-way to the upper road. The model also considers removal of 5 (+/-) feet from the surface of the landslide from the upper road to just downslope from the lower road. After the soil is removed and off hauled, an additional 5 (+/-) feet below this is also removed and redensified as engineered fill. An engineered fill slope with a gradient of 2H:1V is constructed with its toe starting at the upper row of secant piles and crest along outboard side (shoulder) of the upper road. The engineered fill extends below the upper road restoring access.
- d. The landslide mass below the lower row of secant pile with and without a surcharge load. The surcharge is the soil removed from the landslide between the upper and lower roads.

The slope stability safety factor for the above models in both static and seismic conditions are shown in Appendix C graphically and tabulated in this section of the report..

a. 2017 Landslide Event Recreation

Distinguishing the landslide mass layer from native soil is one of the most important goals of the project investigation. In some areas the landslide mass and native soil layers are the same but some native soil was below where the 2017 landslide slide plane formed. If desired, further exploration involving large diameter exploratory borings would be required to absolutely define the landslide mass thickness throughout the landslide area. In order to approximate the thickness of the landslide mass and native soil thicknesses, and also the depth to bedrock in each borehole, laboratory and field test results have been considered. Borehole logs and the soil samples retrieved from drilling were observed as well. Then a model of 2017 slope was estimated. In order to select the soil parameters most accurately, the soil parameters have been adjusted in a way that the 2017 landslide layer thickness that was defined by HKA. The achieved (adjusted) soil layers' parameters were used in the other models.

b. Current Condition Slope Stability Evaluation

In order to determine the future stability of the existing slope which contains the existing active landslide layers, the current condition of the slope has been modeled using the cross section C3 provided by Project Surveyor. Stability safety factors under static and seismic conditions have been evaluated. One of the most important results of current condition slope modeling is to evaluate the behavior of the native soil overlaid on the bedrock and to understand if the native soil will participate in future landsliding under design conditions and if the answer is yes, then how deep will be the future slope failure plane be?

Figures 63 & 64 in Appendix C show the safety factor of the current condition slope stability. The result shows that in a probable predicted future earthquake event, the existing slope can not be stable and will likely fail. The existing landslide mass will continue to be unstable under static condition as well. Under a seismic condition, all of the soil layers above the bedrock will likely be involved in the slope failure. In order to highlight the present failure condition, shading contours have been provided. As discussed previously, the slope is considered relatively stable if the safety factor under a seismic condition is more than 1.1. As can be seen in Figure 64 in Appendix C, the dark blue shading contours show a safety factor equal to or greater than 1.1 and the border of the light and dark blue zones shows the depth of future probable landslide planes and the thickness of the resulting probable future landslide mass. This border mostly touches the bedrock which indicates the predicted potential future landslide includes the native soil layers below the 2017 landslide mass and thus are susceptible to future landsliding. Therefore, slope stabilization should be considered at least as deep as the top surface of the bedrock.

Discussion about Slope Stability Improvement Options

Several alternative methods to improve the existing slope were assessed. As discussed earlier, in a future probable earthquake event, deep landsliding is expected. The in situ native soil layers above the bedrock will become part of the landslide. The bedrock was encountered in B-1 and B-2 at 45 feet and 30 feet respectively. Because the depth of the probable landslide is significant, some of the alternative methods are likely not practical or make the stabilization very costly. HKA previously submitted a memorandum letter on September 15th, 2017 that discussed several slide repair options and their feasibilities from a geological and construction perspective. These options are presented briefly as follow:

- Remove and Replace The Entire Slide Mass as Engineered Fill; This method is not practicable because the existing saturated landslide mass materials are not qualified in their in-situ condition for use as engineered fill; and there is little to no room onsite for material conditioning (moisture conditioning or drying back as needed) or hauling the removed the soil offsite for storage and conditioning.
- Dewater Slide Mass and Stabilize Road; This is not considered feasible because it is difficult to locate and isolate the source of subsurface water; Moreover, the existing slope is not stable seismically even under dry soil conditions.

- Tieback Soil Pin Pile Walls Below Both the Upper and Lower Roadways; This option is likely to be very costly and difficult to construct. Tiebacks will be very long in order to fully penetrate the landslide zone and extend a sufficient length into the stable bedrock zone to provide stabilization. Drilling long inclined tieback holes is difficult. They may need casing to prevent the hole wall from collapsing where it is within the landslide mass. Landslide soil layers can not provide arching stability and will collapse between the pin piles. The wall would need to be installed very deep and seated on the bedrock. Access roads to support drilling equipment would need to be constructed.
- Install culvert in stream and excavate upper slide mass; place and compact excavated spoil over pipe; construct retaining wall to stabilize upper roadway; This option is feasible and physically practical, but may not be permitted by regulatory agencies if another option is deemed less environmentally damaging.

The best solution for deep landslide stabilization may be a combination of feasible methods such as improving the drainage system for the site, excavating and removing the upslope area of the landslide mass soils then placing the excavated soil at the lower parts of the slope over a new culvert placed in the streambed, then recompacting that soil to achieve a compacted fill that sufficiently buttresses the slope to make reconstructed segments of the upper and lower roads stable. This option is likely to also require installation of vertical reinforcement such as piles into the slope. The permit process for this option may prove be very difficult with many agencies involved.

This option of repair must be modified as appropriate depending on the type of vertical reinforcement and its installation location. The upper road is located within the landslide scarp area. The slope crown should be stabilized where there are critical structures above it that must be protected from sliding. The large commercial water tank in its current location is setback beyond the influence of the subject landslide. If the proposed fill slope grading and flattening of the 2017 landslide scarp can provide a stable service platform for the upper road, then it is not necessary to install vertical reinforcement or tiebacks at the upper part of the slope. Construction of a wall between the pin piles is not feasible because the wall would have to be deep, at least reaching the bedrock. Also, it is impractical to remove the existing landslide soil mass and install the wall. If the wall is a sheet pile wall driven into the soil, specialty equipment must gain access to the work area and thus roadbed improvement would need to be provided.

c. Improved slope; installing two rows of secant piles one along the outboard side of the reconstructed lower road and the other on the hillside mid-way to the upper road. Constructing engineered fill slope

from upper row of secant piles to inboard side of reconstructed upper road restoring access and road shoulder.

If the goal is to stabilize the existing slope containing the landslide mass, two rows of secant piles should be installed which extend to a depth with at least a minimum 15 feet embedment into the bedrock. The landslide soil hasn't enough strength to stand between pin piles or widely spaced piers based on principles of arching. Therefore, zero spacing between piles is a requirement. Secant piles in this case are vertical piling that are installed next to each other with no space between each adjacent piles. The secant piles wall is constructed using a series of closely spaced drilled shafts filled with reinforced concrete. The piles can also be driven. However, driving the piles into very dense bedrock can be challenging or impractical. Also, if cast-in-place piles are designed for the project, boreholes in the landslide mass are expected to need casing to prevent their sidewall soils from collapsing into the drilled borehole.

Based on the slope stability results, each secant pile should have minimum 20,000 pounds per foot lateral capacity. For preliminary design purposes it can be assumed the resultant force acts at a location 2/3 the depth to the bedrock within the overburden soil. For practical applications, the actual location of the resultant should be determined by HKA at several sections along wall profile. In Figures 67 & 68 in Appendix C, slope stability safety factors under both static and seismic conditions are presented. Based on the slope stability evaluation results, the safety

factors for both static and seismic conditions are greater than the minimum acceptable limits, which means the uphill side of the slope starting from the outboard side of the lower road will be stabilized after installing two rows of secant piles and constructing an engineered fill slope to support the upper road. However, the proposed secant piles do not provide stability against sliding for soil on the downslope side of the lower row of secant piles. It is assumed the soil down slope from the secant piles (including the portion of the existing 2017 active landslide mass located there) will continue to move or eventually mobilize into the creek at some point in the future.

For the project slope stability analysis, the most critical cross section with deepest landslide material has been considered which requires installation of long and deep secant piles. The length of the piles will be reduced when moving toward the flanks (sides) of the landslide mass. In order to get a better understanding, a 3D view of the slope and potential landslide layers in the boreholes (case 2) are presented in Figures 57 to 58 in Appendix B.

The top 5 (+/-) feet of soils from just upslope from the upper row of secant piles to approximately 40 feet below the lower secant pile row is proposed for removal. These soils should be temporarily stockpiled in an approved location by HKA for re-use. An additional 5 (+/-) feet of soil below the removed soils will also be removed (10 feet total) and redensified back into place. The stockpiled soils, if dried back or moisture conditioned as needed, may be re-used as engineered fill

during construction of the fill slope that will support the upper road. The remaining soil left over should be off hauled or placed as engineered fill in a location on-site approved by HKA. The material should not be placed on the landslide mass below the lower row of secant piles as it can exacerbate instability of this soil mass.

By using this method two positive things with respect to landslide resistance are accomplished. The first is the existing bulging landslide soil mass will be removed from the upslope area effectively un-loading this portion of the hillside and reducing the driving force acting on the landslide mass. The second is, if the removed landslide mass can be dried back to near optimum moisture content it can be re-used as engineered fill during construction of the fill slope that will restore the travel way and shoulder of the upper road.

The graphical stability models presented in Figures 69 & 70 of Appendix C present general failure surface below the engineered fill slope that will support the upper road. The analysis of these models considers the stability of the fill slope without the benefit of the influence from the upper row of secant piles. The general failure surfaces were generated to slice through the landslide soils below the engineered fill slope. Our calculated factors of safety against sliding under static wet winter and seismic shaking conditions are above the minimum acceptable values for modern geotechnical engineering practice.

d. Stability of the landslide mass below the lower row of secant piles after installation with and without a surcharge load.

The stability of the landslide mass below the lower road after the secant piles have been installed was quantified with and without a surcharge load. The purpose of these models was to demonstrate the negligible effect of the secant piles on the stability of this portion of the landslide mass. The results of the analysis indicate that this portion of the landslide mass is unstable in static and seismic conditions. The factors of safety against sliding are less than 1.0 for both loading cases. When the surcharge load of soil was placed upon this portion of the landslide it further reduced the factors of safety against sliding. This indicates that placement of soil upon the lower landslide mass may exacerbate instability or speed up movement of the soil mass into the creek and is not recommended. This model was evaluated to quantify the effects of placing soil removed from the upper portion of the landslide onto to the lower portion of the landslide as a means of disposal. This is presented graphically in Figures 71-74 in Appendix C of this report.

6.6. Slope Stability Conclusions

The slope stability assessment is for general (global type) slope failure and consists of initiation and termination of trial failure surfaces on the top and toe of slopes for recreation of landslide and evaluation of existing condition. The models with slope improvements including secant piles and engineered fill were evaluated with failure surfaces running top to toe as well as mid slope as selected by engineer to evaluate benefit to stability of improvement. In both scenarios, the trial failure

surface passes through the soil layers in the cross section model. The general shear trial failure surface screens for potential instability below the in-situ landslide and native soil layer. The in-situ landslide soil layers were also screened for trial failure surfaces localized within the soil layer.

In table 5, slope stability analysis results for the four (4) aforementioned models static and seismic conditions are shown.

In summary the large landslide soil mass can be stabilized from the lower row of secant piles along the outboard side of the lower road up to the inboard side of the re-constructed upper road. For stability discussion purposes we will refer to this as the "upper landslide" and the portion downslope from the lower row of secant piles the "lower landslide". A second row or upper row of secant piles on the hillside mid-way to the upper road is required to stabilize the upper landslide soil mass described in this conclusion. Factors of safety against sliding are greater than what is considered stable using modern geotechnical engineering standards.

Although the secant piles will restore stability of the upper landslide it will not restore access across the upper road. An engineered fill slope is modeled to support and restore the upper road. The fill slope is modeled to have a 2H:1:V slope gradient with its toe at the upper row of secant piles and crest at the shoulder of the upper road. The fill slope would extend to allow reconstruction of the upper

road to allow vehicular traffic, and would terminate along the inboard cut slope of the upper road.

HKA re-iterates that the stability models indicate that the presence of improvements such as secant piles and engineered fill will stabilize the upper area of the landslide, but will not stabilize the lower area of the landslide. The removed soil during grading can be re-used as engineered fill in construction of the fill slope restoring the upper road. Any excess soil should not be disposed of by placing it upon the lower landslide. Doing so may exacerbate instability by increasing the rate of mobilization of the lower slide into the creek below. If SLVWD would like to stabilize the lower landslide area and dispose of soil in this location, additional rows of secant piles will need to be constructed within the lower landslide along with retaining walls to buttress the fill along the toe. The location and depth of these improvements should be carefully evaluated by HKA.

We anticipate a temporary road will need to be constructed to install the upper row of secant piles on the hillside. Additional working meetings with structural and civil designers, specialty contractors, and SLVWD are anticipated to develop viable working drawings.

6.7. Limitations of Analysis

It must be cautioned that slope stability analysis is an inexact science; and that the mathematical models of the slopes and soils contain many simplifying assumptions, not the least of which is homogeneity. Density, moisture content and

shear strength may vary within a soil type. There may be localized areas of low strength or perched ground water within a soil. Slope stability analyses and the generated factors of safety should be used as indicating trend lines. A slope with a safety factor less than one will not necessarily fail, but the probability of slope movement will be greater than a slope with a higher safety factor. Conversely, a slope with a safety factor greater than one may fail, but the probability of stability is higher than a slope with a lower safety factor.

Condition	Loading Condition	Minimum Factor of Safety Against Sliding	Trial failure Surface Shape
2017 Landslide Event	Static	0.92	Circular
2017 Landslide Event	Seismic	0.45	Circular
Current Condition	Static	0.96	Circular
Current Condition	Seismic	0.48	Circular
Improved Slope by Installing Two Rows			
of Secant Piles With Shallow	Static	3.54	Circular
Redensification of Upper Landslide			
Improved Slope by Installing Two Rows			
of Secant Piles With Shallow	Seismic	1.19	Circular
Redensification of Upper Landslide			
Upper Road Slope Stability General Failure Safety Factor after proposed upslope grading and head scarp flattening	Static	2.73	Circular
Upper Road Slope Stability General Failure Safety Factor after proposed upslope grading and head scarp flattening	Seismic	1.49	Circular

Table 5Slope Stability Analysis Results

General Failure Safety Factor of Landslide Mass Below Lower Secant Row	Static	0.96	Circular
General Failure Safety Factor of Landslide Mass Below Lower Secant Row	Seismic	0.54	Circular
General Failure Safety Factor of Landslide Mass Below Lower Secant Row With Surcharge	Static	0.52	Circular
General Failure Safety Factor of Landslide Mass Below Lower Secant Row With Surcharge	Seismic	0.91	Circular

7. Building Codes and Site Class

Project design and construction should conform to the following current building codes:

-2016 California Building Code (CBC); and

-2016 Green Building Standards Code (CAL Green)

In accordance with section 1613.3.2 of the 2016 CBC, the project site should be

assigned the Site Class D.

8. <u>Recommendations for Design and Construction</u>

The results of our investigation indicate that the different slope improvement / stabilization options are feasible from a geotechnical standpoint. The criteria and recommendations presented in this report are focused on the secant pile repair schemes previously presented in the report and we recommend that those should be followed during design and construction of the project.

Geotechnical considerations at the referenced site include improving the stability of the upper and lower roads crossing the existing landslide, the potential for strong seismic shaking, and providing adequate site drainage provisions.

Our slope stability analysis results have shown that the current condition of the existing overburden soils overlying the bedrock (including both landslide mass and native soil materials) have high instability potential when moistened or saturated during heavy rainfall or during the occurrence of an earthquake. The instability is possible under both static and seismic conditions. Our basis of design is reliant on the potential slip planes derived from the slope stability analysis. The failure planes were considered to toe out on the slope, based on our best estimate of the soil/bedrock contact and also were controlled by the position of the creek as the base of the slide. The geotechnical considerations for the failure condition are related to the geometry of the slope and soil information determined from the test borings, Figures 5 through 26 in Appendix A.

To mitigate the instability potential, it is recommended to unload the upper landslide by removing the upper 5 (+/-) feet of soil. After removal of the soil an additional 5 (+/-) feet of the upper landslide should be also removed, but this soil re-densified back into place as engineer fill. The upper landslide should be stabilized using two rows of buried secant piles. The lower row of secant piles would be constructed along the outboard side of the lower road and is estimated to be 200 feet long by as much as 55 feet deep. The upper row of secant piles is recommended to be constructed on the hillside mid-way to the upper road. The upper row is estimated to be 150 feet long by as much as 40 feet deep. The piles should be advanced a minimum 15 feet deep into the bedrock.

To rebuild and secure the severely damaged portion of the access road where the landslide mass dislodged from the head scarp, an engineered fill slope is recommended to be constructed from the upper row of secant piles up to the inboard side of the upper road.

Due to disturbance of the soil during the 2017 landslide event, the existing landslide soil layers have residual strength which are significantly less than the strength of the native soil. Therefore, it is expected that the landslide soils cannot provide arching. So, there should be no room between two adjacent consecutive piles along the respective wall alignments. Based on the slope stability results, the safety factor for the slope stability both in static and seismic conditions are greater than the minimum acceptable limit. The stability model indicates that if two rows of secant piles are inserted into the model, the unsupported part of the slope located downslope from the piles is considered unstable. In reality, and in the long term, that part of the unsupported slope and landslide mass will likely continue to slide toward the creek at the northern end of the property. Disposal of soil or any other surcharge load placed onto the lower landslide mass will exacerbate instability and is not recommended.

In the aforementioned slope improvement method, we recommend excavating the surficial soils on the slope in the upslope area of the landslide mass. Some portions of the excavated soil will need to be moisture conditioned or dried back as needed, replaced and recompacted at the initial location to remove the existing bulge in the landslide mass that exists below the landslide headscarp (formed during the 2017 landslide event) to make a uniform firm surface and to provide a flatter slope. The rest of the excavated soil may be re-used in construction of the engineered fill slope that will restore the travel way and shoulder of the upper road. Excess soil not used as described above may be placed as engineered fill in other locations on the property approved by HKA. The excess soil should not be disposed of upon the lower landslide mass.

An advanced widespread drainage system should be considered for the project site to collect the runoff water from the hillside. A proper site drainage system is important for the long term performance of the site. As indicated elsewhere in this report, perched water was observed in some of the drilled boreholes. Though groundwater levels could not be studied for this site, the reported observations indicate groundwater collects within the in-situ soil, thus, the proposed slope improvement should include subdrains as part of the site's planned remediation. To minimize the impact of subsurface seepage on the improved slope, subdrains are recommended. HKA would like to have working meetings with client's representative and project designers when the slope improving option enters a conceptual design phase to discuss more about the limitations of our model. The variable depth of the landslide from its deepest point along the center to the flanks where it pinches out to nothing should be carefully considered. The varying depth of the slide will have great affect on the location and magnitude of the resultant force. HKA should work with the civil and structural designers to develop additional models in select locations to optimize a value engineering type of solution. To accomplish this additional testing may be needed such as down hole borings and or geo-physical survey to fine tune the 3-D model of the landslide soil mass. Soil pile interaction using a finite method can also aid in value engineering design.

The following recommendations should be used as guidelines for preparing project plans and specifications:

Site Grading (Fill/Cut Slopes)

1. The HKA should be notified <u>at least four (4) working days</u> prior to any site clearing or grading operation so that the work in the field can be coordinated with the Grading Contractor and arrangements for testing and observation services can be made. The recommendations of this report are based on the assumption that the HKA will perform the required testing and observation services during grading and construction. It is the client's

responsibility to make the necessary arrangements for these required services.

- Where referenced in this report, Percent Relative Compaction and Optimum Moisture Content shall be based on ASTM Test Designation D1557-latest revision.
- Areas to be graded should be cleared of obstructions including loose fill, or other unsuitable material. Existing depressions or voids created during site clearing should be backfilled with engineered fill.
- 4. Cleared areas should then be stripped of organic-laden topsoil. Stripping depth should be from 2 to 4 inches. Actual depth of stripping should be determined in the field by an HKA representative. Stripping should be wasted off-site or stockpiled for use in landscaped areas if desired.
- 5. Areas to receive non-expansive engineered fill should be scarified 8 inches, moisture conditioned to over optimum moisture content, and redensified to 90 percent of maximum density. Portions of the site may need to be moisture conditioned or dried back as needed to achieve suitable moisture content for compaction. These areas may then be brought to design grade with engineered fill.

- Engineered fill should be placed in thin lifts not exceeding 8 inches in loose thickness; moisture conditioned, and compacted to at least 90 percent relative compaction.
- 7. We understand grading at the site will consist of excavation of a portion of landslide overburden soil to construct a flatter slope along the upper landslide to allow for installation of the upper row of secant piles. A temporary access road and working platform will also need to be constructed to support heavy equipment that will be required to advance the secant piles.
- 8. The top 5 (+/-) feet of soils from just upslope from the upper row of secant piles to approximately 40 feet below the lower secant pile row is proposed for removal. These soils should be temporarily stockpiled in an approved location by HKA for re-use. An additional 5 (+/-) feet of soil below the removed soils will also be removed (10 feet total) and redensified back into place. The stockpiled soils, if dried back or moisture conditioned as needed, may be re-used as engineered fill during construction of the fill slope that will support the upper road. The remaining soil left over should be off hauled or placed as engineered fill in a location on-site approved by HKA. The material should not be placed on the landslide mass below the lower row of secant piles as it can exacerbate instability of this soil mass.

- 9.¶ To rebuild and secure the travel way and shoulder of the upper access road where the soil mass dislodged from the head scarp an engineered fill slope with a gradient of 2H:1V is recommended to be constructed from the upper row of secant piles up to the inboard side of the damaged upper road.
- 10. Areas to be graded should be cleared of all obstructions, including foundations and structures if exist, old fill, trees not designated to remain and other unsuitable material. Disturbed soil resulting from demolition and clearing operations may be stockpiled for use as engineered fill, provided the fill is clean of organic material, unacceptable colluvium deposits or other unsuitable material. Existing depressions or voids created during site clearing should be backfilled with engineered fill.
- 11. If project site grading is performed during or shortly after the rainy season, the grading contractor may encounter compaction difficulty, such as pumping or bringing free water to the surface. If compaction cannot be achieved after adjusting the soil moisture content, it may be necessary to over-excavate the subgrade soil and replace it with angular crushed rock to stabilize the subgrade. We estimate that the depth of over-excavation would be approximately 12 inches under these adverse conditions.
- 12. Import soils if utilized as engineered fill at the project site should:

1) Be free of wood, organic debris and other deleterious materials;

- 2) Not contain rocks or clods greater than 5 inches in any dimension;
- 3) Not contain more than 25 percent of fines passing the #200 sieve;
- 4) Have a Sand Equivalent greater than 18;
- 5) Have a Plasticity Index less than 18;
- 6) Have an R-Value of not less than 30; and
- Contractor should submit to HKA samples of import material or utility trench backfill for compliance testing a minimum of 4 days before it is delivered.
- We estimate shrinkage factors of 15 to 25 percent for the on-site materials when used in engineered fills.
- 14. Cut and fill slopes should be protected from erosion by preventing runoff from spilling over graded slopes. Generally, Lined V-ditch and/or curtain drain at the top of the hillside and curtain drain at the secant piles wall may be considered for long-term drainage control. A proper drainage system should be designed for the entire site to collect and control the run off waters.
- 15. After the earthwork operations have been completed and HKA has finished observation of the work, no further earthwork operations shall be performed except with the approval of and under the observation of HKA.

- Permanent graded slopes should be constructed no steeper than 2.H:1V (horizontal to vertical). Graded slopes are expected to require erosion control and periodic maintenance for surface sloughing.
- 17. Fill slopes should be constructed with keyways and benches sloped in the inboard direction a minimum 5 percent. The keyways should be a minimum 8 feet wide and placed over bridging material comprised of 12 inches of gabion over geogrid equivalent to Mirifi 600X of better. The keyway and benches should be constructed with drains to alleviate hydrostatic pressure. The geotechnical engineer should approve the type of drainage system and location for discharge.

Secant Pile Walls

- 18 Secant pile walls are formed by constructing intersecting reinforced concrete piles. Secant pile walls are formed by keeping spacing of piles less than one diameter. Secant pile walls are used to build cut off walls for the control of ground water inflow and to minimize movement in weak and wet soils.
- 19. Secant walls are constructed in the form of hard/soft (or firm) or hard/hard walls on adjacent piles. If the distance between the hard and soft piles are equal to piles diameter, the wall is called tangent pile wall.

- 20. The secant piles are reinforced with either steel rebar or with steel beams and are constructed by either drilling under mud or augering or driving. In this wall system, there are two types of piles. Primary piles are installed first. These piles are mainly responsible for waterproofing and filling the voids.
- 21. In the Hard/Firm (or soft) wall system, the primary piles have no reinforcement and consists of flexible concrete that can be cut while the secondary piles are installed. The secondary piles which should have reinforcement will be installed between the primary piles once the latter gain sufficient strength. Where short term water retention is required, this system offers the most cost-effective and rapid solution. The wall consists of interlocking bored or driven piles. Primary piles are constructed first using a 'soft' cement-bentonite mix or 'firm' concrete. Secondary piles, formed in structural reinforced concrete, are then installed between the primary piles. The primary piles in Hard/Firm (or Soft) wall system should be drilled to minimum bed rock depth and the pile base will be sited on the bedrock. Therefore, all the lateral capacity of the wall will be provided by the secondary piles and therefore, the secondary piles design in hard/firm (or soft) wall system differs from the hard/hard wall system design.
- 22. Hard/hard wall construction is very similar to a hard/firm wall but in this case the primary piles are constructed in higher strength concrete and may be reinforced. Heavy duty rotary piling rigs, using tools fitted with specially

designed cutting heads, are necessary to cut the secondary piles. The end product provides a fully concreted face and can be an effective alternative to diaphragm wall construction.

- 23. Pile overlap is typically in the order of 3 inches. In a tangent pile wall, there is no pile overlap as the piles are constructed flush to each other.
- 24. Verticality tolerances may be hard to achieve for deep piles. Special care should be taken to assure the pile installation is vertical.
- 25. Special construction method might be required to make sure that total waterproofing is provided.
- 26. A monitoring and maintenance program is an integral component of the design of secant pile wall. To maintain the integrity of the wall system, it is necessary to conduct regular inspections of the slope and the secant pile. We recommend secant pile wall be inspected after long duration winter storms, severe seismic shaking, and at least once every 2 years by a licensed engineer or an engineering geologist to monitor the status of the wall system and recommend maintenance when needed.

Drilled piles for the secant Pile Wall

27. If cast-in-place piles are considered for secant pile wall system, the project

site secant piles should be excavated prior to placement of the reinforcement cage. All pile excavations should be observed by the soils engineer prior to placement of steel and concrete. Pile diameter is to be determined by the project structural engineer. Pile drilling sequence and method of pile drilling is to be determined by the project contractor. Casing of the pier shaft within the loose sandy soils may be required.

- Secant piles at the project site should be embedded a minimum of 15 feet into the competent bedrock.
- 29. The landslide layers over the native soil are considered residual strength disturbed soil. The behavior of this layer is not uniform at different locations and depths of the slope. Therefore, it is prudent to neglect the top of the secant piles for calculating passive resistance. This length is decreased as they reach the flanks (sides) of the slope which contain shallower landslide deposits. At present, the only reliable information of landslide thicknesses is the existing geotechnical boreholes. Therefore, complementary investigation to determine the exact thickness of the landslide layer at the different locations of the slope should be performed or conservative landslide depth should be assumed for designing.
- 30. The secant piles are installed next to each other without any room for soil to provide arching. Therefore, if applicable for pile designing, arching capability

factor and safety factor should be considered equal to 1.0.

- 31. At 15 feet below bedrock, an allowable vertical bearing and tension capacity pile of 15 ksf and 6 ksf respectively plus a one third increase for short duration loading may be used for design of the drilled piers. It must be noted that side friction for soil layers overlaid the bedrock has been disregarded due to existing residual soil.
- 32. Total and differential settlement for the secant piles penetrating the looser landslide and native soil deposits to be embedded within the bedrock, are anticipated to be less than 1 inch and 0.5 inch respectively.
- 33. Prior to placing reinforcing steel and concrete, all pile excavations should be thoroughly cleaned. The foundation excavations must be observed by HKA prior to placing reinforcing steel and concrete.
- 34. The Contractors are responsible for following CAL-OSHA regulations, local codes and ordinances and any requirements outlined on any project plan sheets to maintain a safe working environment at the project site.

Active and Passive Pressures

35. The active pressures, as an equivalent fluid pressure, for both undrained and drained conditions under static and seismic conditions are presented in Table 6.

Table 6 Recommended active pressures

Recommended Active Pressure EFW (pcf)	Landslide Soil	Native Soil	Bed Rock
Undrained / Static condition	75	79	76
Undrained / Seismic condition	77	83	82
Drained / Static condition	42	39	28
Drained / Seismic condition	48	47	40

36. The passive pressure available in the soils below the bottom of the excavation may are presented as an equivalent fluid pressure:

Recommended passive pressures					
Recommended Passive Pressure EFW	Landslide Soil	Native Soil	Bed Rock		
(pcf)					
Undrained / Static condition	120	200	350		
Undrained / Seismic condition	100	175	300		
Drained / Static condition	190	310	550		
Drained / Seismic condition	125	250	480		

Table 7Recommended passive pressures

37. Aforementioned drained condition earth pressure values are assumed when walls are fully drained to prevent hydrostatic pressure behind the walls. Drainage materials behind the wall should consist of Class 1, Type A permeable material complying with Section 68 of Caltrans Standard Specifications, latest edition.

Driven Piles

38. Vertical alignment of the piles should be preserved during driving. However, an inclination of 2 to 3 inches from vertical can be accepted as the tolerance for such piles.

- 39. In a group of piles, the middle piles should be driven first and then working towards the perimeter piles. This is to prevent displacement of the already driven piles due to the lateral movement of the soil. In the granular soil if the piles are driven at spacing of less than three times the diameter of the adjacent pile, due to densification of the soil, penetration would be difficult.
- 40. When excessive resistance to the driving is mobilized, the operation can be stopped. If the pile is penetrated less than the calculated depth, the operation can be halted for one week in order to dissipate the excess pore pressure generated in the soil. The driving should be resumed after this period. However, if still the required penetration is not achieved, a pile load test is proposed to check the capacity of the driven pile.
- 41. If pile heave is observed, level readings referenced to a fixed datum shall be taken by the Engineer on all piles immediately after installation and periodically thereafter as adjacent piles are driven to determine the pile heave range.
- 42. If during the driving process for adjacent piles, piles shall be re-driven:
 - For end bearing piles, if the heave is more than 0.5 inch.
 - For shaft friction piles, if the heave is more than 1.5 inch.

Surface & Subsurface Drainage

- 43. The surface drainage from within the slipout area needs to be collected and directed to catch basins, existing creek or to outside of the site. Most importantly surface drainage should not be allowed to runoff or spill over the edge of the fill. The collected runoff should be piped down past the secant piles wall and downslope as well. Subsurface drains should be installed at the contact of recompacted topsoil on the slope. The number of drains and spacing should be determined by the project Civil Engineer. The drains should collect subsurface drainage within the improved area and convey drainage to an adequate discharge point downslope of the improvements.
- 44. Surface drainage should include provisions for positive gradients so that surface runoff is not permitted to pond adjacent to pavements nor spill over the slope. Surface drainage should be directed away from the graded slope.
- 45. The migration of water or spread of extensive root systems below excavations, embankments, foundations, slabs, or pavements may cause undesirable differential movements and subsequent damage to these structures. Landscaping should be planned accordingly.

Monitoring

46. A survey-monitoring program should be implemented to monitor slope

displacements during construction. In addition, improvements should also be surveyed and photographs and/or video taken to document baseline conditions. The deflection at the top of the secant piles should be surveyed periodically. If the piles head deflect significantly or if distress or settlement is noted adjacent to the top of the piles, an evaluation should be performed and corrective measures taken.

Plan Review, Construction Observation, and Testing

- 47. Haro, Kasunich and Associates should be provided an opportunity to review project plans, prior to construction, to evaluate if our recommendations have been properly interpreted and implemented in the design. Having done so, we can prepare the county-required geotechnical plan review letter.
- 48. If we do not review the plans and provide observation services during the earthwork phase of the project, we assume no responsibility for misinterpretation of our recommendations.

LIMITATIONS AND UNIFORMITY OF CONDITIONS

- 1. The recommendations of this report are based upon the assumption that the soil conditions do not deviate from those disclosed in the borings. If any variations or undesirable conditions are encountered during construction, or if the proposed construction will differ from that planned at the time, our firm should be notified so that supplemental recommendations can be given.
- 2. This report is issued with the understanding that it is the responsibility of the owner, or his representative, to ensure that the information and recommendations contained herein are called to the attention of the Architects and Engineers for the project and incorporated into the plans, and that the necessary steps are taken to ensure that the Contractors and Subcontractors carry out such recommendations in the field. The conclusions and recommendations contained herein are professional opinions derived in accordance with current standards of professional practice. No other warranty express or implied is made.
- 3. The findings of this report are valid as of the present date. However, changes in the conditions of a property can occur with the passage of time, whether they be due to natural processes or to the works of man, on this or adjacent properties. In addition, changes in applicable or appropriate standards occur whether they result from legislation or the broadening of knowledge. Accordingly, the findings of this report may be invalidated, wholly or partially, by changes outside our control. Therefore, this report should not be relied upon after a period of three years without being reviewed by a geotechnical engineer.

Project No. SC4090.1 6 August 2018

APPENDIX A

Site Vicinity Map (Figure 1)

Geological Site Map (Figure 2)

Boring Site Plan (Figure 3)

Key to Logs (Figure 4)

Logs of Test Borings (Figures 5 – 26)


Particle Size Distribution Test Results (Figures 27 – 35)


Plasticity Index (Figures 36 - 39)


Direct Shear Results (Figures 40 - 47)

Variation of SPT Blows, Saturation Degree and Void Ratio Versus Depth (Figures

<u>48 – 53)</u>









	PR	IMA	ARY E	VISIONS	5		GROUP SYMBOL	SECO	NDARY DI	VISIC	ONS				
2			GRA	VELS	CLEAN		GW	Well graded gravels,	gravel-sand mi	xtures,	little or no fines.				
uvi.	_		ORE TH	IAN HALF	GRAVE (LESS TH 5% FINE	IAN	GP	Poorly graded gravels fines.	or gravel-sand	l mixtur	res, little or no				
COARSE GRAINED SOILS MORE THAN HALF OF MATERIAL IS LARGER THAN NO. 200	8		FRACT ARGEI	TION IS R THAN SIEVE	GRAVE WITH		GM	Silty gravels, gravel-s	and-silt mixtur	es, non	-plastic fines.				
LF OF	SIEVE SIZE		410.4	ULLYE (FINES		GC	Clayey gravels, grave	-sand-clay mix	ctures, p	plastic fines.				
SE GR	SIEV		SAI	NDS	CLEAN		SW	Weil graded sands, gr	avelly sands, li	ttle or n	no fines				
OAR ORE T	3	м		IAN HALF DARSE	(LESS TH 5% FINE		SP	Poorly graded sands o	graded sands or gravelly sands, little or no fines						
V ž		4	FRACT MALLI	TION IS ER THAN	SAND		SM	Silty sands, sand-silt t	nixtures, non-p	lastic fi	ines.				
and the second state of th		-	NO. 4	SIEVE	FINES		sc	Clayey sands, sand-cl	ay mixtures, pla	istic fin	es.				
S			er	LTS AND	CLAVE	<u>ь</u> ж	MIL	Inorganic silts and ver fine sands or clayey si	y fine sands, ro Its with slight p	ock flou plasticity	r, silty or clayey y.				
ALF OF	IALLEK VE SIZE	ι		LIS AND		0%	CL	Inorganic clays of low sandy clays, silty clays	sticity,	gravelly clays,					
	IS SU	ſ					OL	Organic silts and organ	nic silty clays o	f low pl	lasticity.				
FINE GRAINED SOH.S MORE THAN HALF OF	MATCHALLIS SMALLIER MATCHALLIS SMALLIER THAN NO. 200 SIEVE SIZE AND THAN NO. 200 SIEVE SIZE			LTS AND	CLAYS		MH	Inorganic silts, micace silty soils, elastic silts.	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts.						
FINE	AM THA	L	IQUID	LIMIT IS GR	EATER TH	AN	CH	Inorganic clays of high	plasticity, fat	clays.					
			4 M	50%	. •		OH	Organic clays of medi	um to high plas	ticity, o	rganic silts.				
	HIG	HLY	ORG	GANIC SO	LS		Pt	Peat and other highly of	organic soils.						
		200		.S. STANDAF 0 l	D SERIES S	SIEVE	N SIZES	CLEAR SQUAR 3/4"	E SIEVE OPE 3"	NINGS 12"					
SILTS AND	CLAS	/5		SAND		<u> </u>	G	RAVEL	COBBLE	s	BOULDERS				
			FINE	MEDIUM	COARSE		FINE	COARSE	NG METHOD	ŀ	H,O				
RELA	TIVE	JENS			CONSISTEN	NC I		STANDARD			Final C				
SANDS AN GRAVEL		PI	OWS ER OT*	SILTS AND CLAYS	STREN((TSF)		BLOWS PER FOOT*	PENETRATION TE	Lank						
								MODIFIED CALIFOR	NIA	Ш					
VERY LOO			-4 -10	VERY SOFT	0 - % %~ %	. 2	0=-2 2=4	PITCHER BARRE	P	\boxtimes	Water level designation				
AEDIUM DE	NSE	10 -		FIRM	%~1		4-8	SHELBY TUBE	s		4				
DENSE		30 -		STIFF	1-2		8-16		è		-				
VERY DEN	SE .	OVE	K 20	VERY STIFF HARD	2-4 OVER		16-32 OVER 32	BULK	В						
**Uncon	ntined co	mpress	ave streng	t ner falling 30 incl th in tons/ft ² as de bservation.	hes to drive a 2" etermined by lat	O.D. (1 boratory	3%" I.D.) spiit sp testing or appro	IL	tration Test (AST)	4 D-1586), pocket				
								E	KEY T SLVWD BOULDER CR	- LYON	I TANK CALIFORNIA				
								SCALE: NTS		101-011	1-01				
								DRAWN BY: AJB	HARO KA	SUNIC	CH & ASSOCIATI				
								REVISED:	GEOTECI	HNICAL A	AND COASTAL ENGI				
75 of 30	8							JOB NO. SC4090.1			831) 722-4175				
5 51 500	5							FIGURE N	0.4		GALLING				

DG	GED BY CG	DATE DRILLED May 4, 2017	BORING D	IAMETE	R 6'	•	-	BORING NO. B-1
	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
		Fill						
		Brown and gray medium Silty SAND with Clay binder, moist, medium dense	SM					
		Fill, gray Granite SAND, moist, medium dense		26				
	1-1 (L)			13		105 12	12.7	
	1-2 (T)	Fill, gray Granitic Silty SAND, moist, medium	um	10	13			
		dense		14				
	1-3 (L)	Fill, Gray Silty Granitic SAND, wet, loose with plant roots	SM	6		104	15.1	
	1-4 (T)	plant roots		11		94	16.6 22.6	
	1-6 (T)	Fill, Gray coarse SAND, wet, loose		4		34	22.0	
	1-7 (T)	Fill, Gray Granite SAND with roots and wood fror 16-17.5' wet, loose	m	4		101	15.7	
	1-8 (T)	Fill, gray SAND, coarse from 14.5 to 16 and 17.5		7				
		to 19' Landslide, brown Clayey SAND, saturated, loose		1/18"				
	1-9 (T)	Landslide, brown Oldycy OAND, Saturated, 10030	,				28.8	
	1-10(L)			6		87	26.6	
		Landslide, light brown Clayey SAND, moist, very		5				
	1-11(T)	loose					26.3	(1-11) Grain Size Analysis
								% Gravel = 1.5 % Sand = 62.9
		Landslide, light brown Clayey SAND with Gravels	s	9		10-		% Fines = 35.6
	1-12(L)	(much less Clay than 1-11, very moist, loose				103	23.5	
-	1 KK2	<u>\</u> .		-		_		
T		SUNICH AND ASSOCIATES, IN						



G	GED BY CG	DATE DRILLED May 4, 2017	BORING D	IAMETE	R_6"			BORING NO. B-2
	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
		Fill, mixed, Silty Clayey SAND with Gravels, mo loose	ist, SC					
	2-1 (L)	Fill, mixed light brown Clayey SAND with Grave moist, loose	ls,	13	1	07	13.0	
	2-2 (T)	Increase in moisture from 6 1/2' to 8' Loose and saturated from 8'		6			16.3	
I	2-3 (L)	Gray Clayey SAND with Gravels and roots, very moist to wet, loose	, sc	2		92	23.9	
	2-4 (T)	Brown Clayey SAND with Gravels, very moist, loose	sc	3				
	2-5 (L) 2-6 (T)	Light brown Clayey SAND with Gravels, very moist to wet, loose		7		91	29.6	
	2-7 (L)	Light brown Silty SAND with Gravels, very mois to wet, loose	t SM	6 7		93	32.7	
	2-9 (L)	Sandy CLAY, mosit, stiff, light brown Silty Grani SAND, wet, soft to medium stiff	ite CL	6		83	33.2	
	2-10(T)	Native, light brown CLAY very moist, firm-stiff (weathered bedrock?)	CL	8				
	2-11(L)	Light brown CLAY, very moist, very stiff (weathered Bedrock?)		11	1	02	25.4	
	2-12(T)	Light brown Silty SANDSTONE, mosit, medium dense (weathered Bedrock)	SM					
	2-13(T)	Very light brown Silty SANDSTONE with orange stains, moist, very dense	e BR	50/4"			9.2	
		Boring terminated at 31.50 feet						
-								
Ł	ARO, KAS	SUNICH AND ASSOCIATES, IN	NC.					




OG	GED BY CO	B DATE DRILLED May 23, 2017 BORI	NG DI	METE	R_8'	' HS	_	BORING NO. B-3
	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
-	3-1 (B)	2" AC 10" AB Orange Gravelly SAND					23.2	
	3-2 (B)	Fill, Gray & orange Clayey SAND with Gravel, moist, medium dense	SC					
	3-3 (L)	Water 5' at end of drilling Fill, mixed orange brown Silty SAND with Clay & Gravels, very moist, loose	SM	19		116	11.0	
C	3-4 (L)	Water 10' first encountered (Weathered Granite) Fill, Orange brown Clayey SAND, very moist, wet with Gravel, very loose	SC	9		104	17.1	
5		Orange Gravelly SAND with Clay from 14' to 15' Wet, loose from 15' - 17.5'						
		Orange Clayey SAND, reddish brown decomposed wood from 19'-20'	SC					
C		Orange Clayey SAND, wet, loose	SC					
5		Orange & brown SAND with Gravels from 23' - 25' Orange & brown SAND and Gravelly SAND-Loose	SM	7		00	05.0	
	3-5 (L) 111 3-6 (T)	Brown Sandy CLAY (weathered Granite) moist, firm-medium stiff	CL	7		92	25.6	
D		Orange brown Clayey SAND with seams of wet Gravelly (weathered Granite) SAND	SC					
		Very light brown SANDSTONE with orange stains & striations, moist, very dense	BR					
5 -	3-7 (T)	- i		50/4"	1.			(3-7) Grain Size
	ARO, KA	SUNICH AND ASSOCIATES, INC.						Analysis %Gravel = 0.4 % Sand = 75.4 %Fine = 24.2

	DATE DRILLED May 23, 2017	BORING D	IAMETE	ER_8	" HS		BORING NO. B-4
Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
4-1 (B)		/					
4-2 (B)	Orange Clayey SAND	sc					
	Water at 4' @ end of drilling						
4-3(1)	Fill, gray & brown Clayey SAND		25		77	13.8	
HZ			19				
	Water first encountered		7				
	Gray Clayey SAND with Gravel and roots, wa	iter SC	2		64	22.0	
4-6 (T) \r							
	Crow Clovery SAND and medium to coorce S		10				
4-7 (L)	with roots, wet				96	15.1	
4-8 (T)	Clean grey SAND from 16.5 - 19' saturated, I (Alluvial deposits)	oose Sivi				24.1	
4-9 (T)		e)					
4-10(L)	wet. loose		3		81	32.4	
4-11(T)							
4-12(T)	-	el, CL	7				
	wei, meaium sim						
	Gray Silty & Clayey SAND, wet, loose						
1.12/T	-	ige SC	14			22.0	
	medium SAND, wet, medium dense (Alluvial deposits?)					22.0	
	. ,						
11	Ň						
	I+1 (B) I+2 (B) I+2 (B) I+3 (L) I+4 (T) I+4 (T) I+4 (T) I+6 (T) I+6 (T) I+10(L) I+11(T)	 2" AC 6" AB orange Gravely SAND and grave Clayey SAND Clayey SAND Orange Clayey SAND Water at 4' @ end of drilling Fill, gray & brown Clayey SAND 4-3 (L) 4-4 (T) Water first encountered Gray Clayey SAND with Gravel and roots, wa at 10'. wet. loose 4-7 (L) Gray Clayey SAND from 16.5 - 19' saturated, Ic (Alluvial deposits) 4-9 (T) Native, gray Clayey SAND (weathered granite wet. loose 1-10(L) 1-11(T) Gray & brown CLAY with thin seams of Grave wet, medium stiff Gray Silty & Clayey SAND, wet, loose 4" - 6" seams of orange coarse SAND & oran 	2" AC 6" AB orange Gravely SAND and gravy Clayey SAND SC 4-1 (B) Orange Clayey SAND SC 4-2 (B) Water at 4' @ end of drilling Fill, gray & brown Clayey SAND SC 4-3 (L) Water first encountered Gray Clayey SAND with Gravel and roots, water at 10'. wet. loose SC 4-5 (L) Gray Clayey SAND with Gravel and roots, water at 10'. wet. loose SC 4-7 (L) Gray Clayey SAND from 16.5 - 19' saturated, loose (Alluvial deposits) SM 4-9 (T) Native, gray Clayey SAND (weathered granite) wet. loose SM 4-10(L) Gray & brown CLAY with thin seams of Gravel, wet, medium stiff CL 4-12(T) Gray Silty & Clayey SAND, wet, loose SL 4" - 6" seams of orange coarse SAND & orange medium SAND, wet, medium dense (Alluvial SC	L1 (B) 2" AC 6" AB orange Gravely SAND and gravy Clayey SAND SC L2 (B) Orange Clayey SAND SC Water at 4' @ end of drilling Fill, gray & brown Clayey SAND 25 L4 (T) Water first encountered SC 7 L4 (T) Water first encountered SC 7 L4 (T) Gray Clayey SAND with Gravel and roots, water at 10'. wet. loose SC 7 L4 (T) Gray Clayey SAND and medium to coarse SAND with roots, wet SM 3 L4 (T) Gray Clayey SAND from 16.5 - 19' saturated, loose (Alluvial deposits) SM 3 L9 (T) Native, gray Clayey SAND (weathered granite) wet. loose 3 2 L10(L Gray & brown CLAY with thin seams of Gravel, wet, medium stiff CL 7 L12(T) Gray Silty & Clayey SAND, wet, loose SL 14	+1 (B) 2" AC 6" AB orange Gravely SAND and gravy Clayey SAND SC +2 (B) Orange Clayey SAND SC Water at 4' @ end of drilling Fill, gray & brown Clayey SAND 25 +4 (T) Water first encountered SC 7 +4 (T) Water first encountered SC 7 +4 (T) Gray Clayey SAND with Gravel and roots, water at 10". wet. loose SC 7 +4 (T) Gray Clayey SAND and medium to coarse SAND with roots, wet 10 SM 3 +4 (T) Clean grey SAND from 16.5 - 19' saturated, loose (Alluvial deposits) SM 3 2 +10(L) Native, gray Clayey SAND (weathered granite) wet. loose 3 2 3 +11(T) Gray & brown CLAY with thin seams of Gravel, wet, medium stiff CL 7 +13(T) 4" - 6" seams of orange coarse SAND & orange medium SAND, wet, medium dense (Alluvial SC 14	L1 (B) 2" AC 6" AB orange Gravely SAND and gravy Clayey SAND Orange Clayey SAND SC L2 (B) Orange Clayey SAND SC Water at 4'@ end of drilling Fill, gray & brown Clayey SAND 25 77 L4 (T) Water first encountered Gray Clayey SAND with Gravel and roots, water at 10'. wet. loose SC 7 L4 (T) Gray Clayey SAND and medium to coarse SAND with roots, wet 10 96 L7 (L) Gray Clayey SAND and medium to coarse SAND with roots, wet 10 3 L9 (T) Native, gray Clayey SAND (weathered granite) wet. loose SM 3 L9 (T) Native, gray Clayey SAND (weathered granite) wet. loose 3 81 L11(T) Gray & brown CLAY with thin seams of Gravel, wet, loose CL 7 L11(T) Gray Silty & Clayey SAND, wet, loose 14 7	L1 (B) 2" AC 6" AB orange Gravely SAND and gravy Clayey SAND SC L2 (B) Orange Clayey SAND SC Water at 4' @ end of drilling Fill, gray & brown Clayey SAND 25 77 L4 (T) Water first encountered Gray Clayey SAND with Gravel and roots, water at 10'. wet. loose SC 7 L4 (T) Gray Clayey SAND with Gravel and roots, water at 10'. wet. loose SC 7 L4 (T) Gray Clayey SAND and medium to coarse SAND with roots, wet 10 96 L10 Gray Clayey SAND from 16.5 - 19' saturated, loose (Alluvial deposits) SM 3 L9 (T) Native, gray Clayey SAND (weathered granite) wet. loose SM 81 32.4 L10(L) Gray & brown CLAY with thin seams of Gravel, wet, medium stiff CL 7 7 L12(T) Gray Silty & Clayey SAND, wet, loose SC 14 22.0

Haro,	<mark>Kasunian</mark> Gasta and G	Assoc	Lyon Tank Slide						PR	OJECT NO. SC4090
LOG	GED B	Y CG	DATE DRILLED May 23, 2017	BORING	DIA	METE	R_ 8"	' HS		BORING NO. B-4
Depth, ft.	Sample No. and type	Symbol	SOIL DESCRIPTION	Unified Soil	Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
- 35 - - -	4-14(T		Interbedded 4"-6" thick seams of orange Clay coarse SAND & medium Sand, wet, medium dense & very stiff (Alluvial deposits)		С	19			22.0	
- 40 - -	4-15(T		Saturated gray Clayey SAND spoils from aug Interbedded seams of medium to coarse ligh brown Sand, orange brown Clayey SAND, ve moist to wet, medium dense to 45.5'	t		13				
- 45 - - -	4-16(T		Orange decomposed Granite, mosit, very der Boring terminated at 46.5 feet	nse BR/	SM	57			9.2	(4-16) Grain Size Analysis % Gravel = 0.0 % Sand = 81.8 % Fines = 18.2
- 50 - - - - 55 -										
- - 60 -										
- - 65 -										
- 70										
H	ARO,	KAS	SUNICH AND ASSOCIATES,	INC.						
BY	dk			FIGURE	NO.	11				

	GED BY CO	B DATE DRILLED May 24, 2017	BORING DIA		R_2'	' HS		BORING NO. B-5
Depth, ft.	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
) –		Fill, brown weathered Granite, moist, medium dense	SC					
5	5-1 (L)	Native		7		102	11.8	
10	5-2 (T) 5-3 (L)	Orange decomposed Granite, moist, loose	SN	10 8		99	13.8	(5-3) Direct Shear 0 = 36
10	5-4 (T)	Orange weathered Granite, moist, loose Increase in drilling resistance from 11' - 15'		0				C = 162 psf Ms = 20.3 Atterberg Limits LL = 26.48% PI = 4
15	5-5 (T)	Water at 15' after drilling Orange very weathered Granitic CLAY, moist, medium dense	CL	14				
20	5-6 (T)	Water on Supply Orange, very weathered Granitc, moist, mediu dense	m SC	10				
25	5-7 (L)	Orange, less weathered Granite, moise, loose		19		107	17.2	
	5-8 (T)	Orange weathered Granite, moist, medium der	ise	19				0 = 51 C = 232 psf Ms = 19.7%
80	5-9 (T)	Orange decomposed Granite, very moist, dens	e	42			94	
35 -								




OGO	GED BY CO	G DATE DRILLED May 24, 2017 BC	DRING D		R_ 8" H	6	BORING NO. B-6
	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
	6-1 (L)	Fill Brown Silty SAND with Gravels, moist, medium dense	SM	22		10.7	
	6-2 (T)	Fill Orange brown Silty SAND, Granite, medium dense		13 38	11	8 10.3	(6-3) Direct Shear 0 = 47
)	6-4 (T)	Fill		19			C = 463 psf Ms = 15.1%
	6-5 (Т)	Orange brown decomposed Silty SAND, Granite, moist		20	99	10.9	
5	6-6 (Т)	Fill Orange brown decomposed Granite, moist, medium dense		14		14.1	
)	6-7 (T)	Fill Orange brown decomposed Grante, moist, medium dense Native (?)		11		14.0	
5	6-8 (T)	Gray weathered Granite, very moist, loose Gray, very weathered decomposed Granite, very moist, loose	SM	7			
	6-9 (L)			11	89	26.8	(6-9) Direct Shear 0 = 37 C = 611 psf
	6-10(T)	Orange, very weathered Granite, very moist, loose		4 50 2 1/2	2		
5_	888	Light brown SANDSTONE (Lompico Sandstone) with orange stains, mover, very dense Boring terminated at 33.0 feet	BR				
μ	RO KA	SUNICH AND ASSOCIATES, INC					

DGGED BY	CG DATE DRILLED May 24, 2017 BC			R 8" HS	_	BORING NO. B-7
Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density D.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
	2" AC Fill, Mixed orange brown, olive brown & gray weathered Granite, moist, loose to medium dense	SM				
7-1 (L)			17			
	Olive brown weathered Granite, moist					
7-2 (L)	Fill Mixed orange brown & gray weathered Granite		26	122	11.3	
) 7-3 (T)	Fill, Orange brown weathered Granite, very moist, medium dense		12			
7-4 (T)	Fill, Orange brown weathered Granite, very moist, medium dense		12		12.7	
	Easier drilling from 17' - 20'					
) 7-5 (T)	Fill Orange brown very weathered Granite, very moist, loose	SM	3			
; 7-6 (L)	Filter Fabric Orange gravelly SAND, very moist, loose		12		4.1	
) 7-7 (L)	Very hard drilling at 27' Light brown SANDSTONE with orange stains, moist, very dense	BR	50/2"	114	12.4	
	Boring terminated at 30 feet					
;						
HARO K	ASUNICH AND ASSOCIATES, INC	•				

OGGED BY	DATE DRILLED	BORING DIA	METE	R	-	BORING NO. B-8
Sample No. and type	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
100 - 100 -	Native Yellow brown fine to medium SAND loose to	SM	11			
8-1 (L)	medium dense from 0-3 1/2'		12	118	3.3	
	SAND seam at 4' (decomposed Granite Dark yellow brown Silty SAND with Clay, mica 8	0	4			
8-3 (T)\ 肛	occassional Gravels, moist loose	α				
8-4 (L)	Dark yellow		4			
) 8-5 (L)	Brown & gray Silty SAND with mica & angular coarse SAND, very moist, loose (decomposed	SM	6	106	20.0	(8-5) Direct Shear 0 = 42
	Granite) Hole caved to 12'					C = 358 psf Ms = 21.0%
5 8-6 (L)	Brown with gray pockets Silty SAND with mica and small roots, very moist, very loose	SM	8			(8-6) Direct Shear 0 = 40 C = 0
) 8-7 (T)	Gray SANd with Silt & Gravels, very moist, loos	se	9			
	Gray Clayey SAND in Auger cuttings from 24-2	5' SC				
5 8-8 (L)	Gray Clayey SAND with Gravels, very moist - w loose	vet,	13			
8-9 (T)	Gray Clayey medium to coarse SAND with		6			
) B-10 (L)	occassional 1/2" to 1" diameter angular Gravels wet, loose Buried piece of decomposed wood at 30', gradi more Clayey from 30' - 35'	SC	17			

Haro,	Kalun chi Iala Te	Assoc	Lyon Tank Slide						PR	OJECT NO. SC4090
LOC	GGED B	Y	DATE DRILLED	BORI	NG DI	AMETE	R		7G	BORING NOB-8
Depth, ft.	Sample No. and type	Symbol	SOIL DESCRIPTION		Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
	8-11(L)		Gray brown Sandy CLAY, wet, very soft		33	1				No recovery
- - - 40			Harder drilling at 38'							
- +0 -	8-12(T		Light brown SANDSTONE with orange Grav moist, very dense	els,	BR	50/4"				
45 -	8-13(T		Light brown SANDSTONE with orange Grav moist, very dense Boring terminated at 46.5 feet	els,	5	50/2"				
- 50 										
- 55 - -										
- 60 										
- 65 - -										
— 70 ·										
H	ARO,	KA	SUNICH AND ASSOCIATES,	INC.						
BY	: dk			FIGU	RE NC). 17				

_	GED BY C	G DATE DRILLED July 24, 2017 B				_	-	BORING NO. B-9
	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
-		Orange brown Silty medium to coarse SAND with	SM			-		
	9-1 (L)	mica, moist, loose (decomposed granite)		15			2.9	
	9-2 (T)	•		6				
		Orange brown Silty SAND with Gravels & Mica,	SM	11				
	9-3 (L)	moist, loose (decomposed granite)		5			15.0	
	9-4 (T) \ <u>;</u>			Ū				
)		$\overline{\nabla}$		1				
	9-5 (T)	Water at end of drilling Buried Decomposed Wood from 10' - 11.5'		3				
	9-6 (L)	Orange brown Clayey Silty SAND/Sandy CLAY	sc	8				
		with wood, mica and Gravels (weathered decomposed granite)						
5	9-7 (T)	2" soil & wood debris in sample		6			41.6	
		Buried decomposed wood from 15' - 16.5'					11.0	
)		Orange and brown Clayey SAND weathered	sc	11				
	9-8 (T) \:	Granite with Mica, wet, medium dense				118		
5		Orange brown Sandy CLAX wet loose (very		6				
	9-9 (T)	Orange brown Sandy CLAY, wet, loose (very weathered Granite shale)	CL	0			26.4	
)		Weathered Granite (intact) very moist, loose to						
	9-10(L)	medium dense		22		111	18.8	
		Harder drilling at 32'						
		1	_			-		




JGGEL	BY CO	B DATE DRILLED July 25, 2017 B	ORING DIA	METE	R 8" HS	_	BORING NO. B-10
Sample No.	and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
10-	(T)	Dark brown Clayey SAND with Gravel & roots, very moist, loose	SC	4		18.6	
10-2	2(L)	Dark brown Clayey SAND with Gravels		6			
		₩Water at 1:30 pm Water and end of drilling 10:32 am					
10-3	8(L)	Orange Clayey Gravelly SAND, very moist, loose (decomposed granite)		17	104	12.4	
10-4	(T)	Gray Gravelly SAND (decomposed grainte) wet, medium dense	SC	16		14.6	
) 10-5	20	Gray Clayey fine SAND with angular Gravels (slide debris), loose to medium dense		4		19.6	
10-6 5 10-1		Gray Clayey SAND with Gravels & wood fragment (slide debris?) wet, medium dense		16		21.6	
) 10-8	3(Т	Orange decomposed Granite, very moist, medium dense, grading to dense decomposed Granite from 30' - 35'		12			
10-9		Orange decomposed Granite with black specs, very moist, dense		47		18.1	

	BY CO	B DATE DRILLED July 25, 2017			L .	5	-	BORING NO. B-11
Sample No.	and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetromete Drv Densitv	p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
11-1	(L)	Light orange brown Silty SAND with large root, moist, medium dense (slide material)	SM	26	8	1	10.8	(11-1) Grain Size Analysis % Gravel = 5.2 % Sand = 67.0
11-2 11-3	10	Dark brown Clayey medium to coarse SAND with small and large roopts, moist - very moist, loose		4				% Fines = 27.8
11-4	(L)	Gray Silty medium to coarse SAND with large wood fragment, medium dense	SM	23	11	15	10.7	(11-4) Grain Size Analysis
11-5	(T)	Harder drilling (steady drilling) orange brown SAND with black fleck Decomposed Granite, ver moist, dense	ry	41				% Gravel = 13.5 % Sand = 73.2 % Fines = 13.3
11-6	(T)	Gray medium to coarse SAND Decomposed Granite, moist, medium dense to dense Gray Sandy CLAY, very moist, stiff	CL	12			26.1	
11-7	(L)	Orange brown Sandy CLAY, very moist, firm (old slide material), medium stiff	d CL	11	10)4	20.3	(11-7) Direct Shear 0 = 32 C = 367 psf Ms = 22.0%
11-8	(T)	Harder driling at 30' Orange SAND with Silty and black flecks (Decomposed Granite) very moist, medium dense, bands of orange gray brown and gray	SM	29			19.0	MS – 22.0%
11-9	(T)	coarser Sand from 7' to 7 1/2' ?? Orange decomposed granite, damp, very dense	BR	50/3"				


OG	GED BY CO	G DATE DRILLED July 25, 2017 BOI	RING DI	AMETE	R 8"H	-	BORING NO. B-12
	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
-	12-1(L)	Fill (Landslide Material) Orange brown Silty SAND with Gravels, moist, loose	SM	15	89	6.2	
	12-2(T)	Fill (Landslide Materials) Orange brown Silty SAND with Gravels, moist, very loose	SM				Sample deflecte by rock at 5'
)	12-3(T)	Orange brown Silty SAND with Gravels, moist, loose	SM	5	10	1 17.1	Refusal at 12-13' Gray Granite Rock &
	12-4(L)	Gray brown Clayey SAND	SC	50/5"			Galvanized Wire (Gabion Basket)
5	12-5(L)	Fill Dark orange brown Clayey SAND with mica			81		
)		Orange Sandy CLAY, stiff	CL	27			
	12-6(L) 12-7(T)	Orange very weathered Granite, very moist, loose		8		18.3	
5	12-8(L) 12-9(T)	Orange Clay very weathered Granite, very moist, soft Orange Sandy CLAY (very weathered Granite)		7 7	97	22.8	(12-8) Direct Shear 0 = 45 C = 292 psf
)	2-10(L)	Orange Sandy CLAY (very weathered Granite) wet, soft Orange less weathered Granite, wet, hard		88			Ms = 24.4%
	2-11(T)	Light brown SANDSTONE with orange bands, moist, very dense Boring terminated at 32.5 feet		50/6"		13.1	
5 -							


	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Drv Densitv	p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
		2" AC 5" AB Fill Orange brown Silty SAND, moist, loose, very loose from 2' - 5'						
	13-1 (L) 13-2 (T)	Fill, gray Silty SAND with Clay/Clayey SAND & Gravels, moist, medum dense	SM/SC	2 19	1(08	13.0	
D	13-3 (L)	Gray Silty SAND with Clay & Gravels, moist, medium dense	SM	44	1.	16	15.6	
5	13-4 (L)	Gray Silty SAND with Clay, moist, medium dense	SM	33	1'	15	13.3	
)	13-5 (L)	Native, gray Silty, Clayey SAND/Silty fine Sand with Clay (weathered Granite)	sc	40	12	25	11.2	(13-5) Grain Size Analysis
5	13-6 (L	Harder drilling @ 23 feet Gray granitic SAND, wet, very dense Water at 26' at end of drilling Slow drilling from 25' to 27'	SC	56/2"				% Gravel = 2.6 % Sand = 61.4 % Fines = 35.8
)	13-7 (T) 13-8 (T	Gray granitic SAND with angular Gravel, wet, dense		41 50/4"			15.1 13.0	
5 -		Boring terminated at 32.5 feet						





	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - !bs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
-	15-1 (L)	Fill Orange brown Silty SAND with Clay & Gravels, moist, loose	SM/SC	15 5				
	15-2 (T) 15-3 (L) 15-4 (T)	Fill Light brown (white) SAND, moist, medium dense	SP	45 29				(15-2) Grain Size Analysis
0		Fill Mixed gray & orange Silty SAND with Clay & Gravels, moist	SM					% Gravel = 3.3 % Sand = 66.0 % Fines = 30.7
0	15-5 (T)			24			12.6	
5	15-6 (T)	Fill Mixed orange & gray brown Silty SAND, moist, medium dense - dense Native	SC	30			11.6	
)	15-7 (T	Gray Silty Clayey SAND, moist, medium dense		26			14.4	
5	15-8 (T)	Gray Silty SAND with Clay, moist, medium dense	SM	22			13.8	
)	15-9 (T)	Gray Silty SAND, moist, dense	SM	48				
5 -		Boring terminated at 31.5 feet						


nepun, nu	Sample No. and type Symbol		Unified Soil Classification	s/foot t - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	ture y wt.	MISC.
Idan	Sample N and type Symbol	SOIL DESCRIPTION	Unifie Class	Blows/fo 350 ft - I	Qu - Penet	Dry D p.e	Moisture % dry wt.	LAB RESULTS
) ===	16-1 (L)	Fill Mixed gray Silty SAND with Gravel, moist, medium	SM	28 22		114	13.0 13.2	(16-1) Grain Size Analysis
5	16-3 (L)	Fill(?) Orange gray Clayey SAND with Gravels moist, medium dense	s, SC	41 27				% Sand = 61.9 % Fines = 35.1 (16-3) Grain Size Analysis
0	16-4 (T)	Mixed orange & gray Clayey SAND with Grave moist, medium dense	ıl,	25			12.8	% Gravel= 0.9 % Sand = 58.8 % Fines = 40.3
	16-5 (T)						13.3	(16-4) Atterberg Limits LL = 24.1% PI = 9%
5	16-6 (T)	Mixed orange & gray Silty SAND, moist, mediu dense	im	23			12.9	
0	16-7 (T)	Gray Silty CLAY with Sand, moist, medium de Boring terminated at 21.5 feet	nse ML-CL	24				(16-7) Atterberg Limits II = 24.2%
5								PI
0								
























Liquid Limit:	26.5
Plastic Limit:	22.7
Plasticity Index:	3.8
PI 4	




File N∘	SC 4090.1
Sample N∘	5-3-1
Date:	1/25/2017
By:	RC

	P.I.	P.I. SOIL TEST						
	PLASTIC LIMIT							
Determination	1	2	3	4				
Tare N∘	14	3	10					
Gross Wet WT.	13.57	15.32	16.70					
GrossDry WT.	13.10	14.54	15.56					
Tare WT.	11.07	11.19	11.02					
NET DRY WT.	2.03	3.35	4.54	0.00				
WT. OF Water	0.47	0.78	1.14	0.00				
% Moisture	23.15	23.28	25.11	#DIV/0!				

	LIQUID LIMIT								
NUMBER OF BLOWS									
35	28	23	17						
6e	4f	5e	1c						
12.24	10.42	13.53	11.49						
10.80	9.20	11.52	9.76						
4.20	4.16	4.17	4.20						
6.60	5.04	7.35	5.56						
1.44	1.22	2.01	1.73						
21.82	24.21	27.35	31.12						





Sample #	5-3-1
Ht. of Sample	bag
Tare	4
Gross Wet Wt	282.5
Gross Dry Wt.	261.8
Tare Wt.	109.8
Net Dry Wt.	152.0
Wt. Of Water	20.7
% Moisture	13.6%
Dry Density	#VALUE!
Gold and I	light Brown
Elast	tic silt
Group	

SM

Symbol


Liquid Limit:	22.7
Plastic Limit:	15.8
Plasticity Index:	7.0
PI 7	




File N∘	SC 4090.1
Sample N∘	14-3-1
Date:	1/25/2018
By:	RC

	P.I. SOIL TEST			
	PLASTIC LIMIT			
Determination	1	2	3	4
Tare N∘	22	31	12	
Gross Wet WT.	14.91	13.62	15.87	
GrossDry WT.	14.41	13.26	15.26	
Tare WT.	11.20	11.00	10.97	
NET DRY WT.	3.21	2.26	4.29	0.00
WT. OF Water	0.50	0.36	0.61	0.00
% Moisture	15.58	15.93	14.22	#DIV/0!

LIQUID LIMIT					
NUMBER OF BLOWS					
34	28	23	16		
1a	3c	5e	4e		
12.05	14.41	11.10	11.12		
10.77	12.58	9.82	9.66		
4.21	4.16	4.16	4.19		
6.56	8.42	5.66	5.47		
1.28	1.83	1.28	1.46		
19.51	21.73	22.61	26.69		





Ht. of Sample	6.0				
Tare	14				
Gross Wet Wt	921.5				
Gross Dry Wt.	816.6				
Tare Wt.	109.6				
Net Dry Wt.	707.0				
Wt. Of Water	104.9				
% Moisture	14.8%				
Dry Density	101.3				
Brown Silty Sand					
with Clay					
Group					
Symbol	SC				

14-3-1


Liquid Limit:	24.1
Plastic Limit:	15.4
Plasticity Index:	8.7
PI 9	




File N∘	SC 4090
Sample N∘	16-4
Date:	2/1/2018
By:	RC

	P.I. SOIL TEST				
	PLASTIC LIMIT				
Determination	1	2	3	4	
Tare N∘	26	31	22		
Gross Wet WT.	14.92	16.02	17.48		
GrossDry WT.	14.39	15.36	16.64		
Tare WT.	11.00	10.98	11.19		
NET DRY WT.	3.39	4.38	5.45	0.00	
WT. OF Water	0.53	0.66	0.84	0.00	
% Moisture	15.63	15.07	15.41	#DIV/0!	

LIQUID LIMIT					
NUMBER OF BLOWS					
33	27	21	15		
4e	5b	3e	5g		
14.24	12.21	16.41	16.15		
12.48	10.70	13.93	13.55		
4.19	4.18	4.28	4.17		
8.29	6.52	9.65	9.38		
1.76	1.51	2.48	2.60		
21.23	23.16	25.70	27.72		





Sample #	
Ht. of Sample	bag
Tare	200
Gross Wet Wt	808.3
Gross Dry Wt.	725.9
Tare Wt.	81.2
Net Dry Wt.	644.7
Wt. Of Water	82.4
% Moisture	12.8%
Dry Density	#VALUE!
Descr	iption:
olive	brown
Sandy I	ean Clay
Group	
Symbol	SC


Liquid Limit:	24.2
Plastic Limit:	19.4
Plasticity Index:	4.8
PI 5	




File N∘	SC 4090
Sample N∘	16-7
Date:	2/1/2018
By:	RC


	P.I. SOIL TEST				
	PLASTIC LIMIT				
Determination	1	2	3	4	
Tare N∘	16	12	27		
Gross Wet WT.	13.71	14.87	15.49		
GrossDry WT.	13.28	14.22	14.78		
Tare WT.	10.99	10.96	11.09		
NET DRY WT.	2.29	3.26	3.69	0.00	
WT. OF Water	0.43	0.65	0.71	0.00	
% Moisture	18.78	19.94	19.24	#DIV/0!	


LIQUID LIMIT					
NUMBER OF BLOWS					
33	27	22	15		
4e	5b	3e	5g		
14.24	12.21	16.41	16.15		
12.48	10.70	13.93	13.55		
4.19	4.18	4.28	4.17		
8.29	6.52	9.65	9.38		
1.76	1.51	2.48	2.60		
21.23	23.16	25.70	27.72		








Sample #	
Ht. of Sample	bag
Tare	11
Gross Wet Wt	367.6
Gross Dry Wt.	339.8
Tare Wt.	110.4
Net Dry Wt.	229.4
Wt. Of Water	27.8
% Moisture	12.1%
Dry Density	#VALUE!
Descr	iption:
Dark	Grey
Sandy I	ean Clay
Group	
Symbol	CL-ML









































Project No. SC4090.1 6 August 2018


APPENDIX B


Lyon Tank Slide 3D Orthographical Model (Figures 54 – 58)












APPENDIX C


Summary Results of Stability Analysis (Figures 59 – 71)




48					
44				1	
					s
-0 	 				
8					
2					
2					
8					
4					
0	 				
			and the second s		
			1		
2				N	
8					
4	 				1
+			-		
0					
16	 		1		
		8			
2				5 M	
99					1
	 			-	1 in
4					
0			2		

E3 PROFILE

840			
510			1
836			
832			
828			
824			
820			
816			
812			
808		ļ	
804			
800			
796			
			4.15



 -	CROSS	SECTION	PER	FEBRU	JAR
 =	CROSS	SECTION	PER	JUNE	03





ARY 25, 2017 SURVEY


)3, 2017 SURVEY

CROSS SECTIONS

OF THE LANDS OF SAN LORENZO VALLEY WATER DISTRICT LYON WATER TREATMENT PLANT 365 MADRONE DRIVE BOULDER CREEK, CALIFORNIA APN 081-011-07 JUNE, 2017








Lyon Tank Slope Stability Safety Factor- Cross Section C3- Current Condition - Static


Figure No. 62





Lyon Tank Slope Stability Safety Factor- Cross Section C3- Current Condition - Seismic


136 of 308


Note : The border of light blue and dark blue zones shows the thickness of the future probable landslide. (SF less than 1.1 in Figure No. 63 seismic condition are considered as instable slope.




















Project No. SC4090.1 6 August 2018

APPENDIX D

Some Photos From The Project Site






















Project No. SC4090.3 13 August 2019

SAN LORENZO VALLEY WATER DISTRICT 13060 Highway 9 Boulder Creek, California 95006

Attention: Mr. Rick Rogers

Subject: Geotechnical Investigation

Reference: Lyon Tank Access Road Landslide Repair 365 Madrone Drive Boulder Creek, California

Dear Mr. Rogers:

In accordance with the request of the San Lorenzo Valley Water District (SLVWD), Haro, Kasunich and Associates, Inc. (HKA) have performed a Geotechnical Investigation for the repair of the access road that services the Lyon Tank in Boulder Creek, California.

The accompanying report presents our conclusions and recommendations, as well as the results of the geotechnical investigation on which they are based. A broad soil mass disconnected from the hillside during the winter rain season of 2016/2017 and mobilized downslope leaving a large head scarp that undermined a portion of the access road including Madrone Road. The access road that services the subject water tank crosses over the soil mass in several locations. Portions of the road mobilized along with the soil mass in some locations and in other locations the road was completely buried.

The San Lorenzo Valley Water District (SLVWD) has requested that HKA develop an understanding of the unstable broad soil mass and present geotechnical recommendations for stabilization and reconstruction of the damaged portions of the access road. To better understand the geologic and geotechnical parameters of the project site, HKA completed a field exploration program that included, site reconnaissance, 16 test borings drilled to depths of 7.0 and 51.5 feet below the ground surface (bgs), and laboratory testing for mechanical properties of soil samples collected from within the test borings. The study area was topographically mapped several times by Professional Land Surveyor Paul Jensen. The soil mass continued to mobilize between surveys with most recent map dated February 2018.

Geologic sections were developed using the topographical map along with data collected during the field exploration. A worst case slope stability model of the hillside was created in cross section view by assigning mechanical properties (strength, density, moisture) to the soil layers in the geologic section. The slope stability analysis

was completed with the aid of the computer software program SLOPE/W by GEOSLOPE. A double check of the inputs for the model was completed by back calculating the landslide that already occurred under wet winter conditions without the influence of seismic shaking.

The preliminary results of the analysis were presented to the representatives of the SLVWD. In brief a broad soil mass has disconnected from the hillside from the head scarp down to Hessey Creek. The disconnected soil mass is unstable under wet winter conditions without seismic shaking and will continue to reactivate overtime and creep downslope. The entire disconnected soil mass will be stabilized from the head scarp down to Hessey Creek.

HKA recommends unloading the soil mass by removing the upper 5 (+/-) feet of soil starting below Madrone Road up to the head scarp. The soil mass starting from Hessey Creek up to the head scarp should be stabilized using three rows of buried secant piles or two rows of buried secant walls with a culvert fill slope buttressing the toe. The upper row of secant piles is recommended to be constructed on the hillside approximately halfway up to the head scarp from Madrone Road. The upper row is estimated to be 150 feet long by as much as 40 feet deep. The middle row of secant piles would be constructed along the outboard side of Madrone Road and is estimated to be 200 feet long by as much as 55 feet deep. The lower row of secant piles is recommended to be constructed approximately 20 feet from Hessey Creek and along portions of the existing dirt path. The lower secant row is estimated to be 225 feet long and 50 feet deep. To rebuild and secure the severely damaged portion of the upper access road where the soil mass dislodged from the head scarp, an engineered fill slope is recommended to be constructed from the upper row of secant piles up to the inboard side of the damaged upper road.

Alternatively to the lower row of secant piles, a culvert and fill slope can be constructed to stabilize the base of the slide mass. The culvert will be approximately 8 feet in diameter and 200 feet long. The culvert will control the flow of the Hessey Creek from the upstream limits of the slide down to the existing culvert. The culvert should be backfilled with onsite soils and an engineered fill slope constructed up to Madrone Road.

HKA re-iterates that the disconnected soil mass downslope from Madrone Road is to remain on site. We anticipate a temporary road will need to be constructed to install the upper and lower row of secant piles on the hillside. Additional working meetings with structural and civil designers, specialty contractors, and SLVWD are anticipated, in order to develop viable working drawings.

If you have any questions concerning the data or conclusions presented in this report, please call our office.

Respectfully Submitted,

HARO, KASUNICH AND ASSOCIATES, INC.

Ashton Buckner, E.I.T. Staff Engineer Moses Cuprill C.E. 78904

AB/MC/rh Copies:

4 to Addressee 1 pdf to Rick Rogers<u>rrogers@slvwd.com</u>

TABLE OF CONTENTS

GEOTECHNICAL INVESTIGATION	1
1. Introduction	1
2. Purpose and Scope	7
3. Field Exploration and Laboratory Testing	8
3.1. Field Exploration	8
3.2. Madrone Road Condition	11
3.3. Laboratory Testing	11
4. Site Characterization	12
4.1. Soil Layers Description	12
4.2. Groundwater	14
4.3. Soil Properties	16
5. Geotechnical Related Seismicity	17
6. Quantitative Slope Stability Analysis	19
6.1. General Methodology	19
6.2. Quantitative Analysis with GeoStudio Slope/W	
6.3. Seismic Coefficient	
6.4. Geometric Assumptions	
6.5. Slope Stability Models for Studied Site	
6.6. Slope Stability Conclusions	33
6.7. Limitations of Analysis	
7. Constructability and Estimate of Repair Options	
7.1. Three Rows of Secant Piles	37
7.2. Two Rows of Secant Pile and Buttress Fill Slope	
8. Building Codes and Site Class	38
9. Recommendations for Design and Construction	38
Site Grading (Fill/Cut Slopes)	
Secant Pile Walls	
Drilled Piles for the Secant Pile Wall	
Active and Passive Pressures	52
Driven Piles	
Surface & Subsurface Drainage	54
Monitoring	
Plan Review, Construction Observation and Testing	56
LIMITATIONS AND UNIFORMITY OF CONDITIONS	57

TABLE OF CONTENTS (continued)

APPENDIX A	
Site Vicinity Map	Figure 1
Geological Site Map	
Boring Site Plan	
Key to Logs	-
Logs of Test Borings	
Particle Size Distribution Test Results	
Plasticity Index	•
Direct Shear Results	
Variation of Blows, Saturation and Void Ratio vs Depth	0
APPENDIX B	
Lyon Tank Slide 3D Orthographical Model	Figures 54 - 58
APPENDIX C	
Summary Results of Stability Analysis	Figures 59 -71
APPENDIX D	
Secant Wall Site Plan	Figure 72
Culvert Site Plan	
Proposed Culvert Limits	-
Secant Wall Option	
Culvert Buttress and Secant Wall Option	
APPENDIX E	

Some Photos From The Project Site

GEOTECHNICAL INVESTIGATION

1. Introduction

This report presents the findings, conclusions and recommendations of our Geotechnical Investigation for the Lyon Tank Access Road Landslide Repair Project. The Tank site is located at the end of Madrone Drive in Boulder Creek, California (see Site Vicinity Map, Figure 1 in Appendix A). A broad soil mass disconnected from the hillside and mobilized downslope. We will refer to the disconnected soil mass as the "landslide" from here forward. The slow moving landslide, which initially activated in the winter of 2017, has resulted in significant damage to the only access road to the SLVWD Lyon Water Tank and Water Treatment Facility. The water tank is the main water supply for residents within the San Lorenzo Valley Water district. The landslide is located between the upper most road that provides access to the base of the Lyon Tank which we will refer to as the "upper road" (that traverses the head scarp) and Hessey Creek, located about 200 feet downslope and to the east. A 160 foot long portion of Madrone Road which we will refer to as the "lower road" crosses the active landslide deposit and has been damaged. This report presents the results of our field investigations, laboratory testing, static and seismic slope stability analysis, and development of geotechnical design criteria and recommendations for stabilization of the landslide.

Survey Maps with cross sections of the landslide area were prepared by Paul Jensen, and provided for our use. The landslide maps, with cross sections, are dated February 2017, June 2017, October 2017, and February 2018. The landslide

area was surveyed four times to assist in evaluating the movement of the active landslide and to define potential toe of slip surfaces. The locations of exploratory borings indicated on the maps were surveyed by Mr. Jensen. The ground surface elevations at each boring location on the landslide deposit vary depending on the map date due to the ongoing movement of the landslide.

The Lyon Tank lower road crosses the landslide site immediately before a hairpin turn up to the tank. Just beyond the hairpin turn, the road forks. The lower fork of the road or the "upper road" leading to the tank has been damaged and is unusable due to landsliding. Before the hairpin, a 160 foot length of the lower road has been damaged by landsliding and temporarily repaired. The initial movement of the landslide was first observed by Haro Kasunich and Associates, Inc. (HKA) on 13 February 2017 during an on-site meeting with SLVWD Operations Management staff. We were informed ground and asphalt cracks were first observed in January 2017 after heavy rainfall at the site. At the time of our 13 February visit, the west lateral edge of the landslide and access road had dropped 2" to 4" and a 2' to 3' wide asphalt patch had been placed and compacted from the north to south side of the road to bridge the damaged area. The patch covered over a zone of 1" to 2" wide cracks in the asphalt. Soil cracks with a few inches of vertical displacement extended up the slope toward the upper access road.

A 15-inch diameter culvert on the surface of the slope below the access road on the west side of the slide was observed to be discharging water and angular gravel. The gravel was part of a gravel blanket drain installed during grading for construction of the access road to the Water Treatment Plant. The landslide movement dislodged and broke the pipe, allowing the gravel to flow into the culvert and then to be discharged out the end of the culvert.

In addition to the access road landslide, surficial sliding on the upper slope between the Lyon Tank and Water Treatment Plant was first observed by HKA on 13 February 2017. The slumps occurred about mid slope in several areas. On 15 February, the portion of the upper slope where slump slides occurred was covered with plastic sheeting and sandbags tied by rope to anchor the plastic and divert incident rainfall from the slope to the asphalt road below.

The access road landslide continued to move after heavy rainfall and by 22 February the east side of the upper access road down dropped several inches and numerous 1" to 2" wide cracks along a 50 foot long portion of the road had developed as the slide moved downslope. By Sunday 26 February, the landslide moved significantly and a 70' long portion of the road collapsed at the top of the landslide. The landslide left a 1' to 5' high head scarp at the inboard side of the lower of the upper roads. The west end of the access road dropped about 4 feet and subsurface water was emanating from the landslide scarp at the access road. Buckling of the pavement was observed on the downslope portion of the access road crossing the landslide. In early March, the entire landslide surface from the access road to the slide head scarp and side scarps was covered with plastic sheeting and rope tied sandbags to prevent incident rainfall from infiltrating into the covered part of the landslide deposit.

Several large trees on the landslide deposit were observed to be leaning significantly and posed a danger to the field investigation. The district hired a tree service to remove the worst of the leaning trees, which were removed in March and/or April 2017. On the west side of the access road, which had dropped about 6 feet, the district built a temporary gravel fill slope to provide vehicle access to the Water Treatment Plant and Lyon Tank for workers who perform daily maintenance and monitoring duties required to continue supplying potable water to District customers.

The movement of the landslide continued until early May 2017 when our initial borings were drilled. The plastic sheeting had been removed prior to our drilling and the landslide was re-surveyed in May. At that time the west side and the upper portion of the landslide had dropped from 6' to 8' and a bulge had developed on the slope between the creek and the access road. The west side of the section of the access road crossing the landslide had dropped 6' to 7'. The east side of the access road on the landslide had buckled due to uplift pressure from the slide and the curb drain inlet on the inboard side of the road was damaged by the landslide. The east side of the slide is buttressed by a previous road repair in 1986 which replaced a failed wood crib wall. The repair consisted of removal of soil on the

slope and in the stream channel, installation of a large culvert in the stream, and placement and compaction of rock and soil backfill on the slope and road.

After our initial borings, a path was cleared on the slope below the access road to provide access for a drill rig to advance an additional 4 borings on the landslide deposit below the access road and 1 boring on the landslide deposit above the access road. Adjacent to Boring B-10 on the slope between the access road and Hessey Creek, a constant flow of water seeping from the toe of a steep slope was observed.

A fourth survey of the site in October 2017 indicates the upper landslide headscarp had increased to 6' to 10' high and the landslide had moved up to 4 feet horizontally toward the creek since the first survey (which had been done after significant movement had already occurred).

New longitudinal cracks in the upper road to the Water Treatment Plant were reported by the district in late October 2017. The cracks on the upper Water Treatment Plant parking area were generally 1/32" to 1/16" wide. One asphalt crack was 1/2" wide. We returned to the site and drilled 4 supplemental borings in the Water Treatment Plant parking area to assess the subsurface conditions underlying the parking area and the slope descending to the Lyon Tank.

Based on geological review of published regional geologic maps of the area, we found a fault zone traverses through the project area. The historical presence of the fault zone in the area likely sheared and weakened the earth materials during geologic time and likely also disrupted groundwater flow. The landslide slip surface has extraordinarily weak earth materials along it with very low residual strengths; in part because of historical shearing during previous instability including the 2017 re-activation. The above factors complicate landslide repair because of difficulty in maintaining safety during any mass excavation of the landslide materials. The landslide mass is expected to continue to be unstable and may expand should nothing be done to mitigate the existing condition.

HKA performed field explorations (test borings); 1) to profile the subsurface earth materials; 2) obtain samples; and 3) perform a laboratory testing program. On September 15th, 2017, a memorandum was prepared by HKA including discussion about slope improvement feasibilities. In this report, we present results of the geotechnical analysis which is limited to the 2017 landslide. The proposed mitigation solution is to install three rows of secant piles, one along the outboard side of the middle road, another on the hillside midway upslope to the upper road, and lastly, another row offset 20 feet from Hessey Creek (lower row). Alternatively, the lower row of secant piles may be replaced with a culvert plus fill slope repair. The three rows of piles should be advanced into bedrock a minimum of 15 feet. A temporary road will need to be graded to install the upper and lower row of secant piles.

The upper road is recommended to be re-constructed by grading an engineered fill slope with a slope gradient of 2H:1V with its toe at the upper row of secant piles and crest along the outboard board side of the upper road. To re-construct the travel way of the upper road, the fill slope would continue at 2%-5% from its crest to the inboard cut slope along the upper road.

The culvert and fill slope repair would consist of installing a new 8 feet diameter culvert and a new engineered fill slope along the stream channel. The new culvert would be connected to the existing culvert east of the landslide. Hessey Creek splits into two streams at station 1+40. The culvert will need to be designed to accommodate this channel split. Grading will include placement and compaction of rock and soil backfill for the keyway and the fill slope ascending to the lower road and connection of the new fill slope to the existing fill slope east of the landslide.

2. Purpose and Scope

Our scope of services included review of existing geotechnical and geologic information related to the site, drilling and sampling in sixteen (16) exploratory borings, laboratory testing, and engineering analysis. The key focus was evaluation of the unstable landslide mass using the projected failure mode geometry; and evaluation of a practical method to improve the slope. The purpose

of these services is to provide information and geotechnical recommendations relative to:

- Subsurface soil conditions;
- Groundwater conditions;
- Seismic considerations;
- Relative stability of landslide deposits and in-situ earth materials within the slip-out area (under static loading conditions);
- Earthwork recommendations;
- Construction cost and feasibility of both design options.

3. Field Exploration and Laboratory Testing

3.1. Field Exploration

The field investigation has been completed at the site by drilling 16 boreholes over a period of approximately 6.5 months. Twelve boreholes were drilled at the 2017 landslide between the Lyon Tank and the existing creek at the base of the slope. Boreholes 13 to 16 were drilled at the top of the slope south of the Lyon tank. B-1 to B-12 were drilled within the landslide area. The specifics of the drilled boreholes are presented in Table 1.

No.	Drilling Date	Depth (ft)	Approximate Top Elevation (ft)	Approximate Bottom Elevation (ft)
B-1	May 4, 2017	51.5	819.0	767.5
B-2	May 4, 2017	31.5	819.5	788.0
B-3	May 23, 2017	36.5	815.5	779.0
B-4	May 23, 2017	46.5	822.5	776.0
B-5	May 24, 2017	41.5	847.5	806.0
B-6	May 24, 2017	33.0	851.5	818.5
B-7	May 24, 2017	30.0	810.8	780.8
B-8	July 24, 2017	46.5	797.9	751.4
B-9	July 24, 2017	41.5	792.5	751.0
B-10	July 25, 2017	35.0	778.3	743.3
B-11	July 25, 2017	35.0	779.7	744.7
B-12	July 25, 2017	32.5	838.3	805.8
B-13	November 22, 2017	32.5	888.5	856.0
B-14	October 22, 2017	7.0	888.5	881.5
B-15	November 22, 2017	31.5	888.0	856.5
B-16	November 22, 2017	21.5	888.5	867.0

Table 1: Drilled Boring Specifications

Representative soil samples were obtained from the exploratory borings at selected depths, or at major strata changes. These samples were recovered using a 3.0 inch O.D. Modified California Sampler (L), or by a 2.0 inch O.D. Standard Terzaghi Sampler (T) i.e. SPT sampler. The SPT blow counts with large sampler (N_L) should be reduced by a specific reduction factor to convert to Standard SPT blow counts (N_S). The correlation between these two values are presented below:

$$N_{\rm S} = N_{\rm L} \left[(WH)/(623N \cdot 0.762m) \right] \left[(50.8^2 - 34.9^2)/(D_0^2 - D_i^2) \right]$$

(Equation 1)

The penetration blow counts noted on the boring logs were obtained by driving a sampler into the soil with a 140-pound hammer dropping through a 30-inch fall.

The sampler was driven up to 18 inches into the soil and the number of blows counted for each 6-inch penetration interval. The numbers indicated on the logs are the total number of blows that were recorded for the second and third 6-inch intervals, or the number of blows that were required to drive the penetration depth shown; when high resistance was encountered.

Given the hammer weight and the hammer drop height used for both samplers are the same, the difference of blow counts is because of outer and inner dimensions. For the Modified California Sampler with 3 inch (76.1mm) O.D. and 2.4 inch (61mm) I.D. the reduction factor of 0.65 will be used in our project to convert N_L to Ns. In Figures 48 & 49, Appendix A, variation of field SPT blows versus depth in different boreholes are shown. In these graphs, the large sampler blow counts (N_L) were converted to standard SPT blow counts (N_s).

The soils encountered in the borings were continuously logged in the field and visually described in accordance with the Unified Soil Classification System (ASTM D2488). The Logs of Test Borings are included in Appendix A of this report. The logs depict subsurface conditions at the approximate locations shown on the Boring Site Plans; subsurface conditions at other locations may differ from those encountered at the explored locations. Stratification lines shown on the logs represent the approximate boundaries between soil types; actual transitions may be gradual.

3.2. Madrone Road Condition

Assess to the site for large construction vehicles and equipment will need to be evaluated by contractors. Madrone Road intersects with South Redwood Drive and Boulder Brook Drive with a sharp turn radius that will make mobility difficult for large vehicles. Smaller vehicles may need to be used which will slow construction down.

Madrone Road itself is cut into the hillside with an outboard fill edge that appears to show no signs of distress, movement, or landsliding. Multiple locations along Madrone Road have large redwood trees limiting the road width to approximately 10 feet wide. The asphalt surface will be heavily damaged as a result of construction.

If areas are identified to need improvement, HKA will prepare a geotechnical work plan to investigate and provide recommendations for improvement of the road.

3.3. Laboratory Testing

The laboratory investigation was directed toward a quantitative and qualitative evaluation of the physical and mechanical properties of the subsurface materials at the project site.

Selected samples retrieved from the exploratory borings were returned to the laboratory for examination and testing to evaluate their physical characteristics and

engineering properties. Below is a description of the series of tests performed in our laboratory on selected samples retrieved from the field investigation. These tests were performed in accordance with the standards of the American Society for Testing and Materials (ASTM) and contemporary geotechnical engineering practices. Samples were tested to measure moisture content and unit weight, plasticity, grain size distribution, and shear strength. The results of the laboratory tests are presented in Appendix A and as appropriate adjacent to the corresponding sample designations on the boring logs.

Table 2: List of Laboratory Tests

TEST	Standard Code
Atterberg Limits	ASTM-D 4318
Grain Size	ASTM-D 421, D 422
Specific Gravity	ASTM-D 857
Water Content	ASTM-D 226
Classification	ASTM-D 2488
Direct Shear	ASTM-D 3080

4. Site Characterization

4.1. Soil Layers Description

Based on site visits and observation of retrieved samples during drilling operations, the subsurface soils consist of loose to medium dense, moist to wet, brown to grey silty sand, clayey sand, and sandy clay overlaid on weathered bedrock. The bedrock consists of very dense light brown weathered Lompico Sandstone or Monterey Formation. In boreholes B-1 to B-12, bedrock was encountered at various depths ranging from 26 to 46 feet below ground surface. This variation is likely a result of tectonic pressures that has changed the bedrock elevation, differential weathering, and the possibility of modification by landslide mass movement.

On portions of the existing slope, man-made grading (cut and fill) has changed the soil thicknesses. In some boreholes, the soils encountered suggest silty sand was historically used as fill during historical grading operations that created the old reservoir at the site and/or during grading for the Lyon Tank that was constructed to replace the reservoir about 25 years ago. According to SPT blow counts, this loose to medium dense fill material is suspected to have been placed as uncompacted fill.

Based on our observations, some of the undocumented fill material is comprised of soils excavated from elsewhere on the site, making it difficult to distinguish between the two. Some boreholes were not located within the 2017 landslide area, including boreholes B-5 to B-7. The soil layers in B-1 to B-4 and B-8 to B-12 are within the landslide. The landslide mass found in these boreholes varied in thickness. The maximum 2017 landslide mass thickness observed in B-1 was 38 ft (\pm).

Based on the retrieved soil samples, there are areas where native soils exist above the bedrock that did not move as part of the 2017 landslide mass. These soils lie between the landslide mass and the bedrock. In Table 3, the Soil Layer Conditions after the 2017 Landslide are presented. We note, boreholes B-13 to B-16 were drilled outside of the landslide area. Therefore, the soil layer condition for these four boreholes are not described in Table 3. The landslide and native soil layers observed during drilling of the different boreholes is also presented graphically as a 3D landslide surface within the hillside. This is shown (named as Case 1) in figures 55 & 56 in Appendix B of this report.

No.	Hole Depth (ft)	Hole Top Elevation (ft)	2017 Landslide Mass Thickness (ft)	Thickness of undisturbed native soil below landslide layer to bedrock (ft)	Bedrock Depth (ft)	Bedrock Elevation (ft)	Water Surface Depth (ft)	Water Surface Elevation (ft)
B-1	51.5	819.0	38	7	45	774	-	-
B-2	31.5	819.5	22	8	30	789.5	-	-
B-3	36.5	815.5	25	6	31	784.5	5	810.5
B-4	46.5	822.5	30	16	46	776.5	4	818.5
B-5	41.5	847.5	0	45	45	802.5	15	832.5
B-6	33.0	851.5	0	32	32	819.5	-	-
B-7	30.0	810.8	0	27	27	783.8	-	-
B-8	46.5	797.9	32	6	38	759.9	12	785.9
B-9	41.5	792.5	20	19	39	753.5	4	788.5
B-10	35.0	778.3	24	14	38	740.3	6	772.3
B-11	35.0	779.7	19	15	34	745.7	25	754.7
B-12	32.5	838.3	30	1	31	807.3	-	-

Table 3:Soil Layer Conditions After 2017 Landslide Event

4.2. Groundwater

At the time of drilling, water was encountered in some boreholes at different depths. The significant difference of water level indicates that the observed water is perched water and mainly results from rainwater infiltrating at the site and at neighboring highlands and mountain slopes that then flows through permeable soils that overly the bedrock. The 2017 landslide event caused some parts of surficial soils to become scrambled and fractured, thus a change in permeability of these soil layers resulted. The wetness of the recovered interface soil samples at the slip plane contact zone indicate much higher moisture content percentage than in the underlying weather bedrock, as a result of groundwater following the slip surface fractures. Figures 50 to 53 in Appendix A show variation of soil saturation degree and void ratio versus depth in the different boreholes. These values were calculated using laboratory soil samples measuring dry density and moisture content.

Groundwater conditions vary with environmental variations and seasonal conditions such as frequency and magnitude of rainfall patterns. Seasonal groundwater fluctuations should be considered in design and construction. We recommend the contractor alert the engineers of actual groundwater levels, if encountered during construction, to determine groundwater impact on the construction procedures and on design. Inflow of groundwater during excavation could lead to significant construction problems and unsafe working conditions for personnel. If not properly controlled, groundwater inflow could also contribute to backslope failure of temporary excavations resulting in great bodily injury or death.

4.3. Soil Properties

Topographical maps of the site were provided four times by Paul Jensen to document the continuing movement of the landslide mass. Maps were provided February, June, and October 2017, and February 2018.

The cross section locations as shown in Appendix C, were developed by HKA using the topographic maps prepared by Paul Jensen. These cross sections were used as the basis for our slope stability analysis. The most critical cross section with the deepest landslide plane was selected to carry out the slope stability evaluation. We utilized the exploratory borings from our field investigation to develop a subsurface profile model. Four (4) different soil types were developed in these analyses.

The soil boundaries indicated on the cross sections are based on; 1) the engineer's observations and soil evaluations in the field; 2) the results of field Standard Penetration Tests (SPT) conducted during soil sampling; and 3) the engineer's laboratory test results. The soil boundary lines were projected between and beyond the location of the test borings in both directions, presuming a straight line; based on experience and engineering judgement in the site vicinity. The model is simplified and based on extrapolation of information obtained during field and laboratory testing. Changes in the soil stratum are likely more gradual than indicated in our models.

Strength parameters for the different soil types were determined using standard penetration test (SPT) results, laboratory direct shear results, and engineering judgment. The 2017 landslide was modeled using soil and bedrock parameters determined by laboratory and field test results in the way the landslide occurred and then the physical parameter accuracy was calibrated. In Table 3, in-situ landslide silty sandy layer (Soil 1), in-situ native silty sandy layer (Soil 2), and bed rock (Soil 3). The current condition of the impacted hillside was modeled using Soil 1 to Soil 3. For the improved slope conditions, for those parts that were filled by compacted in-situ soil, Compact Fill (Soil 4) was introduced and used in the model.

Soil No.		Cohesion (psf)	Friction Angle (deg)	Unit Weight (pcf)
1	Residual Soil / Landslide Soil	150	22	85
2	Native Soil	400	28	110
3	Bedrock	3,000	40	125
4	Compacted Fill	1,500	37	115

Table 4:Slope Stability Soil Strengths

5. Geotechnical Related Seismicity

The improvements should be designed in conformance with the most current California Building Code (2016 CBC). For seismic design, the soil properties at

the site are classified as **Site Class** "**D**" based on definitions presented in Section 1613.3.2 in the 2016 CBC that refers to Chapter 20 of ASCE 7. The longitude and latitude were determined using a satellite image generated by Google Earth. These coordinates were taken from the portion of the proposed improvements with the slightly higher mapped peak ground acceleration:

Longitude = -122.135312, Latitude = 37.125984

The coordinates listed were used as inputs in the OSHPD Seismic Design Maps created by California's Office of Statewide Health Planning and Development (OSHPD) to determine the ground motion associated with the maximum considered earthquake (MCE) S_M and the reduced ground motion for design S_D . The results are as follows:

<u>Site Class D</u>

S_{MS}= 1.500 g S_{M1}= 0.902 g S_{DS}= 1.000 g

S_{D1}= 0.601 g

A maximum considered earthquake geometric mean (MCE_G) peak ground acceleration (PGA) was estimated using the Figure 22-7 of the ASCE Standard 7-10. The mapped PGA was 0.527 g and the site coefficient F_{PGA} for Site Class D is 1.0. The MCE_G peak ground acceleration adjusted for Site Class effects is PGA_M = $F_{PGA} * PGA$

6. Quantitative Slope Stability Analysis

Stability analysis was performed on a cross section cut through the project site. The selected cross section location was selected by HKA's Project Geologist. The slope stability analysis was performed to quantify the instability associated with the occurrence of the 2017 landslide using the 2017 slope geometry; and also to analyze the potential for failure of the proposed improved slopes under static winter conditions and seismic loading conditions.

6.1. General Methodology

Slope failures or landslides can cause problems including encroachment, property damage, personal injury, or even death. Failures of slopes occur when stress acting on the soil mass is greater than its internal strength (shear strength). A slope is considered stable when the strength of its soil mass is greater than the stress field acting within it. Some common variables influencing stress are gravity (steeper slopes), hydrostatic pressure (perched groundwater), soil surcharge pressures (overburden), concentrated surcharge at up slope (buildings, vehicles on the road and etc.), and seismic surcharge (earthquake shaking).

Various methods of analyzing stability of slopes yield a factor of safety. A factor of safety (FS) is determined by dividing the resisting forces within the slope soils (earth materials) by the driving forces within the slope (stress field). A FS greater

than or equal to 1.0 is considered to be in equilibrium. A FS less than 1.0 is a potentially un-stable slope condition. HKA considers the potential for instability of a slope or hillside to be low with a FS against sliding greater than or equal to 1.10 under seismic loading conditions and 1.50 under static loading conditions. Some governing agencies including Santa Cruz County Environmental Planning and the Mining Safety and Health Administration (MSHA) require slopes to have a FS equal to or greater than 1.20 to be considered seismically stable.

6.2. Quantitative Analysis with GeoStudio Slope/W

The analysis was completed with the aid of GeoStudio's Slope/W computer software version 2018 R2. A model for the section was defined with the input parameters consisting of slope geometry, soil properties, loading conditions, and pore water pressure ratio. Each model was evaluated under static and seismic loading. Mohr-Coulomb material model was used to define the soil properties. The analysis calculates the factor of safety against sliding for the failure surface(s).

Trial failure surfaces for the analyses consisted of circular type failures. Morgenstern-Price analysis method is used to determine normal and resistive forces in each slice. The forces in each slice are then summed up for total force acting on the mass. In circular (general) failure mode stability assessment, the computer program assumes many failure surfaces using initiation and termination points on the ground surface selected by the user. These chosen points represent the toe and scarp of each potential landslide in relation to the assumed failure surfaces. The critical trial failure surface from the pseudo static analysis condition was selected as the projected failure surface in the development of design parameters.

6.3. Seismic Coefficient

The ground motion parameter used in pseudo static analysis is referred to as the seismic coefficient "k_h". The selection of a seismic coefficient has relied heavily on engineering judgment and professional publications. The 2016 California Building Code (CBC) provides site class definitions for seismic design of structures. Based on these definitions, a review of the site soil properties presented on our soil boring logs, the site is classified Site Class D, in accordance with ASCE 7 (with March 2013 errata). The current version of the California Building Code contains reference to maps of peak ground acceleration (PGA) based on site latitude and longitude. For this project the mapped PGA is 0.527g. The PGA is multiplied by a factor related to the seismicity of the site to obtain the seismic coefficient.

Two empirical charts developed by Blake and others are currently available for estimating the seismicity factor in Figure 1 and Figure 2 of Chapter 5 Analysis of Earthquake-Induced Landslide Hazards in CGS *Special Publication 117 Guidelines for Analyzing and Mitigating Seismic Hazards in California 2008.* Each chart represents a minimum allowable displacement of the embankment or slope. Figure 1 is a minimum allowable displacement of 2 inches and Figure 2 is a minimum allowable displacement of 6 inches. In general, the more displacement

the slope can tolerate, the lower the seismicity factor or percentage of PGA can be calculated. A simple way to think of it is if a maximum of 0 inches of displacement is tolerable then $k_h = 100\%$ of PGA would be calculated. If the slope can tolerate a maximum of 6 inches of movement then k_h would be much closer to 50% of PGA. If the k_h value used results in a factor of safety less than 1.2 for seismic loading conditions and 1.5 for static, a Newmark analysis should be completed.

For this analysis, a maximum displacement of 2 inches within the failure mass was presumed to be tolerable. This presumption is typical for stability analysis involving structures or permanent improvements. The seismicity factor was estimated to be 54.0% of PGA or $k_h = 0.54 * 0.527g = 0.285g$.

6.4. Geometric Assumptions

Six (6) geometric sections (A3, B3, C3, D3, E3 & F3) were prepared by HKA's Geologist using the topographic map and ground surface profiles prepared by the Surveyor. For our analysis, the failure surface was focused along the worst case slope cross section (C3) which has the deepest impacted layers in the 2017 landslide event. Three (3) soil layers were used for the 2017 Landslide Event Recreation model, and for the Current Condition model. Nearest the ground surface, a layer of residual soil and landslide soil exists. The landslide soil is that portion of the layer within the landslide slip circle. Beneath the residual soil and landslide layer, the native soil layer, very dense bedrock is encountered. A fourth soil

layer was added to the Three Secant Walls model and the Culvert and Two Secant Walls model. This fourth soil layer represents the compacted engineered fill to be used in the slope repair and reconstruction.

Perched water was observed in some boreholes at different depths, and in some boreholes, no water was encountered. The landslide happened after an above average rainy season, and landslide movement resulted in ground fractures that act as groundwater conduits. Therefore, the soil has the potential to become partially saturated. In order to consider the effect of rainfall in creating pore water pressure, an "Ru" coefficient is considered for the residual soil and landslide soil layer, and also for the deeper native soils. Ru simply models the pore pressure as a fraction of the vertical earth pressure for each slice. Each soil can have a different Ru value. In our project model, the Ru for the residual soil and landslide soil layer was designated as 0.4, and the Ru for the deeper native soils was designated as 0.5.

6.5. <u>Slope Stability Models for Studied Site</u>

The project slope has been modeled in four (4) conditions and each model has been evaluated in both static and seismic conditions. The models are introduced as follows:

a. 2017 Landslide event re-creation; Based on engineer's judgment of the landslide geometry.

- b. Current condition of the existing slope after the landslide;
- c. Improved slope by installing three rows of secant piles, one along the outboard side of the lower road, another on the hillside mid-way to the upper road, and the last along the toe of the slide near Hessey Creek. The model also considers removal of 5 (+/-) feet from the surface of the landslide from the upper road to downslope from the lower road. After the soil is removed and off hauled, an additional 5 (+/-) feet below this is also removed and redensified as engineered fill. An engineered fill slope with a gradient of 2H:1V is constructed with its toe starting at the upper road. The engineered fill extends below the upper road restoring access.
- d. Alternatively to model "c", improved slope installing two rows of secant piles, one along the outboard side of the lower road and another on the hillside mid-way to the upper road. Construct a toe buttress along Hessey Creek consisting of an 8 feet diameter culvert and fill slope ascending up to the lower road. The model also considers removal of 5 (+/-) feet from the surface of the landslide from the upper road to downslope from the lower road. After the soil is removed and off hauled, an additional 5 (+/-) feet below this is also removed and redensified as engineered fill. An engineered fill slope with a gradient of 2H:1V is constructed with its toe starting at the upper road. The engineered fill extends below the upper road restoring access.

The slope stability safety factor for the above models in both static and seismic conditions are shown in Appendix C graphically and tabulated in this section of the report.

2017 Landslide Event Recreation

Distinguishing the landslide mass layer from native soil is one of the most important goals of the project investigation. In some areas the landslide mass and native soil layers are the same, but some native soil was below where the 2017 landslide slide plane formed. If desired, further exploration involving large diameter exploratory borings would be required to absolutely define the landslide mass thickness throughout the landslide area. In order to approximate the thickness of the landslide mass and native soil thicknesses, and also the depth to bedrock in each borehole, laboratory and field test results have been considered. Borehole logs and the soil samples retrieved from drilling were observed as well. Then a model of the 2017 slope was estimated. In order to select the soil parameters most accurately, the soil parameters have been adjusted in a way that the 2017 landslide mass thickness depicted in the model matches the 2017 landslide layer thickness that was defined by HKA. The achieved (adjusted) soil layers' parameters were used in the other models. The results of the slope stability for this condition can be seen on Figures 60 & 61 in Appendix C.

Current Condition Slope Stability Evaluation

In order to determine the future stability of the existing slope which contains the

existing active landslide layers, the current condition of the slope has been modeled using the cross section C3 provided by Project Surveyor. Stability safety factors under static and seismic conditions have been evaluated. One of the most important results of current condition slope modeling is to evaluate the behavior of the native soil overlaid on the bedrock and to understand if the native soil will participate in future landsliding under design conditions and if the answer is yes, then how deep will be the future slope failure plane be?

Figures 62 and 63 in Appendix C show the slope stability safety factors for the current condition. The results show the existing landslide mass is unstable under the static condition (i.e. near a factor of safety of 1.0), as can be seen in Figure 62 in Appendix C. The results also show that in a probable future earthquake event, the existing slope will likely fail, as can be seen in Figure 63 in Appendix C. Our figure depicts the worst case (i.e. lowest factor of safety) landslide. Note that the analysis indicated multiple failure surface extending as deep as the top of bedrock. Therefore, slope stabilization should be considered at least as deep as the top surface of the bedrock.

Discussion about Slope Stability Improvement Options

Several alternative methods to improve the existing slope were assessed. As discussed earlier, in a future probable earthquake event, deep landsliding is expected. The in situ native soil layers above the bedrock will become part of the landslide. The bedrock was encountered in B-1 and B-2 at 45 feet and 30 feet

respectively. Because the depth of the probable landslide is significant, some of the alternative methods are likely not practical or make the stabilization very costly. HKA previously submitted a memorandum letter on September 15th, 2017 that discussed several slide repair options and their feasibilities from a geological and construction perspective. These options, including the three rows of secant piles option, are presented briefly as follow:

- Remove and Replace The Entire Slide Mass as Engineered Fill; This method is not practicable because the existing saturated landslide mass materials are not qualified in their in-situ condition for use as engineered fill; and there is little to no room onsite for material conditioning (moisture conditioning or drying back as needed) or hauling the removed soil offsite for storage and conditioning.
- Dewater Slide Mass and Stabilize Road; This is not considered feasible because it is difficult to locate and isolate the source of subsurface water; Moreover, the existing slope is not stable seismically even under dry soil conditions as shown in Figure 61.1.
- Tieback Soil Pin Pile Walls Below Both the Upper and Lower Roadways; This option is likely to be very costly and difficult to construct.
 Tiebacks will be very long in order to fully penetrate the landslide zone and extend a sufficient length into the stable bedrock zone to provide

stabilization. Drilling long inclined tieback holes is difficult. They may need casing to prevent the hole wall from collapsing where it is within the landslide mass. Landslide soil layers can not provide arching stability and will collapse between the pin piles. The wall would need to be installed very deep and seated on the bedrock. Access roads to support drilling equipment would need to be constructed.

NEW Improved slope; installing three rows of secant piles. Install three rows of secant piles: one along the outboard side of the reconstructed lower road (middle), on the hillside mid-way to the upper road (upper), and the third one offset approximately 20 feet from Hessey Creek (lower). Constructing engineered fill slope from upper row of secant piles to inboard side of reconstructed upper road restoring access and road shoulder.

If the goal is to stabilize the existing slope containing the landslide mass, three rows of secant piles should be installed which extend to a depth with at least a minimum 15 feet embedment into the bedrock. The landslide soil hasn't enough strength to stand between pin piles or widely spaced piers based on principles of arching. Therefore, zero spacing between piles is a requirement. Secant piles in this case are vertical piling that are installed next to each other with no space between each adjacent piles. The secant pile wall is constructed using a series of closely spaced drilled shafts filled with reinforced concrete. The piles can also be driven. However, driving the piles into very dense bedrock can be challenging or impractical. Also, if cast-in-place piles are designed for the project, boreholes in the landslide mass are expected to need casing, or other means such as ground improvement methods, or by grouting the hole and re-drilling though the grout in increments, to prevent the sidewall soils from collapsing into the drilled borehole.

Based on the slope stability results, secant pile 1 and 2 should have minimum 38,000 pounds per linear foot of wall (plf) lateral capacity and secant pile 3 should have a minimum 30,000 plf lateral capacity. For preliminary design purposes it can be assumed the resultant force acts at a location 2/3 the depth to the bedrock within the overburden soil. For practical applications, the actual location of the resultant should be determined by HKA at several sections along wall profile. In Figures 64 & 67 in Appendix C, slope stability safety factors under both static and seismic conditions are presented. Based on the slope stability evaluation results, the safety factors for both static and seismic conditions are greater than the minimum acceptable limits, which means the upper and lower landslide mass will be stabilized with three rows of secant piles.

For the project slope stability analysis, the most critical cross section with deepest landslide material has been considered which requires installation of long and deep secant piles. The length of the piles will be reduced when moving toward the flanks (sides) of the landslide mass. In order to get a better understanding, a 3D view of the slope and potential landslide layers in the boreholes (case 2) are presented in Figures 57 to 58 in Appendix B. The top 5 (+/-) feet of soils from just upslope from the upper row of secant piles to approximately 50 feet below the middle secant pile row is proposed for removal permanently, as shown in Figure 64 and 65 in Appendix D. These soils should be temporarily stockpiled in an approved location by HKA for re-use. An additional 5 (+/-) feet of soil below the removed soils will also be removed (10 feet total) and redensified back into place. The stockpiled soils, if dried back or moisture conditioned as needed, may be re-used as engineered fill during construction of the fill slope that will support the upper road. The remaining soil left over should be off hauled or placed as engineered fill in a location on-site approved by HKA. The material should not be placed on the landslide mass below the lower row of secant piles as it can exacerbate instability of this soil mass.

By using this method two positive things with respect to landslide resistance are accomplished. The first is the existing bulging landslide soil mass will be removed from the upslope area effectively un-loading this portion of the hillside and reducing the driving force acting on the landslide mass. The second is, if the removed landslide mass can be dried back to near optimum moisture content it can be re-used as engineered fill during construction of the fill slope that will restore the travel way and shoulder of the upper road.

- Improved Slope: installing two rows of secant piles and culvert. Install culvert in stream and excavate slide mass; place and compact excavated

spoils over pipe; construct upper and middle secant walls to stabilize upper and lower roadway;

This option is feasible and physically practical, but may not be permitted by regulatory agencies if another option is deemed less environmentally damaging. This solution for deep landslide stabilization consists of a combination of feasible methods such as improving the drainage system for the site, excavating and removing the upslope area of the landslide mass soils then placing the excavated soil at the lower parts of the slope over a new culvert placed in the streambed, then recompacting that soil to achieve a compacted fill that sufficiently buttresses the slope to make reconstructed segments of the upper and lower roads stable. This option requires installation of two rows of secant piles. One row of secant piles along the outboard side of the reconstructed lower road and another one on the hillside mid-way to the upper road. The permit process for this option may prove difficult with many agencies involved.

The top 5 (+/-) feet of soils from just upslope from the upper row of secant piles to approximately 50 feet below the middle secant pile row is proposed for removal permanently, as shown in Figure 64 and 65 in Appendix D. These soils should be temporarily stockpiled in an approved location by HKA for re-use. An additional 5 (+/-) feet of soil below the removed soils will also be removed (10 feet total) and redensified back into place. The stockpiled soils, if dried back or moisture conditioned as needed, may be re-used as engineered fill during construction of the fill slope that will support the upper road and the culvert buttress of the landslide toe. The remaining soil left over should be off hauled or placed as engineered fill in a location on-site approved by HKA. The material should not be placed on the landslide mass below the lower row of secant piles as it can exacerbate instability of this soil mass.

Two rows of secant piles should be installed in the same manner as the upper and middle row of secant piles refericed above in the section titled, "*NEW Improved slope; installing three rows of secant piles.*"

Based on the slope stability results, each secant pile (Pile 1 and 2) should have minimum 38,000 pounds per linear foot of wall (plf) lateral capacity. For preliminary design purposes it can be assumed the resultant force acts at a location 2/3 the depth to the bedrock within the overburden soil. For practical applications, the actual location of the resultant should be determined by HKA at several sections along wall profile.

The culvert should be a minimum 8 feet in diameter and follow the Hessey Creek alignment starting at the existing culvert to approximately 250 feet upstream. The drainage channel around the culvert should be backfilled with engineered fill to a minimum height of 3 feet above the top of the culvert creating the keyway for the fill slope extending up to the lower road. The fill slope should consist of 5 feet of re-densified landslide material up the lower road secant pile once the upper 5 feet has been removed as specified above.

In Figures 68 through 71 in Appendix C, slope stability safety factors under both static and seismic conditions are presented. Based on the slope stability evaluation results, the safety factors for both static and seismic conditions are greater than the minimum acceptable limits, which means the upper and lower landslide mass will be stabilized after installing two rows of secant piles and fill slope starting at the base of the creek.

6.6. <u>Slope Stability Conclusions</u>

The slope stability assessment is for general (global type) slope failure and consists of initiation and termination of trial failure surfaces on the top and toe of slopes for recreation of the landslide and evaluation of existing condition. The models with slope improvements including secant piles and engineered fill were evaluated with failure surfaces running top to toe as well as mid slope to toe as selected by the engineer to evaluate the benefits to stability of the improvement. In both scenarios, the trial failure surface passes through the soil layers in the cross section model. The general shear trial failure surface screens for potential instability below the in-situ landslide and native soil layer. The in-situ landslide soil layers were also screened for trial failure surfaces localized within the soil layer.

In table 5, slope stability analysis results for the four (4) aforementioned models' static and seismic conditions are shown.

In summary, the large landslide soil mass can be stabilized from the middle row of secant piles along the outboard side of the lower road up to the inboard side of the re-constructed upper road. For stability discussion purposes we will refer to this as the "upper landslide" and the portion downslope from the lower row of secant piles the "lower landslide". A second row or upper row of secant piles on the hillside mid-way to the upper road is required to stabilize the upper landslide soil mass described in this conclusion. Factors of safety against sliding are greater than what is considered stable using modern geotechnical engineering standards.

An engineered fill slope is modeled to support and restore the upper road. The fill slope is modeled to have a 2H:1:V slope gradient with its toe at the upper row of secant piles and crest at the shoulder of the upper road. The fill slope would extend to allow reconstruction of the upper road to allow vehicular traffic, and would terminate along the inboard cut slope of the upper road.

The lower landslide can be stabilized by an additional 30,000 pounds per linear foot capacity secant pile wall or a culvert, keyway, and fill slope extending up to the lower road. The engineered fill slope is modeled at a slope gradient of 3H:1V based off section geometry. The removed soil during grading can be re-used as

engineered fill in construction of the fill slope restoring the upper road and the keyway over the drainage channel.

We anticipate a temporary road will need to be constructed to install the upper and lower row of secant piles on the hillside. Additional working meetings with structural and civil designers, specialty contractors, and SLVWD are anticipated to develop viable working drawings.

6.7. Limitations of Analysis

It must be cautioned that slope stability analysis is an inexact science; and that the mathematical models of the slopes and soils contain many simplifying assumptions, not the least of which is homogeneity. Density, moisture content and shear strength may vary within a soil type. There may be localized areas of low strength or perched ground water within a soil. Slope stability analyses and the generated factors of safety should be used as indicating trend lines. A slope with a safety factor less than one will not necessarily fail, but the probability of slope movement will be greater than a slope with a higher safety factor. Conversely, a slope with a safety factor greater than one may fail, but the probability of stability is higher than a slope with a lower safety factor.

Condition	Figure #	Loading Condition	Minimum Factor of Safety Against Sliding	Trial failure Surface Shape
2017 Landslide Event	60	Static	0.944	Circular
2017 Landslide Event	61	Seismic	0.460	Circular
2017 Landslide Event, Dry	61.1	Seismic	0.875	Circular
Current Condition	62	Static	0.985	Circular
Current Condition	63	Seismic	0.460	Circular
Improved Slope by Installing Three Rows of Secant Piles	64	Static	3.364	Circular
Improved Slope by Installing Three Rows of Secant Piles	65	Seismic	1.196	Circular
Improved Slope by Installing Three Rows of Secant Piles – Lower Landslide	66	Static	4.245	Circular
Improved Slope by Installing Three Rows of Secant Piles – Lower Landslide	67	Seismic	1.216	Circular
Improved Slope by Installing Two rows of Secant Piles and Culvert, Keyway, and Fill Slope	68	Static	4.110	Circular
Improved Slope by Installing Two rows of Secant Piles and Culvert, Keyway, and Fill Slope	69	Seismic	1.240	Circular
Improved Slope by Installing Two rows of Secant Piles and Culvert, Keyway, and Fill Slope – Lower Landslide Failure	70	Static	2.301	Circular
Improved Slope by Installing Two rows of Secant Piles and Culvert, Keyway, and Fill Slope – Lower Landslide Failure	71	Seismic	1.290	Circular

Table 5: Slope Stability Analysis Results

7. Constructability and Estimate of Repair Options

The feasibility and constructability of the two proposed designed options were evaluated by a representative from Granite Rock on site. The two proposed design options for landslide repair are three rows of secant piles, or two row of secant piles and a slope toe buttress fill slope as described in section 6.5, "*NEW Improved slope; installing three rows of secant piles,*" and *"Improved Slope: installing two rows of secant piles and culvert.*"

7.1. Three Rows of Secant Piles

Three rows of secant piles are feasible from a construction standpoint. Key concerns include access for large equipment along Madrone Road including drill rigs and concrete mixer trucks and casing the drilled holes. If casing of the holes is not feasible, then borings can be kept open by ground improvement methods, or by grouting the hole and re-drilling though the grout in increments. Pier excavation sidewalls will collapse due to the loose landslide material.

A mobile concrete batch plant will likely need to be established for the secant piles. Smaller vehicles can transport raw materials to be mixed on site if mixer truck access to the site is not feasible.

Based on our site meeting with Granite Rock and past quotes from Hayward Baker for similar projects, we estimate the cost per secant wall to range from 3 to 4 million dollars. The total cost guestimate would be on the order of 15 million.

7.2. Two Rows of Secant Piles with Buttress Fill Slope

Two rows of secant piles (upper and middle row) and buttress fill slope are feasible from a construction standpoint. The two rows of secant piles will have the same constructability concerns as the first option presented. The buttress fill slope construction will be similar to the lower secant pile row in terms of removing the existing trees, debris, and upper 5 feet of soil. The key difference is constructing the culvert, keyway, and fill slope up to the lower road. This will likely result in a cheaper option as the third secant wall is not necessary. Total cost guestimate for this option would be 12 million.

8. Building Codes and Site Class

Project design and construction should conform to the following current building codes:

-2016 California Building Code (CBC); and

-2016 Green Building Standards Code (CAL Green)

In accordance with section 1613.3.2 of the 2016 CBC, the project site should be assigned the <u>Site Class D</u>.

9. Recommendations for Design and Construction

The results of our investigation indicate that the different slope improvement / stabilization options are feasible from a geotechnical standpoint. The criteria and recommendations presented in this report are focused on the secant pile repair

schemes with or without the Hessey Creek keyway and culvert previously presented in the report.

Geotechnical considerations at the referenced site include improving the stability of the upper and lower landslide, providing stability for the upper and lower road, the potential for strong seismic shaking, and providing adequate site drainage provisions.

Our slope stability analysis results have shown that the current condition of the existing overburden soils overlying the bedrock (including both landslide mass and native soil materials) have high instability potential when moistened or saturated during heavy rainfall or during the occurrence of an earthquake. The instability is possible under both static and seismic conditions. Our basis of design is reliant on the potential slip planes derived from the slope stability analysis. The geotechnical considerations for the failure condition are related to the geometry of the slope and and soil information determined from the test borings such as strength, saturation, and unit weight, refer to the boring logs Figures 5 through 26 in Appendix A.

To mitigate the instability potential of the upper landslide mass, it is recommended to unload the upper landslide by removing the upper 5 (+/-) feet of soil starting from the upper secant pile row to the lower road. After removal of the soil an additional 5 (+/-) feet of the upper landslide should be also removed, but this soil re-densified back into place as engineer fill. The upper landslide should be stabilized using two rows of buried secant piles. The middle row of secant piles would be constructed along the outboard side of the lower road and is estimated to be 200 feet long by as much as 60 feet deep. The upper row of secant piles is recommended to be constructed on the hillside mid-way to the upper road. The upper row is estimated to be 150 feet long by as much as 40 feet deep. The piles should be advanced a minimum 15 feet deep into the bedrock.

To mitigate the instability potential of the lower landslide mass, it is recommended to unload the upper 5 (+/-) feet of soil starting from the lower road extending downslope 50 feet. After removal of the soil, an additional 5 (+/-) feet of the lower landslide mass should be removed and re-densified as engineered fill. The lower landslide should be stabilized with an additional row of secant piles offset approximately 20 feet from Hessey Creek or an 8 feet diameter culvert and drainage channel keyway fill slope extending up to the lower road. The lower row of secant piles is estimated to be 250 feet long by as much as 50 feet deep.

If the culvert option is selected, the culvert should be constructed along the Hessey Creek alignment starting from the existing culvert to approximately 250 feet upstream. The drainage channel should be backfilled with engineered fill to a minimum height of 3 feet above the top of the culvert. A fill slope with a maximum gradient of 2:1 should be constructed from the base of the keyway to the lower road. The engineered fill on the lower landslide mass should be a minimum 5 feet in depth as outlined above. To rebuild and secure the severely damaged portion of the access road where the landslide mass dislodged from the head scarp, an engineered fill slope is recommended to be constructed from the upper row of secant piles up to the inboard side of the upper road.

Due to disturbance of the soil during the 2017 landslide event, the existing landslide soil layers have residual strength which are significantly less than the strength of the native soil. Therefore, it is expected that the landslide soils cannot provide arching. So, there should be no room between two adjacent consecutive piles along the respective wall alignments. Based on the slope stability results, the safety factor for the slope stability both in static and seismic conditions are greater than the minimum acceptable limit.

In the aforementioned slope improvement method, we recommend excavating the surficial soils on the slope in the upslope area of the landslide mass. Some portions of the excavated soil will need to be moisture conditioned or dried back as needed, replaced and recompacted at the initial location to remove the existing bulge in the landslide mass that exists below the landslide headscarp (formed during the 2017 landslide event) to make a uniform firm surface and to provide a flatter slope. The rest of the excavated soil may be re-used in construction of the engineered fill slope that will restore the travel way and shoulder of the upper road and the keyway fill slope along the creek. Excess soil not used as described above may be placed

as engineered fill in other locations on the property approved by HKA. The excess soil should not be disposed of upon the lower landslide mass.

An advanced widespread drainage system should be considered for the project site to collect the runoff water from the hillside. A proper site drainage system is important for the long term performance of the site. As indicated elsewhere in this report, perched water was observed in some of the drilled boreholes. Though groundwater levels could not be studied for this site, the reported observations indicate groundwater collects within the in-situ soil, thus, the proposed slope improvement should include subdrains as part of the site's planned remediation. To minimize the impact of subsurface seepage on the improved slopes, subdrains are recommended.

HKA would like to have working meetings with client's representative and project designers when the slope improving option enters a conceptual design phase to discuss more about the limitations of our model. The variable depth of the landslide from its deepest point along the center to the flanks where it pinches out to nothing should be carefully considered. The varying depth of the slide will have great effect on the location and magnitude of the resultant force. HKA should work with the civil and structural designers to develop additional models in select locations to optimize a value engineering type of solution. To accomplish this, additional testing may be needed such as a geo-physical survey to fine tune the 3-D model of the

landslide soil mass. Soil pile interaction using a finite method can also aid in value engineering design.

The following recommendations should be used as guidelines for preparing project plans and specifications.

Site Grading (Fill/Cut Slopes)

- 1. The HKA should be notified <u>at least four (4) working days</u> prior to any site clearing or grading operation so that the work in the field can be coordinated with the Grading Contractor and arrangements for testing and observation services can be made. The recommendations of this report assume that the HKA will perform the required testing and observation services during grading and construction. It is the client's responsibility to make the necessary arrangements for these required services.
- Where referenced in this report, Percent Relative Compaction and Optimum Moisture Content shall be based on ASTM Test Designation D1557-latest revision.
- Areas to be graded should be cleared of obstructions including loose fill, or other unsuitable material. Existing depressions or voids created during site clearing should be backfilled with engineered fill.

- 4. Cleared areas should then be stripped of organic-laden topsoil. Stripping depth should be from 2 to 4 inches. Actual depth of stripping should be determined in the field by an HKA representative. Stripping should be wasted off-site or stockpiled for use in landscaped areas if desired.
- 5. Areas to receive non-expansive engineered fill should be scarified 8 inches, moisture conditioned to over optimum moisture content, and redensified to 90 percent of maximum density. Portions of the site may need to be moisture conditioned or dried back as needed to achieve suitable moisture content for compaction. These areas may then be brought to design grade with engineered fill.
- Engineered fill should be placed in thin lifts not exceeding 8 inches in loose thickness; moisture conditioned, and compacted to at least 90 percent relative compaction.
- 7. We understand grading at the site will consist of excavation of a portion of landslide overburden soil to construct a flatter slope along the upper and lower landslide. A temporary access road and working platform will also need to be constructed to support heavy equipment that will be required to advance the upper and lower row of secant piles. If the culvert option is selected, grading will consist of excavating, backfilling the drainage channel of Hessey Creek, and creating a fill slope up to the lower road.

- 8. The top 5 (+/-) feet of soils from upslope from the upper row of secant piles to approximately 50 feet below the middle secant pile row is proposed for removal, refer to Figure 74 and 75 in Appendix D. These soils should be temporarily stockpiled in an approved location by HKA for re-use. An additional 5 (+/-) feet of soil below the removed soils will also be removed (10 feet total) and redensified back into place. The stockpiled soils, if dried back or moisture conditioned as needed, may be re-used as engineered fill during construction of the both fill slopes. The remaining soil left over should be off hauled or placed as engineered fill in a location on-site approved by HKA. The material should not be placed on the landslide mass below the lower row of secant piles as it can exacerbate instability of this soil mass.
- 9. To rebuild and secure the travel way and shoulder of the upper access road where the soil mass dislodged from the head scarp an engineered fill slope with a gradient of 2H:1V is recommended to be constructed from the upper row of secant piles up to the inboard side of the damaged upper road.
- 10. To stabilize the toe of the lower landslide with no lower secant pile row, an engineered keyway and fill slope with a gradient of 2H:1V or greater is recommended to be constructed from the base of the drainage channel keyway up to the middle row of secant piles or lower road. The keyway will consist of an 8 feet diameter culvert along the creek channel with

engineered fill backfilled around the culvert up to a minimum height of 3 feet above the top of the culvert. The width of the keyway at finish grade is elevation estimated to be 40 feet.

- 11. Areas to be graded should be cleared of all obstructions, including foundations and structures if exist, old fill, trees not designated to remain and other unsuitable material. Disturbed soil resulting from demolition and clearing operations may be stockpiled for use as engineered fill, provided the fill is clean of organic material, unacceptable colluvium deposits or other unsuitable material. Existing depressions or voids created during site clearing should be backfilled with engineered fill.
- 12. If project site grading is performed during or shortly after the rainy season, the grading contractor may encounter compaction difficulty, such as pumping or bringing free water to the surface. If compaction cannot be achieved after adjusting the soil moisture content, it may be necessary to over-excavate the subgrade soil and replace it with angular crushed rock to stabilize the subgrade. We estimate that the depth of over-excavation would be approximately 12 inches under these adverse conditions.
- 13. Import soils if utilized as engineered fill at the project site should:
 - 1) Be free of wood, organic debris and other deleterious materials;
 - 2) Not contain rocks or clods greater than 5 inches in any dimension;

- 3) Not contain more than 25 percent of fines passing the #200 sieve;
- 4) Have a Sand Equivalent greater than 18;
- 5) Have a Plasticity Index less than 18;
- 6) Have an R-Value of not less than 30; and
- Contractor should submit to HKA samples of import material or utility trench backfill for compliance testing a minimum of 4 days before it is delivered.
- 14. We estimate shrinkage factors of 15 to 25 percent for the on-site materials when used in engineered fills.
- 15. Cut and fill slopes should be protected from erosion by preventing runoff from spilling over graded slopes. Generally, Lined V-ditch and/or curtain drain at the top of the hillside and curtain drain at the secant piles wall may be considered for long-term drainage control. A proper drainage system should be designed for the entire site to collect and control the runoff waters.
- 16. After the earthwork operations have been completed and HKA has finished observation of the work, no further earthwork operations shall be performed except with the approval of and under the observation of HKA.

- Permanent graded slopes should be constructed no steeper than 2H:1V (horizontal to vertical). Graded slopes are expected to require erosion control and periodic maintenance for surface sloughing.
- 18. Fill slopes should be constructed with keyways and benches sloped in the inboard direction a minimum 5 percent. The keyways should be a minimum 8 feet wide and placed over bridging material comprised of 12 inches of gabion over geogrid equivalent to Mirifi 600X of better. The keyway and benches should be constructed with drains to alleviate hydrostatic pressure. The geotechnical engineer should approve the type of drainage system and location for discharge.

Secant Pile Walls

- 19. Secant pile walls are formed by constructing intersecting reinforced concrete piles. Secant pile walls are used to build cut off walls for the control of ground water inflow and to minimize movement in weak and wet soils.
- 20. Secant walls are constructed in the form of hard/soft (or firm) or hard/hard walls on adjacent piles. If the distance between the hard and soft piles are equal to the pile's diameter, the wall is called a tangent pile wall.
- 21. The secant piles are reinforced with either steel rebar or with steel beams and are constructed by either drilling under mud or augering or driving. In this wall

system, there are two types of piles. Primary piles are installed first. These piles are mainly responsible for waterproofing and filling the voids.

- 22. In the Hard/Firm (or soft) wall system, the primary piles have no reinforcement and consists of flexible concrete that can be cut while the secondary piles are installed. The secondary piles which should have reinforcement will be installed between the primary piles once the latter gain sufficient strength. Where short term water retention is required, this system offers the most cost-effective and rapid solution. The wall consists of interlocking bored or driven piles. Primary piles are constructed first using a 'soft' cement-bentonite mix or 'firm' concrete. Secondary piles, formed in structural reinforced concrete, are then installed between the primary piles. The primary piles in Hard/Firm (or Soft) wall system should be drilled at a minimum to bed rock depth and the pile base will be sited on the bedrock. Therefore, all the lateral capacity of the wall will be provided by the secondary piles and therefore, the secondary piles design in hard/firm (or soft) wall system differs from the hard/hard wall system design.
- 23. Hard/hard wall construction is very similar to a hard/firm wall but in this case the primary piles are constructed in higher strength concrete and may be reinforced. Heavy duty rotary piling rigs, using tools fitted with specially designed cutting heads, are necessary to cut the secondary piles. The end

product provides a fully concreted face and can be an effective alternative to diaphragm wall construction.

- 24. Pile overlap is typically in the order of 3 inches. In a tangent pile wall, there is no pile overlap as the piles are constructed flush to each other.
- 25. Verticality tolerances may be hard to achieve for deep piles. Special care should be taken to assure the pile installation is vertical.
- Special construction methods might be required to make sure that total waterproofing is provided.
- 27. A monitoring and maintenance program is an integral component of the design of the secant pile wall. To maintain the integrity of the wall system, it is necessary to conduct regular inspections of the slope and the secant pile. We recommend secant pile walls be inspected after long duration winter storms, severe seismic shaking, and at least once every 2 years by a licensed engineer or an engineering geologist to monitor the status of the wall system and recommend maintenance when needed.

Drilled piles for the secant Pile Wall

28. If cast-in-place piles are considered for secant pile wall system, the project site secant piles should be excavated prior to placement of the reinforcement

cage. All pile excavations should be observed by the soils engineer prior to placement of steel and concrete. Pile diameter is to be determined by the project structural engineer. Pile drilling sequence and method of pile drilling is to be determined by the project contractor. Casing of the pier shaft within the loose sandy soils may be required.

- Secant piles at the project site should be embedded a minimum of 15 feet into the competent bedrock.
- 30. The landslide layers over the native soil are considered residual strength disturbed soil. The behavior of this layer is not uniform at different locations and depths of the slope. Therefore, it is prudent to neglect the top of the secant piles for calculating passive resistance. This length is decreased as they reach the flanks (sides) of the slope which contain shallower landslide deposits. At present, the only reliable information of landslide thicknesses is the existing geotechnical boreholes. Therefore, complementary investigation to determine the exact thickness of the landslide layer at the different locations of the slope should be performed or conservative landslide depth should be assumed for designing.
- 31. The secant piles are installed next to each other without any room for soil to provide arching. Therefore, if applicable for pile designing, arching capability factor and safety factor should be considered equal to 1.0.

- 32. At 15 feet below bedrock, an allowable vertical bearing and tension capacity pile of 15 ksf and 6 ksf respectively plus a one third increase for short duration loading may be used for design of the drilled piers. It must be noted that side friction for soil layers overlaid the bedrock has been disregarded due to existing residual soil.
- 33. Total and differential settlement for the secant piles penetrating the looser landslide and native soil deposits to be embedded within the bedrock, are anticipated to be less than 1 inch and 0.5 inch respectively.
- 34. Prior to placing reinforcing steel and concrete, all pile excavations should be thoroughly cleaned. The foundation excavations must be observed by HKA prior to placing reinforcing steel and concrete.
- 35. The Contractors are responsible for following CAL-OSHA regulations, local codes and ordinances and any requirements outlined on any project plan sheets to maintain a safe working environment at the project site.

Active and Passive Pressures

36. The active pressures, shown as an equivalent fluid pressure, for the governing design conditions (seismic and saturated condition) are presented in Table 6.

Recommended Active Pressure EFW (pcf)	Shear Force Resistance (klf)	Depth to Bedrock (ft)	Equivalent Fluid Weight (pcf) ^{1, 2}
Upper Secant Wall	38	32	74
Middle Secant Wall (Section A)	38	25	120
Middle Secant Wall (Section A – B)	38	35	62
Middle Secant Wall (Section B – E)	38	45	43
Lower Secant Wall	30	36	46

Table 6:Recommended Active Pressures

1. Rankine pressure distribution (triangular) behind the portion of the secant wall between ground surface and top of bedrock used to model slide driving forces.

2. Conservative estimate for middle secant wall section A through B. These values can be further refined with additional analysis.

- 37. The ultimate passive resistance earth pressure available in the bedrock is equivalent to a fluid weight of 580 pcf. This is the ultimate passive resistance. Appropriate structural design safety factors should be applied.
- 38. Our model assumes that the new engineered fill zone is drained. Our model assumes that it is not possible to fully drain the slide mass.

Driven Piles

- 39. Vertical alignment of the piles should be preserved during driving. However, an inclination of 2 to 3 inches from vertical can be accepted as the tolerance for such piles.
- 40. In a group of piles, the middle piles should be driven first and then working towards the perimeter piles. This is to prevent displacement of the already driven piles due to the lateral movement of the soil. In the granular soil if the piles are driven at spacing of less than three times the diameter of the adjacent pile, due to densification of the soil, penetration would be difficult.

- 41. When excessive resistance to the driving is mobilized, the operation can be stopped. If the pile is penetrated less than the calculated depth, the operation can be halted for one week in order to dissipate the excess pore pressure generated in the soil. The driving should be resumed after this period. Note that you will initially encounter higher blows until the pile remobilize the soil. However, if still the required penetration is not achieved, a pile load test is proposed to check the capacity of the driven pile.
- 42. If pile heave is observed, level readings referenced to a fixed datum shall be taken by the Engineer on all piles immediately after installation and periodically thereafter as adjacent piles are driven to determine the pile heave range.
- 43. If during the driving process for adjacent piles, piles shall be re-driven:
 - For end bearing piles, if the heave is more than 0.5 inch.
 - For shaft friction piles, if the heave is more than 1.5 inch.

Surface & Subsurface Drainage

44. The surface drainage from within the slipout area needs to be collected and directed to catch basins, existing creek or to outside of the site. Most importantly surface drainage should not be allowed to runoff or spill over the edge of the fill. The collected runoff should be piped down past the secant

piles wall and downslope as well. Subsurface drains should be installed at the contact of recompacted topsoil on the slope. The number of drains and spacing should be determined by the project Civil Engineer. The drains should collect subsurface drainage within the improved area and convey drainage to an adequate discharge point downslope of the improvements.

- 45. Surface drainage should include provisions for positive gradients so that surface runoff is not permitted to pond adjacent to pavements nor spill over the slope. Surface drainage should be directed away from the graded slope.
- 46. The migration of water or spread of extensive root systems below excavations, embankments, foundations, slabs, or pavements may cause undesirable differential movements and subsequent damage to these structures. Landscaping should be planned accordingly.

Monitoring

47. A survey-monitoring program should be implemented to monitor slope displacements during construction. In addition, improvements should also be surveyed and photographs and/or video taken to document baseline conditions. The deflection at the top of the secant piles should be surveyed periodically. If the piles head deflect significantly or if distress or settlement

is noted adjacent to the top of the piles, an evaluation should be performed and corrective measures taken.

Plan Review, Construction Observation, and Testing

- 48. Haro, Kasunich and Associates should be provided an opportunity to review project plans, prior to construction, to evaluate if our recommendations have been properly interpreted and implemented in the design. Having done so, we can prepare the county-required geotechnical plan review letter.
- 49. If we do not review the plans and provide observation services during the earthwork phase of the project, we assume no responsibility for misinterpretation of our recommendations.

LIMITATIONS AND UNIFORMITY OF CONDITIONS

- 1. The recommendations of this report are based upon the assumption that the soil conditions do not deviate from those disclosed in the borings. If any variations or undesirable conditions are encountered during construction, or if the proposed construction will differ from that planned at the time, our firm should be notified so that supplemental recommendations can be given.
- 2. This report is issued with the understanding that it is the responsibility of the owner, or his representative, to ensure that the information and recommendations contained herein are called to the attention of the Architects and Engineers for the project and incorporated into the plans, and that the necessary steps are taken to ensure that the Contractors and Subcontractors carry out such recommendations in the field. The conclusions and recommendations contained herein are professional opinions derived in accordance with current standards of professional practice. No other warranty expressed or implied is made.
- 3. The findings of this report are valid as of the present date. However, changes in the conditions of a property can occur with the passage of time, whether they be due to natural processes or to the works of man, on this or adjacent properties. In addition, changes in applicable or appropriate standards occur whether they result from legislation or the broadening of knowledge. Accordingly, the findings of this report may be invalidated, wholly or partially, by changes outside our control. Therefore, this report should not be relied upon after a period of three years without being reviewed by a geotechnical engineer.

APPENDIX A

Site Vicinity Map (Figure 1)

Geological Site Map (Figure 2)

Boring Site Plan (Figure 3)

Key to Logs (Figure 4)


Logs of Test Borings (Figures 5 – 26)


Particle Size Distribution Test Results (Figures 27 – 35)


Plasticity Index (Figures 36 - 39)

Direct Shear Results (Figures 40 - 47)

Variation of SPT Blows, Saturation Degree and Void Ratio Versus Depth (Figures 48 – 53)








PREPARED BY PAUL JENSEN PROFESSIONAL LAND SURVEYOR * 4627 SANTA CRUZ, CALIFORNIA


	E	BORING SITE PLAN SLVWD - LYON TANK 3OULDER CREEK, CALIFORNIA APN: 081-011-07
SCALE:	1" = 40'	
DRAWN BY:	AJB	
DATE:	APR 2018	HARO, KASUNICH & ASSOCIATES, INC.
REVISED:		GEOTECHNICAL AND COASTAL ENGINEERS 116 E. LAKE AVENUE, WATSONVILLE, CA 95076
JOB NO.	SC4090.1	(831) 722-4175
FIG	JRE N	D. 3

	PF	RIMA	RY D	IVISIONS	3		GROUP SYMBOL	T	SECONDA	RY DI	VISIO	ONS			
'n	190		GRA	VELS	CLEAN		GW	1	Well graded gravels, grave	l-sand mit	ctures,	little or no fine			
LS IML		мо	RETH	IAN HALF	GRAVE (LESS TH 5% FINE	AN	GP		Poorly graded gravels or gr fines.	avel-sand	mixtu	res, little or no			
COARSE GRAINED SOILS	IS LARGER THAN NO. 200 IS LARGER THAN NO. 200 SIEVE SIZE	I L	FRACT ARGEI	TION IS R THAN SIEVE	GRAVE WITH		GM		Silty gravels, gravel-sand-s	ilt mixtur	es, non	i-plastic fines.			
AIN!	GER THAN I		NO. 4	SIEVE	FINES		GC	1	Clayey gravels, gravel-sand	l-clay mix	tures, j	plastic fines.			
SE GB	NRGER SIEV		SAI	NDS	CLEAN SANDS		SW	1	Weil graded sands, gravelly	/ sands, lit	ttle or i	no fines			
NAR DAR				IAN HALF	(LESS TH 5% FINE		SP	1	Poorly graded sands or gravelly sands, little or no fines						
U 3	2	SN	FRACT MALLI	FION IS ER THAN	SANDS WITH		SM	1	Silty sands, sand-silt mixtures, non-plastic fines.						
		1	NO. 4	STEVE	FINES		SC	0	Clayey sands, sand-clay mi	xtures, pla	stic fir	ies.			
S			er	TTO AND	CLAVE	5 R	ML	I f	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity.						
SOIL	ALLER VE SIZE	u		LTS AND CLAYS		CL		norganic clays of low to mo andy clays, silty clays, lear		sticity,	gravelly clays,				
NEB	N IIA IS SIN 0 SIE	Į.				OL	0	Organic silts and organic sil	ty clays of	f low p	lasticity.				
FINE GRAINED SOILS	MORE THAN HALF OF MATIERIAL IS SMALLER THAN NO. 200 SIEVE SIZE		SILTS AND CLAYS				MH		norganic silts, micaceous o ilty soils, elastic silts.	r diatomac	eous f	ine sandy or			
BINE	MA. THAI	L	IOUID	LIMIT IS GR	EATER TH	AN	СН	I	norganic clays of high plas	ticity, fat o	alays.				
				50%	·		OH	C	Organic clays of medium to	high plast	icity, o	organic silts.			
HIGHLY		ORG	GANIC SOI	LS		Pt	F	eat and other highly organi	c soils.						
	and a second	200		S. STANDAR	D SERIES S	SIEVE		3/4		VE OPE	VINGS 12"				
SILTS A	ND CLA	ys –		SAND			G	JR.	AVEL	COBBLE	s	BOULDERS			
		1	FINE	MEDIUM	COARSE		FINE		COARSE	G METHOD		H,O			
RE	LATIVE	DENSI			CONSISTEN	NC I						Final			
SANDS GRAV		PE	OWS SILTS ER AND		STRENGTH (TSF)**		PER		STANDARD PENETRATION TEST	т					
		FOO	л* 	CLAYS			FOOT*		MODIFIED CALIFORNIA	LorM	Ш	Initial			
VERY LO		0- 4-1		VERY SOFT	0 - % %~ %	. *	0-2 2-4		PITCHER BARREL	P	\boxtimes	Water level designation			
MEDIUM		10 -		FIRM	%-1	4	4-8		SHELBY TUBE	s					
DENS	SE	30 -	50	STIFF	1-2	14 - 1 -	8 - 16		STRAGER FORE	2					
VERY DI	ENSE	OVER	R 50	VERY STIFF			16 - 32		BULK	13					
				HARD	OVER		OVER 32								
•≖Un	nber of blov scontined co trometer, tor	mpressiv	ve streng	th in tons/ft ² as de	nes to drive a 2" etermined by lab	O.D. (1 oratory	%" I.D.) split sp testing or appro	poo oxin	n sampler (ASTM D-1586) nated by the Standard Penetration	Test (ASTM	I D-1586	i), pocket			
											- LYON EEK, (N TANK CALIFORNIA			
									SCALE: NTS	APN: 0	1-01 ⁻	1-07			
									DRAWN BY: AJB		CI INII/				
									DATE: APR 2018 H	GEOTECH	INICAL	CH & ASSOCIA			
222 of	308								JOB NO. SC4090.1			NUE, WATSONVILLE, (831) 722-4175			
222 01	200								FIGURE NO. 4	4		SHI			

LOG	GGED BY	CG DATE DRILLED May 4, 2017	BORING D	IAMETE	ER_ 6		-	BORING NO. B-1
Depth, ft.	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
- 0 -		Fill	1	1				
		Brown and gray medium Silty SAND with Cla binder, moist, medium dense	ay SM					
5		Fill, gray Granite SAND, moist, medium dens	se	00	-			
	1-1 (L)			26		105	12.7	5- C
	1-2 (T)			13				
		Fill, gray Granitic Silty SAND, moist, medium dense		1.5				
10	1-3 (L)		_	14		104	15.1	
	1-4 (T)	Fill, Gray Silty Granitic SAND, wet, loose with plant roots	n SM	6			16.6	
	1-5 (L)			11		94	22.6	
15	1-6 (T)	Fill, Gray coarse SAND, wet, loose		4				
	1-7 (T)	Fill, Gray Granite SAND with roots and wood	from	4		101	15.7	
	1-8 (T)	16-17.5' wet, loose		7				
20		Fill, gray SAND, coarse from 14.5 to 16 and to 19'	17.5					
20	1-9 (T)	Landslide, brown Clayey SAND, saturated, lo	oose SC	1/18"			28.8	
	1-10(L)			6		87	26.6	
				E.			20.0	
25	1-11(T)	Landslide, light brown Clayey SAND, moist, v	very	5			26.3	(1-11) Grain Size
		loose					2010	Analysis
								% Gravel = 1.5 % Sand = 62.9
30		Landslide, light brown Clayey SAND with Gra	ivels	9				% Fines = 35.6
	1-12(L)	(much less Clay than 1-11, very moist, loose				103	23.5	
35 -								
00 -	- <u>-</u>	Y						




00	GGED BY CO	G DATE DRILLED May 4, 2017 BO	RING DI	AMETE	R_6"	-	BORING NO. B-2
naput, IL.	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
		Fill, mixed, Silty Clayey SAND with Gravels, moist, loose	sc				
	2-1 (L) 2-2 (T)	Fill, mixed light brown Clayey SAND with Gravels, moist, loose Increase in moisture from 6 1/2' to 8'		13 6	107	13.0	
0	2-3 (L)	Loose and saturated from 8' Gray Clayey SAND with Gravels and roots, very moist to wet, loose	sc	2	92	23.9	
	2-4 (T)	Brown Clayey SAND with Gravels, very moist, loose	sc	3			
5	2-5 (L) 2-6 (T)	Light brown Clayey SAND with Gravels, very moist to wet, loose		7 5	91	29.6	
)	2-7 (L)	Light brown Silty SAND with Gravels, very moist to wet, loose	SM	6 7	93	32.7	
	2-9 (L) 2-10(T)	Sandy CLAY, mosit, stiff, light brown Silty Granite SAND, wet, soft to medium stiff Native, light brown CLAY very moist, firm-stiff	CL	6 8	83	33.2	
5	2-11(L)	(weathered bedrock?) Light brown CLAY, very moist, very stiff (weathered Bedrock?)		11	102	25.4	
	2-12(T)	Light brown Silty SANDSTONE, mosit, medium dense (weathered Bedrock) Very light brown Silty SANDSTONE with orange	SM BR	19			
)	2-13(T)	stains, moist, very dense Boring terminated at 31.50 feet		50/4"		9.2	
i -							
		SUNICH AND ASSOCIATES, INC.					




LUI	GGED BY C	G DATE DRILLED May 23, 2017 BOI	RING DI	AMETE	R 8" HS	-	BORING NO. B-3
Depth, ft.	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
0 -	3-1 (B)	2" AC 10" AB Orange Gravelly SAND	1	1-1		23.2	
	3-2 (B)	Fill, Gray & orange Clayey SAND with Gravel, moist, medium dense	SC				
5	3-3 (L)	Water 5' at end of drilling Fill, mixed orange brown Silty SAND with Clay & Gravels, very moist, loose	SM	19	116	11.0	
10	3-4 (L)	Water 10' first encountered (Weathered Granite) Fill, Orange brown Clayey SAND, very moist, wet with Gravel, very loose	sc	9	104	17.1	
5		Orange Gravelly SAND with Clay from 14' to 15' Wet, loose from 15' - 17.5'					
		Orange Clayey SAND, reddish brown decomposed wood from 19'-20'	sc				
20		Orange Clayey SAND, wet, loose	SC				
5		Orange & brown SAND with Gravels from 23' - 25' Orange & brown SAND and Gravelly SAND-Loose	SM				
	3-5 (L) 3-6 (T)	Brown Sandy CLAY (weathered Granite) moist, firm-medium stiff	CL	7 7	92	25.6	
0		Orange brown Clayey SAND with seams of wet Gravelly (weathered Granite) SAND	sc				
		Very light brown SANDSTONE with orange stains & striations, moist, very dense	BR				
5 -	3-7 (T)			50/4"			(3-7) Grain Size
	ARO, KAS	SUNICH AND ASSOCIATES, INC.					Analysis %Gravel = 0.4 % Sand = 75.4 %Fine = 24.2

227 of 308

_	GGED BY C	G DATE DRILLED May 23, 2017 E	BORING DI	AWETE	R 8" H	5	BORING NO. B-4
in fundad	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	P.c.r. Moisture % dry wt.	MISC. LAB RESULTS
Ŷ	4-1 (B)	2" AC 6" AB orange Gravely SAND and gravy Clayey SAND					
	4-2 (B)	Orange Clayey SAND	sc				
		Water at 4' @ end of drilling					
	4-3 (L)	Fill, gray & brown Clayey SAND	10-1	25	77	13.8	
	4-4 (T)			19			
)		₩ater first encountered		7			
	4-5 (L)	Gray Clayey SAND with Gravel and roots, water	SC	2	64	22.0	
	4-6 (T)	at 10'. wet. loose		-			
5	4-7 (L)	Gray Clayey SAND and medium to coarse SAND		10	96	15.1	
	4-8 (T)	with roots, wet Clean grey SAND from 16.5 - 19' saturated, loose	SM	3	90	24.1	
	4-9 (T)	(Alluvial deposits)		2		24.1	
)	Z/	Native, gray Clayey SAND (weathered granite) wet. loose		3	-		
	4-10(L)				81	32.4	
	4-11(T)						
		Crow & brown CLAV with this second of Course		-			
	4-12(T)	Gray & brown CLAY with thin seams of Gravel, wet, medium stiff	CL	7			
		Gray Silty & Clayey SAND, wet, loose	-				
		4" - 6" seams of orange coarse SAND & orange	SC	14			
	4-13(T)	medium SAND, wet, medium dense (Alluvial deposits?)				22.0	
		×					
-		1					



LOGGED BY_	CG DATE DRILLED May 24, 2017 BO		AMETE	R 2" HS	-	BORING NO. B-5
Depth, ft. Sample No. and type Sumhol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
	Fill, brown weathered Granite, moist, medium dense	SC				
5 5-1 (L)	Native	1	7	102	11.8	
5-2 (T) 5-3 (L)	Orange decomposed Granite, moist, loose	SN	5 10	99	13.8	(5-3) Direct Shear
¹⁰ 5-4 (T)	Orange weathered Granite, moist, loose		8			$\phi = 36^{\circ}$ C = 162 psf Ms = 20.3 Atterberg Limits
15	Increase in drilling resistance from 11' - 15'					LL = 26.48% PI = 4
5-5 (T)	Water at 15' after drilling Orange very weathered Granitic CLAY, moist, medium dense	CL	14			
20 5-6 (T)	Water on Supply Orange, very weathered Granitc, moist, medium dense	SC	10			
25 5-7 (L)	Orange, less weathered Granite, moise, loose		19	107	17.2	(5-7)Direct Shear
5-8 (T)	Orange weathered Granite, moist, medium dense		19			∮ = 51⁰ C = 232 psf Ms = 19.7%
90 5-9 (T)	Orange decomposed Granite, very moist, dense		42		94	
5 _						




	CG DATE DRILLED May 24, 2017 BO		AMETE	R 8" HS	-	BORING NO. B-6
Ueptn, rt. Sample No. and type	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density D.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
)	Fill Brown Silty SAND with Gravels, moist, medium dense	SM	22		10.7	
6-2 (T)			13		10.1	
6-3 (L)	Orange brown Silty SAND, Granite, medium		38	118	10.3	(6-3) Direct Shear
6-4 (T)	∐ense Nit		19	110	10.0	$\phi = 47^{\circ}$ C = 463 psf Ms = 15.1%
0 6-5 (T)	Fill Orange brown decomposed Silty SAND, Granite, moist		20	99	10.9	
5 6-6 (T)	Fill Orange brown decomposed Granite, moist, Mail medium dense		14		14.1	
0 6-7 (T)	Fill Orange brown decomposed Grante, moist, medium dense Native (?)		11		14.0	
	Gray weathered Granite, very moist, loose	SM				
5 6-8 (T)	Gray, very weathered decomposed Granite, very		7			
6-9 (L)	V.A. moist, loose		11	89	26.8	(6-9) Direct Shear ∮ = 37°
) 6-10(T) 6-11(T)	Orange, very weathered Granite, very moist,		4 50 2 1/2			C = 611 psf
5	Light brown SANDSTONE (Lompico Sandstone) with orange stains, mover, very dense Boring terminated at 33.0 feet	BR				


	BY CO	DATE DRILLED May 24, 2017		AMETE	R 8" HS	-	BORING NO. B-7
Sample No.	and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density D.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
T		2" AC Fill, Mixed orange brown, olive brown & gray	SM				
		weathered Granite, moist, loose to medium dens		17			
7-1	(L)	Olive house weathered Oracity assist					
		Olive brown weathered Granite, moist					
7-2	(L)	Fill Mixed orange brown & gray weathered Granite		26	122	11.3	
7-3	1-11			12			
		Fill, Orange brown weathered Granite, very mois medium dense	t,				
7-4		Fill, Orange brown weathered Granite, very mois	t,	12		12.7	
		medium dense Easier drilling from 17' - 20'					
		Fill	CM				
7-5	(т)\\	Orange brown very weathered Granite, very moist, loose	SM	3			
7-6	(L)	Filter Fabric		12		4.1	
		Orange gravelly SAND, very moist, loose Very hard drilling at 27'	BR				
7-7		Light brown SANDSTONE with orange stains, moist, very dense		50/2"	114	12.4	
		Boring terminated at 30 feet					

		Lyon Tank Slide				PF	OJECT NO. SC409
LO	GGED BY	DATE DRILLED	BORING D	IAMETE	R		BORING NO. B-8
Depth, ft.	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	p.c.t. Moisture % drv wt.	MISC. LAB RESULTS
- 0	8-1 (L)	Native Yellow brown fine to medium SAND loose to medium dense from 0-3 1/2' SAND seam at 4' (decomposed Granite	SM	11 12	11	8 3.3	
9	8-3 (T)	Dark yellow brown Silty SAND with Clay, mica & occassional Gravels, moist loose Dark yellow		4			
10	8-5 (L)	Brown & gray Silty SAND with mica & angular coarse SAND, very moist, loose (decomposed Granite) Hole caved to 12'	SM	6	10	3 20.0	(8-5) Direct Shear ∮ = 42° C = 358 psf Ma = 21.0%
15	8-6 (L)	Brown with gray pockets Silty SAND with mica and small roots, very moist, very loose	SM	8			Ms = 21.0% (8-6) Direct Shear $\oint = 40^{\circ}$ C = 0 $p = f$
20	8-7 (T)	Gray SANd with Silt & Gravels, very moist, loose		9			
25	8-8 (L)	Gray Clayey SAND in Auger cuttings from 24-25' Gray Clayey SAND with Gravels, very moist - wet loose		13			
30	8-9 (T) 8-10 (L)	Gray Clayey medium to coarse SAND with occassional 1/2" to 1" diameter angular Gravels, wet, loose Buried piece of decomposed wood at 30', grading more Clayey from 30' - 35'	sc	6			
35 –		N					
		SUNICH AND ASSOCIATES, INC					
BY:	dk	F	IGURE NO.	16			

234 of 308



	ED BY C	G DATE DRILLED July 24, 2017 BC			-		-	BORING NO. B-9
Deptn, ft.	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classificatio	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetromete	Dry Density p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
, Т		Orange brown Silty medium to coarse SAND with mica, moist, loose (decomposed granite)	SM	15	-	-		
	9-1 (L)			6			2.9	
ç)-2 (T) \]	¥		Ū				
5 g)-3 (L)	Orange brown Silty SAND with Gravels & Mica,	SM	11			15.0	
)-4 (T)	moist, loose (decomposed granite)		5				
10		¥ Water at end of drilling		3				
)-5 (T) \	Buried Decomposed Wood from 10' - 11.5'		8				
)-6 (L)	Orange brown Clayey Silty SAND/Sandy CLAY with wood, mica and Gravels (weathered	SC					
15		decomposed granite) 2" soil & wood debris in sample		6				
9)-7 (T)	Buried decomposed wood from 15' - 16.5'		0			41.6	
20			1					
100	-8 (T)	Orange and brown Clayey SAND weathered Granite with Mica, wet, medium dense	SC	11		118		
25 9	-9 (T)	Orange brown Sandy CLAY, wet, loose (very weathered Granite shale)	CL	6			26.4	
		Weathered Granite (intact) very moist, loose to						
30	-10(L)	medium dense	/	22		111	18.8	
		Harder drilling at 32'				24.4.74	10.0	
15 _	11	ξ		-		-		




OGGED BY	CG DATE DRILLED July 25, 2017 E	ORING DI	AMETE	R 8" HS	5	BORING NO. B-10
Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
10-1(T)	Dark brown Clayey SAND with Gravel & roots, very moist, loose	SC	4		18.6	
10-2(L)	Dark brown Clayey SAND with Gravels		6			
	₩Water at 1:30 pm Water and end of drilling 10:32 am					
0 10-3(L)	Orange Clayey Gravelly SAND, very moist, loose (decomposed granite)		17	104	12.4	
5 10-4(T)	Gray Gravelly SAND (decomposed grainte) wet, medium dense	sc	16		14.6	
10-5(T)			4		19.6	
10-6 (1)	Gray Clayey fine SAND with angular Gravels (slide debris), loose to medium dense		11			
10-7(T)	Gray Clayey SAND with Gravels & wood fragment (slide debris?) wet, medium dense		16		21.6	
10-8(T	Orange decomposed Granite, very moist, medium dense, grading to dense decomposed Granite from 30' - 35'		12			
10-9(T)	Orange decomposed Granite with black specs, very moist, dense		47		18.1	

	CG DATE DRILLED July 25, 2017 BO	RING DI	AMETE	R 8"F	IS	2	BORING NO. B-11
Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
11-1(L)	Light orange brown Silty SAND with large root, moist, medium dense (slide material)	SM	26	8	31	10.8	(11-1) Grain Size Analysis % Gravel = 5.2 % Sand = 67.0
11-2(T)	Dark brown Clayey medium to coarse SAND with small and large roopts, moist - very moist, loose	sc	4				% Fines = 27.8
10 11-4(L)	Gray Silty medium to coarse SAND with large wood fragment, medium dense	SM	23	1	15	10.7	(11-4) Grain Size Analysis
/5 11-5(T)∖\1	Harder drilling (steady drilling) orange brown SAND with black fleck Decomposed Granite, very moist, dense Gray medium to coarse SAND Decomposed		41				% Gravel = 13.5 % Sand = 73.2 % Fines = 13.3
20 11-6(T)	Granite, moist, medium dense to dense Gray Sandy CLAY, very moist, stiff	CL	12			26.1	
25 11-7(L)	Orange brown Sandy CLAY, very moist, firm (old slide material), medium stiff	CL	11	1(04	20.3	(11-7) Direct Shear ∮ = 32° C = 367 psf Ms = 22.0%
0 11-8(T)	Harder driling at 30' Orange SAND with Silty and black flecks (Decomposed Granite) very moist, medium dense, bands of orange gray brown and gray	SM	29			19.0	
5_11-9(T)	coarser Sand from 7' to 7 1/2' ?? Orange decomposed granite, damp, very dense	BR	50/3"				


LOGGED B	Y CG	DATE DRILLED July 25, 2017 BO	DRING DI	AMETE	R 8"H	-	BORING NO. B-12
Depth, ft. Sample No. and type	Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density D.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
0		Fill (Landslide Material) Orange brown Silty SAND with Gravels, moist, loose	SM	15	89	6.2	
5 12-2(T		Fill (Landslide Materials) Orange brown Silty SAND with Gravels, moist, very loose	SM				Sample deflecte by rock at 5'
10 12-3(T	$\overline{\mathbf{V}}$	Orange brown Silty SAND with Gravels, moist, loose	SM	5	101	17.1	Refusal at 12-13' Gray
12-4(L		Gray brown Clayey SAND	SC	50/5"			Granite Rock & Galvanized Wire (Gabion Basket)
15 12-5(L		Fill Dark orange brown Clayey SAND with mica			81		
20 12-6(L		Orange Sandy CLAY, stiff	CL	27			
12-7(T		Orange very weathered Granite, very moist, loose		8		18.3	
25 12-8(L		Orange Clay very weathered Granite, very moist, soft		7	97	22.8	(12-8) Direct Shear $\phi = 45^{v}$
12-9(T		Orange Sandy CLAY (very weathered Granite) Orange Sandy CLAY (very weathered Granite)		7			φ = 45° C = 292 psf Ms = 24.4%
30 2-10(L	15	Orange Sandy CLAY (very weathered Granite) wet, soft Orange less weathered Granite, wet, hard Light brown SANDSTONE with orange bands,		88 50/6"		10.1	
2-11(7	1×24	moist, very dense Boring terminated at 32.5 feet				13.1	
35 _						1	


Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
	2" AC 5" AB Fill Orange brown Silty SAND, moist, loose, very loose from 2' - 5'					
			2	10	3 13.0	
13-1 (L) 13-2 (T)	Fill, gray Silty SAND with Clay/Clayey SAND & Gravels, moist, medum dense	SM/SC	19		10.0	
			44	11	3 15.6	
13-3 (L)	Gray Silty SAND with Clay & Gravels, moist, medium dense	SM			10.0	
13-4 (L)	Gray Silty SAND with Clay, moist, medium dense	SM	33	11	5 13.3	
	Native, gray Silty, Clayey SAND/Silty fine Sand	sc	40	12	5 11.2	(13-5) Grain Size
13-5 (L)	with Clay (weathered Granite)					Analysis % Gravel = 2.6
13-6 (L)	Harder drilling @ 23 feet Gray granitic SAND, wet, very dense		56/2"			% Sand = 61.4 % Fines = 35.8
	Water at 26' at end of drilling Slow drilling from 25' to 27'	sc				
13-7 (T)	Gray granitic SAND with angular Gravel, wet, dense		41		15.1	
13-8 (T)	Boring terminated at 32.5 feet	-	50/4"		13.0	
			-			





ni findan	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer	p.c.f.	Moisture % dry wt.	MISC. LAB RESULTS
-	15-1 (L)	Fill Orange brown Silty SAND with Clay & Gravels, moist, loose	SM/SC	15 5				
	15-2 (T) 15-3 (L) 15-4 (T)	Fill Light brown (white) SAND, moist, medium dense	SP	45 29	1	10	12.9 17.4	Analysis % Gravel = 3,3
0	15-5 (T	Fill Mixed gray & orange Silty SAND with Clay & Gravels, moist	SM	24			12.6	% Sand = 66.0 % Fines = 30.7
5	15-6 (T)	Fill Mixed orange & gray brown Silty SAND, moist, medium dense - dense Native	SC	30			11.6	
0	15-7 (T	Gray Silty Clayey SAND, moist, medium dense		26			14.4	
5	15-8 (T)	Gray Silty SAND with Clay, moist, medium dense	SM	22			13.8	
)	15-9 (T)	Gray Silty SAND, moist, dense Boring terminated at 31.5 feet	SM	48				
5 -								


Перти, п.	Sample No. and type Symbol	SOIL DESCRIPTION	Unified Soil Classification	Blows/foot 350 ft - Ibs.	Qu - t.s.f. Penetrometer Dry Density	Moisture % dry wt.	MISC. LAB RESULTS
5	16-1 (L) 16-2 (T) 16-3 (L) 16-4 (T)	Fill Mixed gray Silty SAND with Gravel, moist, medium Fill(?) Orange gray Clayey SAND with Gravels, moist, medium dense	SM SC	28 22 41 27		13.0 13.2 12.8	Analysis % Gravel = 3.0 % Sand = 61.9 % Fines = 35.1 (16-3) Grain Size Analysis % Gravel= 0.9
0	16-5 (T)	Mixed orange & gray Clayey SAND with Gravel, moist, medium dense	25		13.3	% Sand = 58.8 % Fines = 40.3 (16-4) Atterberg Limits LL = 24.1% PL= 9%	
5	16-6 (T)	Mixed orange & gray Silty SAND, moist, medium dense		23		12.9	
0	16-7 (T)	Gray Silty CLAY with Sand, moist, medium dense Boring terminated at 21.5 feet	ML-CL	24			(16-7) Atterberg Limits II = 24.2% PI = 4,6% PL = 5%
D							
























Liquid Limit:	26.5
Plastic Limit:	22.7
Plasticity Index:	3.8
PI 4	




File N∘	SC 4090.1
Sample N∘	5-3-1
Date:	1/25/2017
By:	RC

	P.I. SOIL TEST			
	PLASTIC LIMIT			
Determination	1	2	3	4
Tare N∘	14	3	10	
Gross Wet WT.	13.57	15.32	16.70	
GrossDry WT.	13.10	14.54	15.56	
Tare WT.	11.07	11.19	11.02	
NET DRY WT.	2.03	3.35	4.54	0.00
WT. OF Water	0.47	0.78	1.14	0.00
% Moisture	23.15	23.28	25.11	#DIV/0!

LIQUID LIMIT						
NUMBER OF BLOWS						
35	28	28 23 17				
6e	4f	4f 5e 1c				
12.24	10.42	11.49				
10.80	9.20 11.52 9.76					
4.20	4.16	4.17	4.20			
6.60	5.04	7.35	5.56			
1.44	1.22	2.01	1.73			
21.82	24.21	27.35	31.12			



Sample #	5-3-1			
Ht. of Sample	bag			
Tare	4			
Gross Wet Wt	282.5			
Gross Dry Wt.	261.8			
Tare Wt.	109.8			
Net Dry Wt.	152.0			
Wt. Of Water	20.7			
% Moisture	13.6%			
Dry Density	#VALUE!			
Gold and I	Gold and Light Brown			
Elast	Elastic silt			
Group				
Symbol	SM			



Liquid Limit:	22.7
Plastic Limit:	15.8
Plasticity Index:	7.0
PI 7	



File N∘	SC 4090.1
Sample N∘	14-3-1
Date:	1/25/2018
By:	RC

14-3-1

6.0

14

921.5

816.6

109.6

707.0

104.9

14.8%


101.3


with Clay

SC

	P.I.	SOIL TES	г	
	PLASTIC LIMIT			
Determination	1	2	3	4
Tare N∘	22	31	12	
Gross Wet WT.	14.91	13.62	15.87	
GrossDry WT.	14.41	13.26	15.26	
Tare WT.	11.20	11.00	10.97	
NET DRY WT.	3.21	2.26	4.29	0.00
WT. OF Water	0.50	0.36	0.61	0.00
% Moisture	15.58	15.93	14.22	#DIV/0!

LIQUID LIMIT				
NUMBER OF BLOWS				
34	28	23	16	
1a	3c 5e 4e			
12.05	14.41	11.10	11.12	
10.77	12.58 9.82 9.66			
4.21	4.16	4.16	4.19	
6.56	8.42	5.66	5.47	
1.28	1.83	1.28	1.46	
19.51	21.73	22.61	26.69	








Liquid Limit:	24.1
Plastic Limit:	15.4
Plasticity Index:	8.7
PI 9	




File N∘	SC 4090
Sample N∘	16-4
Date:	2/1/2018
By:	RC

	P.I. SOIL TEST			
	PLASTIC LIMIT			
Determination	1	2	3	4
Tare N∘	26	31	22	
Gross Wet WT.	14.92	16.02	17.48	
GrossDry WT.	14.39	15.36	16.64	
Tare WT.	11.00	10.98	11.19	
NET DRY WT.	3.39	4.38	5.45	0.00
WT. OF Water	0.53	0.66	0.84	0.00
% Moisture	15.63	15.07	15.41	#DIV/0!

LIQUID LIMIT						
	NUM	1BER OF BLC	OWS			
33	27 21 15					
4e	5b	3e	5g			
14.24	12.21	16.41	16.15			
12.48	10.70 13.93 13.5					
4.19	4.18	4.28	4.17			
8.29	6.52	9.65	9.38			
1.76	1.51	2.48	2.60			
21.23	23.16	25.70	27.72			





Sample #	
Ht. of Sample	bag
Tare	200
Gross Wet Wt	808.3
Gross Dry Wt.	725.9
Tare Wt.	81.2
Net Dry Wt.	644.7
Wt. Of Water	82.4
% Moisture	12.8%
Dry Density	#VALUE!
Descr	iption:
olive	brown
Sandy I	ean Clay
Group	
Symbol	SC


Liquid Limit:	24.2
Plastic Limit:	19.4
Plasticity Index:	4.8
PI 5	




File N∘	SC 4090
Sample N∘	16-7
Date:	2/1/2018
By:	RC


	P.I. SOIL TEST				
	ŀ	PLASTIC LI	MIT		
Determination	1	2	3	4	
Tare N∘	16	12	27		
Gross Wet WT.	13.71	14.87	15.49		
GrossDry WT.	13.28	14.22	14.78		
Tare WT.	10.99	10.96	11.09		
NET DRY WT.	2.29	3.26	3.69	0.00	
WT. OF Water	0.43	0.65	0.71	0.00	
% Moisture	18.78	19.94	19.24	#DIV/0!	


LIQUID LIMIT						
	NUM	1BER OF BLC	OWS			
33	27 22 15					
4e	5b	3e	5g			
14.24	12.21	16.41	16.15			
12.48	10.70	.70 13.93 13.55				
4.19	4.18	4.28	4.17			
8.29	6.52	9.65	9.38			
1.76	1.51	2.48	2.60			
21.23	23.16	25.70	27.72			








Sample #	
Ht. of Sample	bag
Tare	11
Gross Wet Wt	367.6
Gross Dry Wt.	339.8
Tare Wt.	110.4
Net Dry Wt.	229.4
Wt. Of Water	27.8
% Moisture	12.1%
Dry Density	#VALUE!
Descr	iption:
Dark	Grey
Sandy I	ean Clay
Group	
Symbol	CL-ML








































APPENDIX B

Lyon Tank Slide 3D Orthographical Model (Figures 54 – 58)






PREPARED BY PAUL JENSEN PROFESSIONAL LAND SURVEYOR # 4627 SANTA CRUZ, CALIFORNIA


FIGURE NO. 54


TOPOGRAPHIC MAP


1"=20'

OF THE LANDS OF SAN LORENZO VALLEY WATER DISTRICT LYON WATER TREATMENT PLANT 365 MADRONE DRIVE BOULDER CREEK, CALIFORNIA APN 081-011-07 OCTOBER, 2017










APPENDIX C


Summary Results of Stability Analysis (Figures 59 – 71)




48				
44			1	
-0 	 			
8		 		· · · · · · · · · · · · · · · · · · ·
2		 		
2				
8				
4		 		
0	 	 and and and and and and and and and and		
		and the second s		
2			1	
8				
4	 			1
*		-		
0	 1	 		
16	 	1		
				11
2		 	5 M	
99				11
	 		-	1 in
4		 		
0		2		

E3 PROFILE

840			
			1
836			
832			
828			
824			
820			
816			
812			
808		ļ	
804			
800			
796			
			4.15



 -	CROSS	SECTION	PER	FEBRU	JAR
 =	CROSS	SECTION	PER	JUNE	03





ARY 25, 2017 SURVEY


)3, 2017 SURVEY


CROSS SECTIONS


OF THE LANDS OF SAN LORENZO VALLEY WATER DISTRICT LYON WATER TREATMENT PLANT 365 MADRONE DRIVE BOULDER CREEK, CALIFORNIA APN 081-011-07 JUNE, 2017



































APPENDIX D


Secant Wall Site Plan (Figure 72)

Culvert Site Plan (Figure 73)


Proposed Culvert Limits (Figure 74)

Secant Wall Option (Figure 75)

Culvert Buttress with Secant Walls (Figure 76)







(E) ADALINA SUDENCE

PROPOSED CULVERT LIMITS					
LYON TANK, 350 MADRONE DRIVE					
BOULDER CREEK, CALIFORNIA					
SAN LORENZO VALLEY WATER DISTRICT					
SCALE:	1" = 20'				
DRAWN BY:	AJB				
DATE:	JUNE 2019	HARO, KASUNICH & ASSOCIATES, INC. GEOTECHNICAL AND COASTAL ENGINEERS			
REVISED:					
		116 E. LAKE AVENUE, WATSONVILI	E, CA 95076		
JOB NO.	SC4090.3	(831) 722-4175			
FIGURE NO. 74			SHEET NO.		





FIGURE NO	O. 75	SHEET NO.
DRAWN BY: AJB DATE: JUNE 2019 REVISED: JOB NO. SC4090.3	HARO, KASUNICH & ASSOC GEOTECHNICAL AND COASTAL 116 E. LAKE AVENUE, WATSONVILLI (831) 722-4175	ENGINEERS
E	SECANT WALL OPTION YON TANK, 350 MADRONE DRIV BOULDER CREEK, CALIFORNIA ORENZO VALLEY WATER DIST	
(P) SECANT F	PILES	
2+50	3	740
(P)	PILE	770
HESSEYCREEK	/	- 780
23 FT		
		800
		- 810
		- 820
		- 830
		850
		860



	860
	850
	840
	830
	820
NT	810
40 FT CHANNEL	800
MITS OF GRADING	790
	780
(P) 8 FT CULVERT ALONG CREEK PROFILE	770
~	760
	750
2+50 3+0	740 20
Culvert Buttress with Secant Walls	6
LYON TANK, 350 MADRONE DRIVE BOULDER CREEK, CALIFORNIA SAN LORENZO VALLEY WATER DISTRIC	ст
SCALE: 1" = 20'	
DRAWN BY: AJB DATE: JUNE 2019 REVISED: INFORMATION CONSTAL EN 116 E. LAKE AVENUE, WATSONVILLE, C	IGINEERS
JOB NO. SC4090.3 (831) 722-4175	ET NO.
FIGURE NO. 76	

APPENDIX E

Some Photos From The Project Site

















